

GEOLOGY • UPPER SIXTH

UPPER SIXTH — GEOLOGY

CHAPTER 1

STRATIGRAPHY

SUGGESTED TIME: 22 PERIODS

IN THIS CHAPTER

This chapter equips students with the fundamental tools of stratigraphy: principles, the geologic time scale, dating techniques, contact relationships, event sequencing, and correlation methods. Mastery of these concepts is essential for interpreting sedimentary basins and succeeding in the GCE Advanced Level Geology examination.

- Define the scope and importance of stratigraphy in geological investigations.
- State and apply the fundamental principles of stratigraphy (superposition, original horizontality, lateral continuity, cross-cutting relationships, faunal succession).
- Construct and interpret the geologic time scale, distinguishing eons, eras, periods, epochs, and ages.
- Explain the principles, applications, and limitations of relative and absolute dating methods.
- Calculate ages using radiometric decay equations and interpret isotopic data.
- Identify and classify stratigraphic contacts (conformable, unconformable, disconformity, angular unconformity, nonconformity).



DOWNLOAD ON- BUCH

Free • Google Play
AI tutor, past papers,
results



GO ONBUCH+

All signed courses, unlimited AI
tutor, PDF sheets — OnBuch+
tab in the app

THIS SIGNED COURSE CONTAINS

COURSE

complete, illustrated,
step by step

METHODS

and worked examples

EXERCISES

exam style + solutions

SUMMARY SHEET

the essentials to
remember



Signed • OnBuch+

ONBUCH+ TEACHING TEAM
FOLLOWS THE OFFICIAL MINESEC SYLLABUS

OnBuch+

CONTENTS

- | | |
|---|--|
| 1. 1. Introduction & Scope of Stratigraphy | 8. 8. Correlation of Stratigraphic Successions |
| 2. 2. Fundamental Stratigraphic Principles | 9. 9. Integration, Revision & Exam Practice |
| 3. 3. The Geologic Time Scale | 10. Integration activity |
| 4. 4. Overview of Dating Methods | 11. Methods and worked examples |
| 5. 5. Radiometric Dating in Detail | 12. Exercises |
| 6. 6. Stratigraphic Contacts and Unconformities | 13. Solutions to the exercises |
| 7. 7. Sequencing Geologic Events | 14. Summary sheet |

CHAPTER OBJECTIVES

- Define the scope and importance of stratigraphy in geological investigations.
- State and apply the fundamental principles of stratigraphy (superposition, original horizontality, lateral continuity, cross-cutting relationships, faunal succession).
- Construct and interpret the geologic time scale, distinguishing eons, eras, periods, epochs, and ages.
- Explain the principles, applications, and limitations of relative and absolute dating methods.
- Calculate ages using radiometric decay equations and interpret isotopic data.
- Identify and classify stratigraphic contacts (conformable, unconformable, disconformity, angular unconformity, nonconformity).
- Reconstruct a sequence of geologic events from a cross-section or outcrop description.
- Correlate lithostratigraphic, biostratigraphic, and chronostratigraphic units across different localities.
- Integrate multiple stratigraphic datasets to solve a realistic geological problem.
- Apply stratigraphic reasoning to answer GCE-style structured and essay questions.

PREREQUISITES

- Basic rock classification (igneous, sedimentary, metamorphic) from Lower Sixth.
- Understanding of sedimentary processes and depositional environments.
- Fundamentals of radioactive decay and half-life from chemistry/physics.
- Map reading and cross-section construction skills.
- Familiarity with fossil identification and index fossil concept.

1 INTRODUCTION & SCOPE OF STRATIGRAPHY

EXPERIMENT The geologist's puzzle

Imagine you are a geologist hired by a mining company in the Adamawa region to locate a new bauxite deposit. The only clues are the layered rocks exposed along a river cut. How would you read the Earth's history written in those layers to predict where the ore lies? You notice a thick reddish layer at the bottom, a grey fossil-bearing layer above it, and a pale sandy layer at the top. Which layer is the oldest? What environment did each layer form in? And in which layer should you dig for bauxite, which forms by intense tropical weathering of older rocks? Every one of these questions can be answered — but only if you master the science that reads rock layers the way a historian reads the pages of a book. That science is **stratigraphy**, and it is the foundation upon which the whole of historical geology is built.

The problem posed above is the central problem of this chapter: given a stack of rock layers, how do we establish their order, their ages, their environments of formation, and their economic potential? By the end of this section you will know what stratigraphy is, how it is subdivided, how it was born, and why it is indispensable to geologists in Cameroon and worldwide.

1.1 What is Stratigraphy?

When you walk along the road cuts between Bafoussam and Bamenda, or along the sea cliffs near Limbe, you see that rocks are not random: they occur in layers, called **strata** (singular: stratum). These layers are pages of an archive. Each layer records the conditions — river, sea, desert, volcano — that existed when it was deposited. Stratigraphy is the science of reading that archive.

DEFINITION Stratigraphy

Stratigraphy (from Latin stratum, “layer”, and Greek graphein, “to write/describe”) is the branch of geology concerned with the order, relative position, description, age determination and correlation of rock layers (strata), and with the interpretation of the geological history they record.

Notice the five verbs hidden in this definition: to order strata, to position them, to describe them, to date them, and to correlate them (match them from place to place). Each of these tasks corresponds to a subdivision of stratigraphy.

DEFINITION Subdivisions of stratigraphy

- **Lithostratigraphy**: the classification of strata into units based on their physical rock characters (lithology, texture, colour, mineral composition), independent of age or fossils. Its basic unit is the **formation**.
- **Biostratigraphy**: the classification and correlation of strata based on their fossil content. Its basic unit is the **biozone** (or simply zone).
- **Chronostratigraphy**: the classification of strata into units that represent rocks formed during a specific interval of geologic time. Its units (e.g. **system**, **series**, **stage**) are bodies of rock with time significance.
- **Magnetostratigraphy**: the classification and correlation of strata based on the record of past reversals of the Earth's magnetic field preserved in the rocks (remanent magnetism).

WARNING Do not confuse rock units with time units


A very common GCE mistake is to mix up lithostratigraphic units (rock bodies: group, formation, member, bed) with chronostratigraphic units (rock bodies defined by time: system, series, stage) and with geologic-time units (pure time: period, epoch, age). Remember: a formation is a mappable rock body; a system is the rock record of a period. You may walk on the Cretaceous System, but you live in the Holocene Epoch. A formation can be diachronous — deposited at different times in different places — whereas a stage boundary is, by definition, the same age everywhere.

1.2 The Hierarchy of Lithostratigraphic Units

Because rock bodies occur at many scales, lithostratigraphy organises them into a hierarchy, from the thinnest distinguishable layer to vast complexes of related strata.

DEFINITION Lithostratigraphic hierarchy

- **Bed**: the smallest formal unit; a single distinguishable layer (e.g. one sandstone bed).
- **Member**: a subdivision of a formation with a distinct lithology.
- **Formation**: the fundamental unit; a body of rock homogeneous enough to be mapped at surface or traced in the subsurface. Formations are named after a geographic locality (e.g. a formation named after a town near its type section).
- **Group**: two or more adjacent, genetically related formations.
- **Supergroup**: an assemblage of related groups.



Hierarchy of lithostratigraphic units: each unit nests inside the next larger one, from the individual bed up to the supergroup.

1.3 Historical Development of Stratigraphy

Stratigraphy did not appear overnight; it grew from simple observations into a rigorous, internationally codified science.

Nicolas Steno (1669). Working in Italy, the Danish physician Nicolas Steno (Niels Stensen) studied the layered rocks of Tuscany and stated the three founding principles of stratigraphy: the **law of superposition** (younger layers lie on older ones), the **principle of original horizontality** (layers are deposited flat), and the **principle of lateral continuity** (layers extend sideways until they thin out or meet a barrier). We shall study these in detail in Section 2.

PROPERTY Law of Superposition (Steno, 1669)


In an undeformed sequence of sedimentary (or layered volcanic) rocks, each layer is older than the layer above it and younger than the layer below it: the oldest layers are at the bottom, the youngest at the top. This law gives relative ages only, not numerical ages. (Its justification by simple reasoning about deposition is examinable: sediments can only settle on top of a pre-existing surface.)

William Smith (1815). The English canal engineer William “Strata” Smith noticed that the same rock layers, exposed in different parts of England, always contained the same assemblages of fossils, and always occurred in the same order. From this he formulated the **principle of faunal succession** and, in 1815, published the first geological map of an entire country (England and Wales). His discovery made it possible to correlate strata across long distances — the birth of biostratigraphy.

Charles Lyell (1830–1833). In his *Principles of Geology*, Lyell championed **uniformitarianism**: the idea that the slow processes we observe today (erosion, sedimentation, volcanism) op-

erated in the same way through the past, so “the present is the key to the past”. This justified interpreting ancient strata by comparison with modern environments, and implied that Earth history was immensely long.

Modern stratigraphic codes. During the twentieth century, stratigraphy became codified and international. National and international stratigraphic codes fixed the rules for naming and defining units (type sections, priority of names). Today the **International Commission on Stratigraphy** (ICS), a body of the International Union of Geological Sciences (IUGS), coordinates the definition of global chronostratigraphic boundaries and publishes the **International Chronostratigraphic Chart**, the official framework of geologic time used by geologists worldwide. Each boundary is fixed at a physical reference point in a rock section called a **GSSP** (Global Boundary Stratotype Section and Point), informally a “golden spike”.



Timeline of the major historical milestones in the development of stratigraphy.

DID YOU KNOW?

Stratigraphy beneath our feet in Cameroon

Cameroon’s sedimentary basins — the Douala/Kribi–Campo basin in the south and the Logone Birni basin in the far north — were unravelled by stratigraphy. Oil exploration in the Rio del Rey basin depends on correlating sandstone reservoir formations and shale seals from well to well, exactly the lithostratigraphic and biostratigraphic reasoning you are learning here. Even the volcanic rocks of the Cameroon Volcanic Line are dated and ordered using stratigraphic principles combined with radiometric dating.

1.4 Why Stratigraphy Matters

Stratigraphy is not an academic luxury; it is a working tool with direct economic and scientific value.

- **Resource exploration.** Oil, gas, coal, bauxite, iron, limestone and groundwater all occur in specific layers. Stratigraphy tells the explorer which layer to target and where that layer continues underground. Our Adamawa bauxite, for example, forms as a weathering horizon on older rocks: finding the right ancient land surface (a stratigraphic contact) is the key to the ore.
- **Basin analysis.** Sedimentary basins (like the Douala basin) fill with strata that record subsidence, sea-level changes and sediment supply. Reading this fill lets geologists recon-

struct the basin's history and predict where reservoir rocks, source rocks and seals lie — the essence of petroleum geology.

- **Palaeoenvironmental reconstruction.** Fossils and sedimentary structures in strata reveal past climates, seas, rivers and deserts. Stratigraphy turns a cliff face into a history book of environments, and provides the framework for dating past events — including climate changes relevant to our own future.

1.5 Reading a Stratigraphic Column

The standard document of stratigraphy is the **stratigraphic column**: a vertical drawing of the succession of layers, oldest at the bottom, with thicknesses to scale, standard symbols for rock types, colours, and fossil content.

METHOD How to read a stratigraphic column legend

1. Start at the bottom: by superposition, this is the oldest unit.
2. Read the lithology symbols: brick pattern for limestone, dots for sandstone, dashes for shale, triangles or “v” shapes for volcanic rocks. Check the legend first — symbols vary between authors.
3. Read the thickness scale: the vertical axis is drawn to scale (e.g. 1 cm = 10 m), so you can measure true bed thicknesses.
4. Note the colours: colours usually follow international convention (e.g. blue tones for marine limestones, yellow for sandstones) but always confirm with the legend.
5. Identify fossils and ages written beside the column: these give the biostratigraphic and chronostratigraphic framework.
6. Mark the contacts between units: sharp, gradational, or wavy (unconformity) lines — they will be studied in Section 6.

WORKED EXAMPLE 1 Reading a river-cut section

Statement. In a river cut in the Adamawa region, a geologist observes from bottom to top: (A) 5 m of grey shale with marine shells; (B) 3 m of cross-bedded sandstone; (C) 2 m of red lateritic horizon rich in aluminium oxides. (1) Place the units in chronological order. (2) Which subdivision(s) of stratigraphy are used to order the units, and which to interpret their environments? (3) Where should the mining company sample for bauxite?

SOLUTION

Solution.

1. By the law of superposition, the undeformed sequence is oldest at the bottom: A (shale) → B (sandstone) → C (laterite). Chronological order of formation: A, then B, then C.
2. Lithostratigraphy is used to describe and order the rock units (shale, sandstone, laterite as distinct beds/formations). The marine shells allow biostratigraphy (fossil-based dating and correlation). Environmental interpretation (marine shale, fluvial or coastal sandstone, tropical weathering surface) uses sedimentology together with the stratigraphic framework.
3. Bauxite forms by intense tropical weathering, so the target is unit C, the lateritic horizon — and, crucially, the company should trace this horizon laterally (principle of lateral continuity) to find where it thickens into an economic deposit.

KEY POINTS Key points of Section 1

- Stratigraphy is the science of the order, position, description, dating and correlation of rock layers.
- Its main subdivisions are lithostratigraphy (rock character), biostratigraphy (fossils), chronostratigraphy (time-rock units) and magnetostratigraphy (magnetic reversals).
- Lithostratigraphic hierarchy: bed → member → formation (fundamental unit) → group → supergroup.
- Founders: Steno (superposition, 1669), Smith (faunal succession, 1815), Lyell (uniformitarianism, 1830s); today the ICS maintains the International Chronostratigraphic Chart.
- Stratigraphy underpins resource exploration, basin analysis and palaeoenvironmental reconstruction.
- Never confuse lithostratigraphic units (rocks) with chronostratigraphic units (time-rock) or geologic-time units (pure time).

EXERCISE 1 Check your understanding

1. Define stratigraphy and name its four subdivisions, giving the basis of classification of each.
2. A student writes: “The Cretaceous formation contains many fossils.” Identify and correct the terminological error.

3. Explain why the formation is called the fundamental lithostratigraphic unit.
4. State the law of superposition and give the condition under which it may fail.

SOLUTION Exercise 1

1. Stratigraphy is the branch of geology dealing with the order, relative position, description, dating and correlation of strata. Subdivisions: lithostratigraphy (rock character), biostratigraphy (fossil content), chronostratigraphy (time interval of formation), magnetostratigraphy (magnetic reversal record).
2. “Cretaceous” is a chronostratigraphic/time term (System/Period), not a lithostratigraphic one. Correct: “The Cretaceous System contains many fossils” or “The formation, dated as Cretaceous, contains many fossils”.
3. Because it is the smallest unit that is homogeneous and distinct enough to be mapped and traced in the field; members and beds are its subdivisions, groups its assemblages.
4. In an undeformed sequence, each bed is younger than the one below and older than the one above. It fails where strata have been overturned by folding or thrusting; younging indicators (graded bedding, cross-bedding, mud cracks) must then be used.

2 FUNDAMENTAL STRATIGRAPHIC PRINCIPLES

In the previous section we defined stratigraphy as the science of layered rocks and saw that its ultimate goal is to reconstruct the history of the Earth from the rock record. But how can a geologist, standing in front of a road cut near Bafoussam or a cliff on the flanks of Mount Cameroon, read that history? The answer lies in a small set of remarkably powerful principles, most of them established between the 17th and 19th centuries by pioneers such as Nicolaus Steno, James Hutton and William Smith. These principles are the grammar of stratigraphy: once you master them, any outcrop becomes a readable text. In this section we state each principle rigorously, justify it, illustrate it, and learn to apply it.

2.1 Principle of Original Horizontality

Intuition. Pour a bucket of sand into a basin of water and watch it settle: it forms a flat, horizontal layer. Sediments deposited under gravity behave the same way, whether in the ocean, a lake such as Lake Nyos, or a river floodplain in the Benue trough.

DEFINITION Principle of Original Horizontality (Steno, 1669)

Layers of sediment are originally deposited in a horizontal or near-horizontal position, because deposition is controlled by gravity. Consequently, any sedimentary succession that is today tilted, folded or overturned must have been deformed after deposition.

This simple idea has an enormous consequence: **tilted strata are evidence of a tectonic event younger than the strata themselves**. When you see the steeply dipping sandstones around the Benue trough, you immediately know that compressional tectonics affected the region after the sediments were laid down.

WARNING Exceptions to strict horizontality

Two situations produce beds that were never perfectly horizontal:

- **Depositional (primary) dip**: cross-bedding in dunes and deltas, and the slopes of reef mounds or volcano flanks, can reach 30° or more. These dips are primary and do not indicate tectonism.
- **Heavily deformed terranes**: in strongly folded or thrust regions, beds may be vertical or overturned. Never assume horizontality there without a structural analysis (way-up criteria such as graded bedding, mud cracks, ripple marks).

2.2 Principle of Lateral Continuity and Facies Changes

Intuition. Imagine a layer of mud deposited on the floor of a wide lagoon. If a valley is later eroded through the lagoon, the mud layer appears on both valley walls. You do not need to see the layer continuously to know the two outcrops were once connected.

DEFINITION Principle of Lateral Continuity

A sedimentary layer extends laterally in all directions until it thins out (pinches out) at the edge of the depositional basin, or until it passes laterally into a different sediment type (a **facies change**) where the depositional environment changed.

The notion of **facies** is essential: at any one time, different sediments accumulate side by side — sand near a shore, mud offshore, limestone on a clear-water platform. A single time plane therefore cuts across several rock types, and a single rock type can be of different ages in different places (the facies is said to be diachronous when it migrates with time, e.g. during a marine transgression).

WARNING Common mistake

Do not correlate two beds simply because they have the same lithology (e.g. two sandstones). A beach sand is young near the present shore and older inland after a transgression. Lithology alone is not a time marker.

2.3 Principle of Cross-Cutting Relationships

Intuition. To slice a cake, the cake must already exist. Likewise, a feature that cuts across rocks must be younger than the rocks it cuts.

PROPERTY Principle of Cross-Cutting Relationships

Any geological feature (igneous intrusion, fault, mineral vein, erosional surface) that cuts across another rock body or structure is younger than everything it cuts. Conversely, a rock body is older than any feature that cuts it. The proof is direct observation of geometric relations at the contact; it is examinable as a reasoning exercise on a cross-section.

Typical applications:

- A basaltic **dyke** cutting gneisses of the Congo craton is younger than the gneisses.
- A **fault** displacing sedimentary beds is younger than the youngest bed it offsets.
- A quartz **vein** cross-cutting a granite post-dates the granite.

If a dyke is truncated by a fault, the dyke is older than the fault: the principle applies recursively and allows a complete relative chronology to be built.

2.4 Principle of Faunal Succession and Index Fossils

Intuition. William Smith, surveying canal cuttings in England around 1800, noticed that each layer contained a characteristic assemblage of fossils, and that these assemblages always succeeded one another in the same order, wherever he looked. Life evolves and never repeats itself; therefore fossil content is a clock.

DEFINITION Principle of Faunal Succession

Fossil organisms succeed one another through time in a definite, irreversible order. Each interval of geological time is characterised by a distinctive fossil assemblage, so strata containing the same assemblage can be recognised and correlated from one region to another.

DEFINITION Index fossil

An **index fossil** is a fossil that is ideal for dating and correlating rocks because it combines three qualities:

1. Wide geographic distribution — it can be found in many regions;
2. Narrow time range — the species lived for a short interval only;
3. Easy identification — it is abundant, well preserved and distinctive.

Classic examples: ammonites (Mesozoic), trilobites (Palaeozoic), graptolites (Ordovician–Silurian), foraminifera (Cenozoic).

2.5 Principle of Inclusions and Baked Contacts


Intuition. If you find pebbles of granite inside a conglomerate, the granite must have existed, been eroded and fragmented before the conglomerate formed. Fragments are always older than the rock that contains them.

DEFINITION Principle of Inclusions


Fragments (**inclusions**) of one rock contained within another rock are older than the enclosing rock. This applies to pebbles in conglomerates, xenoliths in granites, and clasts in volcanic breccias.

A related field criterion is the **baked contact**: where hot magma intrudes cold country rock, the surrounding rock is thermally metamorphosed (“baked”) over a contact aureole. A baked margin on the country rock proves the intrusion is younger; conversely, if pebbles of an already-baked rock occur in an overlying conglomerate, the intrusion is older than the conglomerate. These two criteria together let you distinguish an intrusive contact from a depositional one.

2.6 Synthetic Illustration: the Five Principles on One Cross-Section




(a) Horizontality



(b) Pinch-out



(c) Dyke (younger)



(d) Faunal succession

The fundamental principles at a glance: (a) originally horizontal beds; (b) lateral continuity ending in a pinch-out; (c) a cross-cutting dyke younger than the host beds; (d) an ordered succession of fossil assemblages.

2.7 Worked Example: Interpreting an Outcrop Sketch

WORKED EXAMPLE 2 Reading a simple outcrop

A road cut shows, from bottom to top: (i) folded schists; (ii) a horizontal conglomerate containing pebbles of schist and of a granite; (iii) horizontal sandstone beds with ammonites; (iv) a basalt dyke cutting the conglomerate and the sandstone but stopping at the top of the sandstone; (v) a soil cover. Establish the relative chronology.

SOLUTION

Solution. Apply the principles one by one:

1. Schists: the oldest unit present. Their folding (deformation) is younger than the schists but older than everything that lies undeformed above (original horizontality).
2. Conglomerate: rests on the eroded schists (an unconformity). By the principle of inclusions, the schist and granite pebbles are older than the conglomerate; the granite therefore existed and was exposed at the surface before conglomerate deposition.
3. Sandstone with ammonites: younger than the conglomerate (superposition) and Mesozoic in character (faunal succession, ammonites as index fossils).
4. Basalt dyke: by cross-cutting relationships, it is younger than the conglomerate and the sandstone. Since it does not cut the soil, it is older than the soil.
5. Soil: youngest feature.

Chronology (oldest → youngest): schists → folding and erosion → granite (existed before conglomerate) → conglomerate → sandstone → basalt dyke → soil.

2.8 Method: a Checklist for Any Unknown Outcrop

METHOD Applying the five principles systematically

1. List the units and features: beds, intrusions, faults, veins, erosion surfaces.
2. Check way-up and horizontality: are beds horizontal, tilted or overturned? Look for graded bedding or mud cracks.
3. Apply superposition and lateral continuity: order the undisturbed beds from oldest (bottom) to youngest (top); trace each bed laterally and note pinch-outs and facies changes.
4. Apply inclusions: any fragments (pebbles, xenoliths) are older than their host rock.
5. Apply cross-cutting relationships: every dyke, fault or vein is younger than what it

cuts; rank several cutting features by who cuts whom.

6. Use fossils: identify index fossils to assign relative ages and to correlate with other sections.
7. Write the full chronology from oldest to youngest, stating the principle used at each step.

WARNING Horizontality trap

In heavily deformed terranes (e.g. the Pan-African belts of northern Cameroon), beds may be vertical or upside down. Never apply superposition blindly: first establish the younging direction with sedimentary way-up criteria. Assuming horizontality without structural analysis is one of the most frequent causes of inverted chronologies in the GCE practical paper.

KEY POINTS Key points

- Sediments are deposited horizontally; tilted beds record later tectonism.
- Beds extend laterally until they pinch out or change facies; lithology alone is not a time marker.
- Whatever cuts is younger; whatever is included is older.
- Fossil assemblages succeed in a fixed order; index fossils (wide distribution, short range, easy identification) date and correlate strata.
- Baked contacts prove an intrusion post-dates its country rock.
- Combine all five principles, in the checklist order, to decode any outcrop.

EXERCISE 2 Outcrop chronology

A cliff section shows limestone beds (with trilobites) cut by a dolerite dyke; the dyke and the limestone are both truncated by an erosion surface overlain by a conglomerate containing dolerite pebbles; a fault cuts the limestone and the dyke but not the conglomerate. Establish the complete relative chronology, justifying each step with the appropriate principle.

SOLUTION Exercise 1

Oldest → youngest: limestone (base of the exposed succession; trilobites indicate Palaeozoic) → dolerite dyke (cross-cuts the limestone, so younger) → fault (cuts limestone and dyke, so younger than both) → erosion surface (truncates dyke and fault, so younger still) → conglomerate (lies above the erosion surface; its dolerite pebbles confirm, by the principle of inclusions, that the dyke existed and was eroded before conglomerate deposition). Note the double proof that the dyke is older than the conglomerate: the dyke is truncated by the erosion surface and its pebbles occur in the conglomerate.

3 THE GEOLOGIC TIME SCALE

In the previous section we established the fundamental principles of stratigraphy — superposition, horizontality, lateral continuity, cross-cutting relationships, faunal succession. These principles allow us to place rocks and events in relative order: bed A is older than bed B, fault F is younger than both. But a relative order is not enough. To communicate globally, geologists need a standard calendar of Earth history: a single, internationally agreed framework in which every slice of time has a name, a rank and a numerical age. That framework is the **Geologic Time Scale** (GTS). It is the single most frequently examined diagram in the whole GCE Advanced Level Geology paper, and mastering it is non-negotiable.

3.1 From Relative Order to a Global Calendar

Imagine the history of Cameroon written without any dates: “the German period came before the French mandate, which came before independence.” The order is correct, but you could not say how long each episode lasted or when exactly it began. Stratigraphy faced exactly this problem in the nineteenth century. Geologists could stack strata in order, but they needed named compartments of time.

The solution was to divide the rock record into packages bounded by worldwide recognisable events — typically mass extinctions or abrupt faunal changes — and to give each package a name. Later (twentieth century), radiometric dating attached numerical ages to the boundaries. The modern GTS is therefore a hybrid: its compartments are defined by rocks and fossils, and its boundary ages are calibrated by isotopic dating.

KEY POINTS Two linked hierarchies

There are always two parallel scales:

- **Chronostratigraphic** (bodies of rock): Eonothem → Erathem → System → Series → Stage.
- **Geochronologic** (intervals of time): Eon → Era → Period → Epoch → Age.

Rocks belong to a System; time belongs to a Period. We say “the Jurassic Period” (time) but “the Jurassic System” (the rocks deposited during it).

WARNING Period, System, Series — do not mix the ranks

A classic GCE trap: candidates write “the Cretaceous Series” when they mean the whole Cretaceous time interval. Series is the chronostratigraphic rank below System (equivalent to an Epoch in time), e.g. the Upper Cretaceous Series. Period (time) and System (rock) are equivalent in rank but used in different contexts. Rule of thumb: time words (Period, Epoch, Age) answer “when?”; rock words (System, Series, Stage) answer “which rocks?”.

3.2 The Structure of the Scale: Eons to Ages

The scale is a nested hierarchy, like a set of boxes within boxes:

Rank (time)	Typical duration	Example
Eon	Hundreds of Ma to ~2 Ga	Phanerozoic
Era	Tens to hundreds of Ma	Mesozoic
Period	Tens of Ma	Jurassic
Epoch	A few to tens of Ma	Pleistocene
Age	~1 Ma or less	Calabrian

EXAMPLE Zooming into one address

Just as a letter addressed to a student in Buea reads Cameroon → South-West Region → Fako Division → Buea, a fossil ammonite might be “addressed” in time as: Phanerozoic Eon → Mesozoic Era → Cretaceous Period → Late Cretaceous Epoch → Campanian Age. Each rank narrows the interval. For the GCE you must know the scale down to Period (with Cenozoic Epochs as a bonus).

3.3 The Precambrian: Hadean, Archean, Proterozoic

Nearly **88%** of Earth history precedes the Cambrian. This vast interval, formerly lumped as “the Precambrian”, is now formally divided:

- **Hadean** Eon (4 567–4 000 Ma): from the formation of the Earth (about 4.57 Ga) to the oldest preserved rocks. Intense meteorite bombardment, magma ocean, formation of the first crust and oceans. No formal rock record — hence the name, from Hades.
- **Archean** Eon (4 000–2 500 Ma): oldest continental crust (cratons), first undisputed life (prokary-

otes, stromatolites). The Congo craton, which underlies much of southern Cameroon, contains Archean rocks.

- **Proterozoic** Eon (2 500–541 Ma): oxygenation of the atmosphere, first eukaryotes, then multicellular (Ediacaran) life; ends with the appearance of abundant shelly fossils that marks the Cambrian. The Proterozoic is subdivided into three eras (Paleoproterozoic, Mesoproterozoic, Neoproterozoic) but knowledge of these subdivisions is not required for the GCE examination.

PROPERTY The Great Oxidation Event (GOE)

Around 2.4–2.3 Ga (early Proterozoic), photosynthetic cyanobacteria raised atmospheric O₂ dramatically. Geological evidence: banded iron formations (BIFs) stop forming in abundance as dissolved iron was oxidised and precipitated, and red beds (continental sediments stained by iron oxides) appear. The GOE made aerobic life — and ultimately animals — possible. (Its causes and timing are discussed qualitatively at GCE level; no numerical derivation is examinable.)

WARNING “Precambrian” is informal

“Precambrian” is a convenient informal term for everything before 541 Ma, but it is not a formal unit. In an exam answer, name the formal eons: Hadean, Archean, Proterozoic. Also note the Archean–Proterozoic boundary is fixed chronometrically at 2 500 Ma, not by a fossil event.

3.4 The Phanerozoic: Eras, Periods and Numerical Ages

The **Phanerozoic** Eon (“visible life”, 541 Ma to present) is divided into three eras, separated by the two greatest mass extinctions:

- **Paleozoic** (541–252 Ma): “ancient life”. Cambrian explosion of shelly faunas; Ordovician radiation; Silurian colonisation of land by plants; Devonian “age of fishes” and first forests; Carboniferous coal swamps; Permian supercontinent Pangaea. Ends with the **Permian–Triassic extinction** (~252 Ma), the largest known, wiping out most marine species.
- **Mesozoic** (252–66 Ma): “middle life”, the age of reptiles. Triassic recovery and first dinosaurs and mammals; Jurassic giant dinosaurs and first birds; Cretaceous flowering plants and chalk seas. Ends with the **Cretaceous–Paleogene (K/Pg) extinction** at **66.0 Ma** — an asteroid impact plus massive volcanism — which eliminated non-avian dinosaurs and ammonites.
- **Cenozoic** (66 Ma–present): “recent life”, the age of mammals and birds. Divided into Paleogene, Neogene and Quaternary periods, with epochs (Paleocene, Eocene, Oligocene, Miocene, Pliocene, Pleistocene, Holocene). The Holocene began ~11 700 years ago after the last ice age.


Period	Base age (Ma)	Key milestone
Quaternary	2.58	Ice ages; humans
Neogene	23.0	Grasslands, hominids
Paleogene	66.0	Mammal radiation after K/Pg
Cretaceous	145	Flowering plants; ends 66.0 Ma
Jurassic	201	Dinosaurs dominant; first birds
Triassic	252	Recovery; first dinosaurs, mammals
Permian	299	Pangaea; ends in greatest extinction
Carboniferous	359	Coal forests, first reptiles
Devonian	419	Fishes, first forests & tetrapods
Silurian	444	Land plants, jawed fish
Ordovician	485	Marine radiation
Cambrian	541	Explosion of shelly life

METHOD Mnemonic for the order of periods

Learn the Phanerozoic periods in order (oldest → youngest) with:

“Camels Often Sit Down Carefully; Perhaps Their Joints Creak — Pretty Nasty Quakes”

Cambrian, Ordovician, Silurian, Devonian, Carboniferous, Permian, Triassic, Jurassic, Cretaceous, Paleogene, Neogene, Quaternary. Recite it until automatic — a mis-ordered time scale loses marks instantly.



Phanerozoic time scale drawn to scale: each bar runs from the present back to the base age of the period. Note how the Cretaceous (~79 Myr) dwarfs the Quaternary (~2.6 Myr) — a common exam point.

WARNING Reading the chart correctly

Two frequent errors: (1) assuming all periods have equal duration — they do not; the Cretaceous lasted about 79 Myr, the Silurian only about 25 Myr; (2) forgetting that larger Ma numbers are older. The base of the Cambrian (541 Ma) is older than the base of the Triassic (252 Ma).

3.5 GSSPs: The “Golden Spikes”

How is a boundary made official? Not by vote alone, but by choosing one physical reference point in one rock section on Earth.


DEFINITION GSSP – Global Boundary Stratotype Section and Point

A **GSSP** is an internationally agreed reference point within a specific, continuously deposited rock section that defines the lower boundary of a chronostratigraphic unit (Stage, Series, System). It is popularly called a **golden spike** because geologists symbolically drive a marker into the outcrop. The boundary is defined by a primary marker —

usually the first appearance of a fossil species, a magnetic reversal, or a geochemical signal — and all sections worldwide are then correlated to it.

EXAMPLE Famous GSSPs

- Base of the Cambrian (541 Ma): Fortune Head, Newfoundland (Canada); marked by the first appearance of the trace fossil *Treptichnus pedum*.
- Cretaceous–Paleogene boundary (66.0 Ma): El Kef, Tunisia; marked by a global iridium anomaly and shocked quartz from the Chicxulub impact.
- Base of the Quaternary (2.58 Ma): Monte San Nicola, Sicily; marked by a marine climate (glacial) signal.



A GSSP “golden spike”: the boundary between two Systems is fixed at a precise point in a continuous section, defined by a primary marker (e.g. a fossil first appearance).

PROPERTY The time scale is a living document

The GTS is continuously refined by the International Commission on Stratigraphy (ICS) as dating improves: boundary ages are revised (e.g. the K/Pg boundary is now placed at 66.0 Ma, not 65.5 Ma as in older books). For exams, always use the latest ICS values given in your syllabus or question paper, and quote ages to the precision taught (whole Ma for the GCE). This property is not examinable as a proof, but quoting an outdated age can cost marks.

DID YOU KNOW? Cameroon on the time scale

Cameroon displays rocks from across the scale: Archean–Proterozoic basement of the Congo craton in the south, Cretaceous sediments of the Benue trough in the north, and Cenozoic volcanics of the Cameroon Volcanic Line, including Mount Cameroon — whose eruptions (e.g. 1999, 2000) are events of the Holocene, the youngest Age of the youngest Epoch. Lake Nyos, site of the 1986 gas disaster, occupies a young volcanic maar on this same line.

3.6 Reading and Constructing a Time–Scale Chart for the Exam

METHOD Constructing a simplified time scale

1. Draw a vertical bar; mark the present (0 Ma) at the top and 4 600 Ma at the bottom.
2. Mark the three great divides: 2 500 Ma (Archean/Proterozoic), 541 Ma (Precambrian/Cambrian = base of Phanerozoic), 252 Ma (Paleozoic/Mesozoic), 66 Ma (Mesozoic/Cenozoic).
3. Subdivide the Phanerozoic into the 12 periods using the mnemonic; add base ages from the table above.
4. Check proportions: the Precambrian must occupy about 88% of the bar — if your Phanerozoic looks half the chart, it is wrong.

WORKED EXAMPLE 3 Placing events on the time scale

Statement: A trilobite-bearing shale in the Benue region is dated at 470 Ma. (a) To which eon, era and period does it belong? (b) A basalt of the Cameroon Volcanic Line is dated at 30 Ma. Which era and period? (c) Which rock is older, and by how much?

SOLUTION

Solution.

- (a) 470 Ma lies between 485 and 444 Ma $\Rightarrow$ Ordovician Period, Paleozoic Era, Phanerozoic Eon. (Consistent with trilobites, typical Paleozoic fossils.)
- (b) 30 Ma lies between 66 and 23 Ma $\Rightarrow$ Paleogene Period, Cenozoic Era.
- (c) The shale is older: $470 - 30 = 440$ Myr older.

Method: always locate the age between two boundary values from the table, then read off period, era, eon.

EXERCISE 3 Time-scale practice

(a) Give the full “time address” (eon, era, period) of a dinosaur bone dated at 100 Ma and of a stromatolite dated at 2 000 Ma. (b) State the numerical ages of the two great mass-extinction boundaries. (c) Why is the base of the Cambrian defined by a trace fossil rather than a numerical age alone?

SOLUTION Exercise 1

(a) 100 Ma: between 145 and 66 Ma $\Rightarrow$ Cretaceous Period, Mesozoic Era, Phanerozoic Eon. 2 000 Ma: between 2 500 and 541 Ma $\Rightarrow$ Proterozoic Eon (subdivided into Paleoproterozoic, Mesoproterozoic, Neoproterozoic eras, but not required at this level). (b) Permian–Triassic at 252 Ma; Cretaceous–Paleogene at 66.0 Ma. (c) Because the GSSP concept defines boundaries by a physical, correlatable event in a rock section (first appearance of *Treptichnus pedum*); the numerical age (541 Ma) is a secondary, revisable calibration obtained by radiometric dating, whereas the golden spike is permanent.

KEY POINTS Key points of Section 3

- Hierarchy: Eon $\rightarrow$ Era $\rightarrow$ Period $\rightarrow$ Epoch $\rightarrow$ Age (time); System $\rightarrow$ Series $\rightarrow$ Stage (rock).
- Precambrian = Hadean + Archean + Proterozoic (~88% of history); GOE at ~2.4 Ga.
- Learn the four anchor ages: 541, 252, 66.0 Ma and 2 500 Ma; then the 12 period bases.
- Boundaries are defined by GSSPs (“golden spikes”), calibrated numerically by radiometric dating.
- Use the latest ICS ages; larger Ma = older.

4**OVERVIEW OF DATING METHODS**

In the previous section we built the **geologic time scale**: a ladder of eons, eras, periods and epochs whose rungs were first defined by relative criteria (superposition, fossils) and later calibrated in millions of years. But where do those numbers — 66 Ma for the end of the dinosaurs, 541 Ma for the base of the Cambrian — actually come from? To answer that question we must now look at the toolbox of the geologist: the family of **dating methods**. This section gives you the map of that toolbox; the next section will zoom into radiometric dating, the most powerful tool of all.

4.1 Relative versus Absolute Dating

Imagine you find two old photographs of the town of Buea. In the first, the mountain road is unpaved; in the second, it is tarred. Even without any date written on the photos, you know which one is older: the unpaved road came first. That is **relative dating**: placing events in order. If, however, one photo carries the stamp “March 1978”, you have an **absolute** (or numerical) **age**: a number attached to a time scale.

DEFINITION Relative and absolute dating

Relative dating determines the order of geologic events (which rock, structure or fossil is older or younger) without giving an age in years. It rests on the stratigraphic principles (superposition, cross-cutting relationships, included fragments) and on fossil succession.

Absolute (numerical) dating assigns an age in years (ka = thousands of years, Ma = millions of years) to a rock, mineral or object, usually by measuring a physical or chemical “clock” such as the radioactive decay of an isotope.

WARNING A frequent confusion

“Absolute” does not mean “exact”. Every numerical age carries an uncertainty. An age of 125.3 ± 0.7 Ma is absolute but not exact; a relative statement (“the lava flow is younger than the sandstone it crosses”) can be perfectly certain. Precision and certainty are different things.

4.2 Relative Dating Techniques

Beyond the basic principles of Steno and the cross-cutting rules, modern stratigraphy has developed several specialised relative-dating techniques. Each uses a different kind of “signal” recorded in the rocks.

1. Biostratigraphy. This is the oldest and still the most widely used technique. It exploits the law of faunal succession: fossil species appear and disappear in a definite, irreversible order. **Index fossils** — species that were widespread geographically but short-lived in time (many ammonites, graptolites, foraminifera) — allow beds to be placed in a **biozone** and correlated between distant outcrops. The Cretaceous limestones of the Douala and Rio del Rey basins, for example, are zoned using planktonic foraminifera.

2. Magnetostratigraphy. When lava cools or sediment settles, magnetic minerals (like magnetite) align with the Earth’s magnetic field and freeze its direction. The Earth’s field has reversed polarity many times (normal ↔ reversed). The resulting pattern of normal and reversed **magnetozones** in a succession is like a barcode: it can be matched to the global **Geomagnetic Polarity Time Scale** (GPTS). Magnetostratigraphy is especially powerful for dating the lava flows of the **Cameroon Volcanic Line** and for correlating deep-sea sediment cores.

3. Chemostratigraphy. The chemical and isotopic composition of seawater has varied through time (e.g. the ratios $^{87}\text{Sr}/^{86}\text{Sr}$ and $\delta^{13}\text{C}$ recorded in marine carbonates). A measured curve of

isotope values through a succession can be matched to the global reference curve, giving relative ages — very useful in rocks without fossils, such as some Precambrian carbonates of the Congo craton margin.

4. Sequence stratigraphy. Sea-level rises and falls leave characteristic packages of sediment (**sequences**) bounded by erosion surfaces (**sequence boundaries**). Because major sea-level changes are often global (eustatic), sequence boundaries can be approximately synchronous and serve as correlation horizons between basins — a technique heavily used in petroleum exploration of the Rio del Rey and Douala basins.

Technique	Signal used	Best suited to
Biostratigraphy	Index fossils, biozones	Fossiliferous sedimentary rocks
Magnetostratigraphy	Polarity reversals	Lavas, fine sediments, any age
Chemostratigraphy	Isotope / element curves	Marine carbonates, barren rocks
Sequence stratigraphy	Sea-level cycles, boundaries	Basin-fill sedimentary successions

KEY POINTS Relative dating in one sentence

All relative techniques answer the question “older or younger than what?” — they order events and correlate rocks, but only an absolute clock can say “how many years ago?”.

4.3 Families of Absolute Dating Methods

Absolute clocks fall into four main families. You should know what each measures and over what time range it works.

1. Radiometric dating (parent–daughter decay). A radioactive **parent** isotope decays at a constant rate (half-life $T_{1/2}$) into a stable **daughter** isotope. Measuring the parent/daughter ratio in a mineral gives the time elapsed since the system closed. Examples: K–Ar and $^{40}\text{Ar}/^{39}\text{Ar}$ (volcanic rocks), U–Pb on zircon (very old rocks), Rb–Sr, Sm–Nd, U-series (e.g. U–Th for carbonates up to ~500 ka), and ^{14}C for young organic material. Range: from a few thousand years (^{14}C) to the age of the Earth (U–Pb). This family is treated in detail in Section 5.

2. Luminescence dating (OSL, TL). Quartz and feldspar grains buried in sediment trap electrons in crystal defects, accumulating energy from natural radioactivity. Exposure to light (or heat) “resets” the clock. Measuring the stored luminescence gives the time since the grains were last exposed to sunlight — i.e. since burial. Range: roughly 100 years to ~300 ka. Ideal for dating dunes, river terraces and archaeological sediments that contain no dateable volcanic material.

3. Cosmogenic nuclide dating. Cosmic rays striking rocks at the Earth’s surface produce rare isotopes such as ^{10}Be and ^{26}Al in situ. Their concentration measures how long a surface (a moraine, a lava flow top, an exposed fault scarp) has been exposed to the sky. Range: roughly 10^3 to a few 10^6 years. Useful for landscape evolution, e.g. exposure ages of young flows on Mount Cameroon.

4. Dendrochronology (tree-ring dating). Counting annual growth rings of trees gives exact calendar ages, but only back a few thousand years (about 12 ka with overlapping sequences). Its great geological role is to calibrate the radiocarbon clock.

DID YOU KNOW? Dating the Cameroon Volcanic Line

The volcanoes of the Cameroon Volcanic Line, from Mount Cameroon on the coast to the Adamawa plateau, have been dated mainly by the K–Ar and $^{40}\text{Ar}/^{39}\text{Ar}$ methods on feldspar and whole-rock samples. These ages show that volcanic activity has occurred along the line for tens of millions of years, with Mount Cameroon remaining active today — it erupted several times during the 20th century.

4.4 Closure Temperature: When the Clock Starts Ticking

Here is the key intuition. A radiometric clock does not date the moment a mineral formed in a deep magma chamber; it dates the moment the mineral became a closed box for parent and daughter atoms. While the rock is hot, atoms (especially argon, a gas) can diffuse in and out of the crystal, so no daughter product accumulates. Only when the rock cools enough does the mineral trap its daughter atoms, and the clock starts.

DEFINITION Closure temperature

The **closure temperature** (T_c) of an isotopic system in a given mineral is the temperature below which that mineral becomes a closed system: parent and daughter isotopes can no longer escape or enter by diffusion, so the daughter product begins to accumulate and the radiometric clock starts.

Different systems have different closure temperatures. Approximate values (worth knowing as orders of magnitude):

System / mineral	Typical use	T_c (approx.)
U–Pb in zircon	Crystallisation of granites, very old rocks	> 900 °C
K–Ar / Ar–Ar in hornblende	Cooling of deep crustal rocks	~ 500 °C
K–Ar / Ar–Ar in biotite	Later cooling stages	~ 300 °C
Fission track in apatite	Near-surface cooling, uplift	~ 110 °C

Two consequences follow. First, a single granite can yield different ages from different minerals — not an error, but a cooling history: the zircon records crystallisation, the biotite records later cooling. Second, if a rock is reheated above T_c during a later metamorphic event, the clock is reset (daughter products escape) and the measured age dates the reheating, not the original formation.

PROPERTY The closed-system assumption


A radiometric age is only as reliable as the assumption that the system remained closed: no parent or daughter isotope was added or lost since closure, and the initial daughter content is known or negligible. Weathering, metamorphism or fluid circulation that opens the system produces ages that are too young, too old, or geologically meaningless. (The mathematical treatment of this assumption is examinable in Section 5.)

4.5 Choosing the Right Dating Method

No single method dates everything. The geologist must match the method to the sample, asking four questions:

METHOD Selecting a dating method

1. What is the rock type? Igneous rocks → radiometric (K–Ar, U–Pb). Sedimentary rocks can rarely be dated directly → date bracketing lava flows or ash beds, or use luminescence on the sediment itself. Metamorphic rocks → systems with high T_c (U–Pb, Sm–Nd).
2. What is the expected age? Younger than ~50 ka with organic matter → ^{14}C . Thousands to hundreds of ka → luminescence, U-series, Ar–Ar. Millions to billions of years → K–Ar, U–Pb, Rb–Sr.
3. Which minerals are available? No zircon → no U–Pb. No K-bearing mineral → no K–Ar. No quartz/feldspar → no OSL.
4. What precision is required? $^{40}\text{Ar}/^{39}\text{Ar}$ and U–Pb give the best analytical precision; choose the system whose uncertainty is small compared with the age differences you need to resolve.



Decision tree for selecting an absolute dating method from sample characteristics (simplified).

4.6 Reporting an Age with its Uncertainty

A measurement without an uncertainty is scientifically useless. Analytical results are always reported as an age plus or minus an uncertainty at a stated confidence level.

METHOD How to report an age

1. Give the central value and the uncertainty with the same number of decimal places: 125.3 ± 0.7 Ma.
2. State the confidence level: “2σ” means there is about a 95% probability that the true age lies within the interval; “1σ” corresponds to about 68%.
3. State the method and the mineral dated: e.g. “⁴⁰Ar/³⁹Ar on hornblende”.
4. Interpret the result: here the true age lies, with ~95% confidence, between 124.6 and 126.0 Ma (Early Cretaceous).

WARNING The carbon–14 trap

¹⁴C has a half-life of only about 5 730 years. After roughly 8–9 half-lives (~50 ka) so little ¹⁴C remains that ages become unreliable. Never use carbon-14 to date a dinosaur bone (66 Ma old), a granite, or any rock: it works only on organic material younger than about 50 000 years. This is a classic GCE trap.

WORKED EXAMPLE 4 Choosing a method for a Cameroonian basalt

Statement. A geologist collects a fresh basalt flow from the flank of Mount Cameroon. Field relations show it overlies a soil containing charcoal. She wishes to date the eruption. (a) Which absolute method(s) could date the basalt itself? (b) Which method could date the buried soil? (c) Why would ^{14}C be unsuitable for the basalt?

SOLUTION

Solution.

- (a) The basalt is an igneous rock containing K-bearing minerals (feldspar, glass): the K–Ar or $^{40}\text{Ar}/^{39}\text{Ar}$ method is appropriate. The clock started when the lava cooled below the closure temperature of argon in those minerals — essentially the eruption date.
- (b) The soil contains charcoal (organic carbon). If the eruption is younger than ~50 ka, radiocarbon (^{14}C) dating of the charcoal gives the age of the soil just before burial — a maximum age for the flow. If no charcoal were present, OSL on buried quartz grains could date the soil's last exposure to sunlight.
- (c) Basalt contains no organic carbon: ^{14}C dating measures the decay of carbon incorporated by living organisms. Moreover, if the flow were older than ~50 ka, essentially all ^{14}C would have decayed anyway. Carbon-14 can never date a rock directly.

EXERCISE 4 Matching methods to samples

For each sample, propose the most suitable dating method and justify your choice in one sentence: (1) a zircon-bearing granite from the Precambrian basement north of Yaoundé; (2) a sand dune estimated at 20 000 years old, with no fossils; (3) a fossilised tree trunk from a Miocene lignite; (4) a Holocene lava flow of the Cameroon Volcanic Line.

SOLUTION Exercise 1

1. U–Pb on zircon: very old rock, and zircon's very high closure temperature preserves the crystallisation age even through later events.
2. OSL (luminescence): quartz grains in the dune record time since burial; the age (20 ka) fits the OSL range, and no organic matter is needed.
3. No direct method is ideal: the trunk is Miocene (millions of years), far beyond ^{14}C ; one must date bracketing volcanic ash beds by K–Ar/Ar–Ar, or correlate the lignite biostratigraphically.
4. $^{40}\text{Ar}/^{39}\text{Ar}$ (or K–Ar) on the lava: it dates cooling of the flow; charcoal beneath it could

be cross-checked by ^{14}C if younger than 50 ka.

KEY POINTS Key points of this section

- Relative dating orders events (biostratigraphy, magnetostratigraphy, chemostratigraphy, sequence stratigraphy); absolute dating gives ages in years.
- The four absolute families are radiometric, luminescence, cosmogenic nuclides and dendrochronology, each with its own age range and target material.
- The closure temperature defines when a mineral's isotopic clock starts; reheating can reset it.
- A radiometric age is valid only if the system stayed closed.
- Always report an age with its uncertainty (e.g. $125.3 \pm 0.7 \text{ Ma}$, 2σ) — and never use ^{14}C beyond ~50 ka or on rocks.

5 RADIOMETRIC DATING IN DETAIL

In the previous section we surveyed the landscape of dating methods and saw that radiometric dating is the only family of techniques capable of giving us absolute ages in millions of years. We now open the hood of this remarkable engine. Our guiding question is simple: how can a handful of atoms inside a mineral grain tell us that a granite cooled 500 million years ago? The answer rests on one of the most reliable clocks in nature — the spontaneous, unchanging decay of radioactive isotopes.

5.1 The Radioactive Decay Law and Half-Life

Intuition first. Imagine a very large bag of popcorn placed over a fire. You cannot predict which kernel will pop next, but you can predict with great confidence that about half of the kernels will have popped after a certain time. Radioactive atoms behave exactly like this: each unstable (parent) nucleus has a fixed probability of decaying per unit time into a stable (daughter) nucleus, and this probability is unaffected by temperature, pressure, or chemical bonds. That is what makes radioactivity a trustworthy clock — no geological furnace or deep burial can speed it up or slow it down.

DEFINITION Radioactive decay and the decay constant

Radioactive decay is the spontaneous transformation of an unstable parent isotope (P) into a daughter isotope (D), often with emission of particles or radiation. The **decay con-**

stant λ is the probability that a given nucleus decays per unit time; it is characteristic of each isotopic system.

Because every nucleus decays independently with the same probability, the number of parent atoms N decreases in proportion to the number remaining:

$$\frac{dN}{dt} = -\lambda N$$

Integrating from an initial quantity N_0 at $t = 0$ gives the **decay law**:

PROPERTY Radioactive decay law

$$N = N_0 e^{-\lambda t}$$

where N is the number of parent atoms remaining after time t , N_0 the initial number, and λ the decay constant (in yr^{-1} or Ma^{-1}). The derivation by separation of variables is examinable.

The **half-life** $t_{1/2}$ is the time needed for half of the parent atoms to decay. Setting $N = N_0/2$:

$$\frac{N_0}{2} = N_0 e^{-\lambda t_{1/2}} \implies \ln \frac{1}{2} = -\lambda t_{1/2} \implies t_{1/2} = \frac{\ln 2}{\lambda} \approx \frac{0.693}{\lambda}$$

Since a geologist measures the ratio of daughter to parent rather than N_0 , we rewrite the law in a practical form. The daughter produced is $D^* = N_0 - N = N(e^{\lambda t} - 1)$, so:

$$\frac{D^*}{N} = e^{\lambda t} - 1 \implies t = \frac{1}{\lambda} \ln \left(1 + \frac{D^*}{N} \right)$$

This is the master equation of radiometric dating: measure the daughter-to-parent ratio today, know λ , and the age t falls out.

WARNING Half-life is not "half the age"

A very common mistake is to think that after one half-life the clock is "half used up" and after two half-lives it is finished. In fact the parent decreases exponentially: after two half-lives one quarter remains, after three one eighth, and so on — the parent never mathematically reaches zero. Also, $t_{1/2}$ is a constant of the isotope; it does not depend on how much material you have.

5.2 The Major Isotopic Systems

Nature offers several parent-daughter pairs, each with its own half-life, suitable minerals, and

geological niche. A good geochronologist chooses the system the way a mechanic chooses a spanner — the right tool for the job.

System	Decay	Half-life / typical minerals	Best used for
U–Pb	$^{238}\text{U} \longrightarrow ^{206}\text{Pb}$; $^{235}\text{U} \longrightarrow ^{207}\text{Pb}$	$t_{1/2}$: 4 468 Ma and 704 Ma; zircon, monazite, apatite	Very old rocks; the gold standard for Precambrian terranes
K–Ar / Ar–Ar	$^{40}\text{K} \longrightarrow ^{40}\text{Ar}$	$t_{1/2} = 1250$ Ma; micas, K-feldspar, hornblende	Volcanic rocks (e.g. Mount Cameroon lavas), cooling ages
Rb–Sr	$^{87}\text{Rb} \longrightarrow ^{87}\text{Sr}$	$t_{1/2} \approx 48\,800$ Ma; micas, K-feldspar, whole rocks	Ancient granites and metamorphic suites; isochron dating
Sm–Nd	$^{147}\text{Sm} \longrightarrow ^{143}\text{Nd}$	$t_{1/2} \approx 106\,000$ Ma; garnet, pyroxenes, whole rocks	Mafic/ultramafic rocks; crustal residence ages
Lu–Hf	$^{176}\text{Lu} \longrightarrow ^{176}\text{Hf}$	$t_{1/2} \approx 37\,000$ Ma; garnet, zircon	Garnet-bearing metamorphic rocks; crust evolution
Re–Os	$^{187}\text{Re} \longrightarrow ^{187}\text{Os}$	$t_{1/2} \approx 41\,600$ Ma; sulphides, organic-rich shales	Ore deposits, mantle rocks, black shales

DID YOU KNOW? Dating the Cameroon Volcanic Line

The volcanic mounts of the Cameroon Volcanic Line — from Mount Cameroon on the coast to the Adamawa plateau — have been dated largely by the **K–Ar** and **Ar–Ar** methods, because young basaltic lavas contain potassium-bearing minerals and glass that trap argon well. These ages revealed that the line became progressively active over tens of millions of years, with Mount Cameroon remaining active to the present day.

5.3 The Isochron Method: Eliminating the Unknown Initial Daughter

The problem. Our master equation assumes that all the daughter isotope present today was produced by decay. But when a mineral crystallises, it usually already contains some daughter isotope — the initial daughter D_0 . If we ignore it, we overestimate the age. The isochron method is the elegant graphical solution.

Take the Rb–Sr system. ^{87}Rb decays to ^{87}Sr , and we normalise everything by the stable, non-radiogenic isotope ^{86}Sr :

$$\left(\frac{{}^{87}\text{Sr}}{{}^{86}\text{Sr}}\right)_{\text{today}} = \left(\frac{{}^{87}\text{Sr}}{{}^{86}\text{Sr}}\right)_0 + \left(\frac{{}^{87}\text{Rb}}{{}^{86}\text{Sr}}\right)_{\text{today}} (e^{\lambda t} - 1)$$

This is the equation of a straight line $y = b + mx$ where $y = {}^{87}\text{Sr}/{}^{86}\text{Sr}$, $x = {}^{87}\text{Rb}/{}^{86}\text{Sr}$, the intercept b is the initial ratio, and the slope is $m = e^{\lambda t} - 1$.

DEFINITION Isochron

An **isochron** is a straight line on an isotope–ratio diagram (e.g. ${}^{87}\text{Sr}/{}^{86}\text{Sr}$ versus ${}^{87}\text{Rb}/{}^{86}\text{Sr}$) along which all points correspond to samples of the same age that shared the same initial daughter isotope ratio.

PROPERTY Slope of the isochron


The slope of an isochron equals

$$m = e^{\lambda t} - 1 \quad \Rightarrow \quad t = \frac{1}{\lambda} \ln(1 + m).$$

The y-intercept gives the initial daughter ratio $({}^{87}\text{Sr}/{}^{86}\text{Sr})_0$ — a bonus piece of petroge-
netic information. No proof is required at GCE level, but you must be able to use the rela-
tion.

METHOD Constructing and reading a Rb–Sr isochron

1. Collect several cogenetic samples (different minerals or whole rocks from the same intrusion).
2. Measure ${}^{87}\text{Rb}/{}^{86}\text{Sr}$ (x-axis) and ${}^{87}\text{Sr}/{}^{86}\text{Sr}$ (y-axis) for each.
3. Plot the points; if they fall on a straight line, the system stayed closed — the line is an isochron.
4. Measure the slope m from the graph, then compute $t = \frac{1}{\lambda} \ln(1 + m)$.
5. Read the initial ratio from the y-intercept.



Schematic Rb–Sr isochron diagram. Cogenetic samples define a straight line whose slope gives the age and whose intercept gives the initial strontium isotope ratio.

5.4 The Concordia–Discordia Diagram for U–Pb Zircons


Uranium–lead dating enjoys a unique privilege: it contains two independent clocks in the same mineral, $^{238}\text{U} \longrightarrow ^{206}\text{Pb}$ and $^{235}\text{U} \longrightarrow ^{207}\text{Pb}$. If a zircon has remained a perfectly closed system since crystallisation, both clocks must give the same age — the ages are concordant.

DEFINITION Concordia

The **Concordia** is the theoretical curve on a plot of $^{206}\text{Pb}/^{238}\text{U}$ (y-axis) versus $^{207}\text{Pb}/^{235}\text{U}$ (x-axis) along which the two U–Pb ages agree exactly. Each point on the curve corresponds to one specific age.

Real zircons often lose some of their radiogenic lead (for example during a later heating event). Lead loss moves a data point off the Concordia, and a suite of zircons that all suffered the same disturbance plot along a straight line called the **Discordia**. The Discordia intersects the Concordia at two points:

- the **upper intercept** gives the crystallisation age of the zircons;
- the **lower intercept** approximates the age of the disturbance (the lead-loss event).



Concordia-Discordia diagram. Undisturbed zircons lie on the Concordia; lead loss displaces analyses along the Discordia, whose intercepts date the crystallisation and the later disturbance.

WARNING Always check concordance

Always check for concordance between the $^{238}\text{U}/^{206}\text{Pb}$ and $^{235}\text{U}/^{207}\text{Pb}$ ages before accepting a U-Pb result. If the two ages disagree (the point lies off the Concordia), the system has been disturbed and a single "age" is meaningless — you must use the Discordia intercepts instead.

5.5 Common Sources of Error

Radiometric dating is powerful but not magical. The examiner expects you to know the four classic pitfalls:

- **Lead loss (U-Pb):** Pb is a relatively mobile element; metamorphic heating can expel part of the accumulated ^{206}Pb and ^{207}Pb , giving discordant, too-young ages. Detected by the Concordia diagram.
- **Inheritance:** a zircon crystal may grow around an older core (inherited from the source rock or an earlier crystal). Dating a mixed grain yields a spurious intermediate age. Modern practice dates single growth zones.
- **Metamorphic resetting:** during a strong metamorphic event, isotopic clocks (especially K-Ar and Rb-Sr) may be partially or wholly reset, so the measured age records the metamorphism, not the original crystallisation.
- **Excess argon (K-Ar, Ar-Ar):** sometimes ^{40}Ar from surrounding fluids is trapped in the min-

eral at crystallisation. This "excess argon" mimics radiogenic argon and produces ages that are too old — a notorious problem in very young volcanic rocks.

WARNING Closed system assumption

Every radiometric age assumes the mineral behaved as a **closed system**: no parent or daughter entered or left after crystallisation (except by decay). Whenever you quote an age, ask yourself whether this assumption is defensible — this is exactly what examiners probe in essay questions.

5.6 Practice Calculation: Age of a Zircon from $^{238}\text{U}/^{206}\text{Pb}$

METHOD Age from a measured parent/daughter ratio

1. Write the decay law in daughter/parent form: $\frac{D^*}{N} = e^{\lambda t} - 1$.
2. Identify the measured ratio. If given $^{238}\text{U}/^{206}\text{Pb} = N/D^*$, invert it.
3. Compute $t = \frac{1}{\lambda} \ln\left(1 + \frac{D^*}{N}\right)$, using $\lambda = \frac{\ln 2}{t_{1/2}}$.
4. State the age with units (Ma) and comment on concordance if a second system is available.

WORKED EXAMPLE 5 Dating a zircon from a Cameroonian basement granite

A zircon extracted from a granite of the Precambrian basement north of the Benue trough yields a measured ratio $^{238}\text{U}/^{206}\text{Pb} = 12.0$. Take $t_{1/2}(^{238}\text{U}) = 4.468 \times 10^9 \text{ yr}$ and $\ln 2 = 0.693$. Calculate the age of the zircon, assuming no initial lead and a closed system.

SOLUTION

Step 1 — Decay constant:

$$\lambda = \frac{\ln 2}{t_{1/2}} = \frac{0.693}{4.468 \times 10^9 \text{ yr}} = 1.551 \times 10^{-10} \text{ yr}^{-1}.$$

Step 2 — Daughter/parent ratio:

$$\frac{D^*}{N} = \frac{^{206}\text{Pb}}{^{238}\text{U}} = \frac{1}{12.0} = 0.0833.$$

Step 3 — Age equation:

$$t = \frac{1}{\lambda} \ln\left(1 + \frac{D^*}{N}\right) = \frac{1}{1.551 \times 10^{-10}} \ln(1.0833).$$

Since $\ln(1.0833) = 0.0800$:

$$t = \frac{0.0800}{1.551 \times 10^{-10}} = 5.16 \times 10^8 \text{ yr} \approx 516 \text{ Ma.}$$

Conclusion: the zircon crystallised about 516 million years ago (early Palaeozoic, Cambrian). Before accepting the result, we would verify that the $^{235}\text{U}/^{207}\text{Pb}$ age is concordant.

EXERCISE 5 Check your mastery

A biotite from a schist gives a Rb–Sr isochron with slope $m = 0.0143$. Given $\lambda(^{87}\text{Rb}) = 1.42 \times 10^{-11} \text{ yr}^{-1}$, calculate the age of the rock. Then state two reasons why a K–Ar age on the same rock might come out younger.

SOLUTION Exercise 1

$t = \frac{1}{\lambda} \ln(1 + m) = \frac{\ln(1.0143)}{1.42 \times 10^{-11}} = \frac{0.0142}{1.42 \times 10^{-11}} = 1.0 \times 10^9 \text{ yr} = 1000 \text{ Ma}$. A K–Ar age could be younger because (i) metamorphic heating caused argon loss (partial resetting), or (ii) the K–Ar system records later cooling below the argon closure temperature rather than crystallisation.

KEY POINTS Key points of Section 5

- Decay law: $N = N_0 e^{-\lambda t}$; half-life $t_{1/2} = \ln 2 / \lambda$; practical form $t = \frac{1}{\lambda} \ln(1 + D^* / N)$.
- The **isochron** method removes the unknown initial daughter: slope = $e^{\lambda t} - 1$, intercept = initial ratio.
- U–Pb zircon dating is self-checking via the **Concordia**; disturbed samples define a **Discordia** whose upper intercept dates crystallisation.
- Beware lead loss, inheritance, metamorphic resetting and excess argon — all violate the closed-system assumption.

With the machinery of absolute dating now in hand, we are ready to examine what happens when rock successions meet: the stratigraphic contacts and unconformities that record gaps and dramas in Earth's history — the subject of the next section.

6 STRATIGRAPHIC CONTACTS AND UNCONFORMITIES

In the previous section, we saw how radiometric dating gives us absolute ages for rocks. But long before geologists could measure ages in millions of years, they could already read the relative history of a region simply by looking at how rock units touch one another. The surfaces that separate rock units — the **stratigraphic contacts** — are the punctuation marks of the stratigraphic record: some mark continuous, quiet deposition; others mark dramatic interruptions of uplift, folding and erosion. In this section we learn to recognise, classify and interpret these contacts, a skill that is systematically tested at the GCE Advanced Level, both in theory and in map- and section-based exercises.

6.1 What is a Stratigraphic Contact?

DEFINITION Stratigraphic contact

A **stratigraphic contact** is the surface that separates two distinct rock units (formations, members, or any mappable bodies of rock). It may correspond to a bedding plane, an erosional surface, or an intrusive or faulted boundary.

Think of a layered cake: the interface between two layers is a contact. If the baker poured the second layer immediately after the first, the interface is smooth and continuous — this is a **conformable** contact. If, instead, the first cake was sliced, tilted and partly eaten before the second layer was added, the interface records a gap in time and a period of disturbance — this is an **unconformable** contact.

Contacts are fundamental because they are the surfaces we trace on geological maps and the boundaries we measure in stratigraphic sections. Their nature (conformable or not) tells us whether deposition was continuous or interrupted.

6.2 Conformable Contacts

A contact is **conformable** when the strata above and below were deposited in an essentially continuous sequence, without significant erosion or interruption of sedimentation. Beds above and below are parallel, and palaeontological content shows a regular succession. Three varieties are distinguished:

- **Gradational contact:** one rock type passes progressively into the other (e.g. shale passing upward into siltstone then sandstone as the sea shallows). There is no single sharp surface; the boundary is placed by convention where a chosen lithological change occurs.
- **Sharp (abrupt) conformable contact:** lithology changes suddenly (e.g. limestone directly overlain by shale) but without any evidence of erosion or time gap. Such contacts reflect a rapid change in depositional conditions, for instance a sudden marine transgression.
- **Paraconformity:** a special case discussed below, in which the contact looks conformable (beds are parallel) but actually conceals a time gap.

WARNING Conformable does not always mean “no time gap”

A sharp conformable contact can look dramatic yet represent continuous deposition, while a perfectly parallel contact (paraconformity) can hide millions of years of non-deposition. Never judge a contact by its geometry alone: look for evidence of erosion or missing time.

6.3 Unconformities: Definition and Types

DEFINITION Unconformity

An **unconformity** is a surface of erosion or non-deposition that separates younger strata from older rocks and represents a significant **gap in the geological record** (a hiatus). It records an interval during which deposition stopped and/or previously deposited rocks were eroded.

Four main types are recognised, and you must be able to define, sketch and identify each of them.

DEFINITION Angular unconformity

An **angular unconformity** is an erosional surface on which younger, roughly horizontal strata rest upon older strata that have been tilted or folded and truncated by erosion. The beds above and below the surface are not parallel.

An angular unconformity records a full tectonic cycle: (1) deposition of the older sequence; (2) tectonic deformation (tilting/folding) and uplift; (3) erosion levelling the landscape; (4) subsidence and deposition of the younger sequence.

DEFINITION Disconformity

A **disconformity** is an unconformity in which the strata above and below the erosional surface are parallel, but the surface itself shows clear evidence of erosion (irregular topography, channels, basal conglomerate, paleosol). It records uplift and erosion without significant deformation.


DEFINITION Nonconformity

A **nonconformity** is an unconformity in which sedimentary strata rest directly on eroded

igneous or metamorphic (crystalline) basement. It records deep erosion that stripped away the cover rocks before renewed deposition. In Cameroon, sediments of the Douala basin resting on the Precambrian basement of the Congo craton illustrate this relationship.

PROPERTY The paraconformity: a hidden gap

A **paraconformity** is an unconformity in which the beds above and below are parallel and the surface shows no obvious erosional features; the time gap is detected mainly through a fossil (biostratigraphic) break — one or more biozones are missing between the two units. It typically records a long period of non-deposition (e.g. a submarine hiatus) rather than active erosion.



The four main types of unconformity (orange surface). (a) Angular unconformity: truncated tilted beds below. (b) Disconformity: parallel beds with an irregular erosional surface. (c) Nonconformity: sediments on eroded crystalline basement. (d) Paraconformity: parallel beds, no visible erosion; the gap is revealed by missing fossil zones.

6.4 Recognition Criteria in the Field and on Maps

How do we prove that a contact is an unconformity and not simply a facies change? We look for diagnostic evidence:

- **Basal conglomerate:** a conglomerate at the base of the younger unit containing pebbles derived from the underlying rocks — direct proof that the older unit was lithified and eroded before the younger one was deposited.
- **Paleosol (fossil soil):** a horizon of weathering, root traces or lateritic alteration just below the contact, proving exposure at the Earth's surface.
- **Truncation:** beds, folds, dykes or faults in the older unit are cut off by the contact surface; on a geological map, the contact cuts across the outcrop pattern of the older unit.
- **Fossil break:** missing biozones between the two units (the key criterion for a paraconformity).
- **Age gap:** radiometric or biostratigraphic ages show a hiatus between the two units.

- **Relief on the surface:** channels, potholes or an irregular, wavy geometry (disconformity).

METHOD Field checklist for identifying an unconformity

1. Locate the contact and describe its geometry: flat, wavy, channelled? Are beds above and below parallel?
2. Examine the base of the upper unit: search for a basal conglomerate; identify the pebbles — do they match the rocks below?
3. Examine the top of the lower unit: look for weathering, paleosol, root traces, iron staining.
4. Check for truncation: are beds, folds, dykes or faults below cut by the surface?
5. Sample for fossils above and below: is any biozone missing?
6. Classify the contact (angular unconformity, disconformity, nonconformity, paraconformity) and estimate the hiatus if ages are available.

WARNING Do not confuse a facies change with an unconformity

A lateral or vertical **facies change** (e.g. sandstone passing to shale) can produce a sharp contact with no time gap at all. Before calling a surface an unconformity, you must demonstrate erosion or non-deposition: basal conglomerate, paleosol, truncation, or a fossil/age gap. Sharpness of a contact alone proves nothing.

6.5 Significance of Unconformities

- **Basin history:** each unconformity records a tectonic event — uplift, deformation, sea-level fall. Counting and dating unconformities allows the geologist to reconstruct the subsidence/uplift history of a sedimentary basin and to subdivide the fill into sequences.
- **Missing record:** the hiatus means part of Earth history is simply absent at that locality; correlation with more complete sections elsewhere is needed.
- **Hydrocarbon traps:** unconformities are major exploration targets. Weathered rocks just below the surface are often porous (good reservoirs), while fine-grained sediments deposited above form a seal; truncation of tilted reservoir beds against the unconformity creates stratigraphic traps. Several traps of this type are known in the Rio del Rey and Douala basins of Cameroon.
- **Mineralisation and aquifers:** weathering profiles above unconformities can concentrate lateritic ores, and the permeable zone along the surface can channel groundwater.

DID YOU KNOW? Hutton's unconformity

The concept was born in 1788 when James Hutton, the father of modern geology, examined the outcrop at Siccar Point (Scotland), where near-horizontal Devonian sandstones rest on vertical Silurian greywackes. Hutton realised that an immense span of time — deposition, tilting, mountain building, erosion, then renewed deposition — was recorded in that single surface. This convinced him that the Earth was vastly older than commonly believed.

6.6 Sketching and Labelling Contacts on a Measured Section

In the GCE practical-style questions you may be asked to draw a stratigraphic column from field data. Proceed as follows:

METHOD Drawing a measured section with contacts

1. Draw a vertical axis with a scale (e.g. 1 cm = 10 m) and mark thicknesses upward from the base.
2. For each bed, draw a rectangle whose width is constant and whose height equals the bed thickness; ornament it with the standard lithological symbol (dots for sandstone, dashes for shale, bricks for limestone).
3. Draw each contact according to its nature: a simple line for a conformable contact; a bold wavy line for a disconformity; a bold line with truncated, differently oriented beds below for an angular unconformity.
4. Label each unit (name, lithology, thickness, age) and each contact (type of contact, evidence observed).
5. Add a title, scale and north/location information if it is a field section.

WORKED EXAMPLE 6 Interpreting a contact in the field

Statement. Along a road cut, a geologist observes horizontal red sandstones resting on steeply dipping grey shales. At the base of the sandstone there is a 30 cm bed of conglomerate whose pebbles are made of grey shale identical to that below. Fossils indicate that the shale is Ordovician and the sandstone is Cretaceous. (a) Name the type of contact. (b) List the evidence supporting your answer. (c) Reconstruct the geological history.

SOLUTION

Solution.

1. (a) The contact is an **angular unconformity**: the beds above (horizontal sandstone) and below (steeply dipping shale) are not parallel, and an erosional surface separates them.
2. (b) Evidence: (i) angular discordance between horizontal and dipping strata; (ii) truncation of the dipping shale beds by the contact; (iii) a basal conglomerate containing pebbles reworked from the underlying shale, proving the shale was lithified and eroded before sandstone deposition; (iv) a large time gap (Ordovician to Cretaceous) with missing systems.
3. (c) History: (1) deposition of the grey shales in the Ordovician; (2) tectonic deformation tilting the shales, with uplift; (3) prolonged erosion levelling the surface; (4) renewed deposition of red sandstones in the Cretaceous, beginning with a basal conglomerate.

EXERCISE 6 Classify and justify

For each situation, name the type of contact and justify: (1) horizontal Cenozoic sands resting on eroded Precambrian gneiss of the Congo craton; (2) parallel Cretaceous limestones and marls separated by a surface with a lateritic paleosol; (3) parallel Eocene and Oligocene shales with two missing planktonic foraminifera zones but no erosional feature.

SOLUTION Exercise 1

1. Nonconformity: sedimentary rocks rest on eroded crystalline (metamorphic) basement.
2. Disconformity: beds are parallel but the paleosol proves exposure and erosion/non-deposition.
3. Paraconformity: beds parallel, no erosional surface; the hiatus is revealed only by the missing fossil zones.

KEY POINTS Key points

- A **stratigraphic contact** separates two rock units; it is conformable (continuous deposition) or unconformable (hiatus).
- Four unconformity types: **angular unconformity** (tilted/folded beds below), **discon-**

formity (parallel beds, erosional surface), **nonconformity** (sediments on crystalline basement), **paraconformity** (parallel beds, gap shown only by fossils).

- Diagnostic evidence: basal conglomerate, paleosol, truncation, fossil/age gap.
- Unconformities record tectonic and sea-level events and can form stratigraphic hydrocarbon traps.
- Never call a contact an unconformity without evidence of erosion or non-deposition.

7 SEQUENCING GEOLOGIC EVENTS

In Section 6 we learned to recognise and interpret stratigraphic contacts — conformable surfaces, unconformities, intrusive contacts and fault contacts. Each contact, taken alone, tells us something about the order in which two rock bodies were emplaced. But real outcrops, and real GCE examination questions, rarely present a single contact: they present a puzzle in which sedimentation, folding, intrusion, erosion and faulting are all tangled together. The skill we now develop is the one that examiners reward most highly: reading a complex cross-section and reconstructing its **geologic history** — a complete, ordered narrative of events from oldest to youngest.

7.1 From contacts to chronology: the logic of relative dating

EXPERIMENT A roadside cutting near Bafoussam

Imagine a road cutting exposing, from bottom to top: folded schists, a granite that cuts across them, a horizontal sandstone resting on the eroded top of both, and a dolerite dyke that cuts the sandstone but stops at a fault which offsets everything. Even without a single numerical age, you can already say: the schists are oldest, the granite came next, then erosion, then the sandstone, then the dyke, then the fault. You have just built a relative chronology using nothing but the principles of superposition, cross-cutting relationships and unconformities.

The whole of this section rests on a small toolkit of principles already met in Sections 2 and 6, now applied simultaneously:

- **Superposition:** in an undisturbed sedimentary pile, the lowest bed is oldest.
- **Original horizontality:** tilted or folded strata were deposited flat, so deformation post-dates deposition.
- **Cross-cutting relationships:** whatever cuts (dyke, fault, vein) is younger than whatever is cut.

- **Unconformities:** an erosional surface separates older, deformed and eroded rocks below from younger rocks above.
- **Inclusions:** fragments enclosed in a rock are older than the rock containing them (e.g. schist xenoliths in granite).

PROPERTY Age of an intrusion

An intrusion is younger than all the rocks it cuts (cross-cutting) but older than all the rocks that overlie it unconformably or that contain its eroded pebbles. The same logic applies to faults and to any cross-cutting body. (Proof not examinable; the property follows directly from the cross-cutting and superposition principles.)

7.2 The Event List technique

Faced with a complicated section, students who “just look and guess” almost always miss an event or invert two of them. The rigorous approach is systematic.

METHOD The Event List technique


1. Inventory. List every observable feature on the section: each sedimentary unit, each fold, each intrusion, each fault, each unconformity (erosional surface). Give each a label (A, B, C...).
2. Local ordering. For each pair of features in contact, apply one principle to decide which is older. Write down the evidence (“dyke D cuts unit B $\Rightarrow$ D younger than B”).
3. Global ordering. Chain the local decisions into a single ordered list from oldest to youngest. Check for contradictions (e.g. a fault claimed to be both older and younger than the same unit).
4. Insert absolute ages. Where radiometric dates are given, place them in the list and use them to bracket the undated events.
5. Write the narrative. Convert the ordered list into a prose geologic history, oldest event first.

DEFINITION Bracketing age

The **bracketing age** of a rock unit or event is the age interval constrained by the age of the youngest dated unit below it (or cut by it) and the age of the oldest dated unit above it (or cutting it). The true age lies between the two bounds.

EXAMPLE Bracketing a lava flow

A basalt flow rests on sandstone dated by fossils to the Cretaceous and is overlain by a tuff dated radiometrically at 60 Ma. The basalt is therefore younger than Cretaceous and older than 60 Ma: its bracketing age is “Late Cretaceous to earliest Palaeogene”. Along the Cameroon Volcanic Line, lavas are commonly bracketed between dated flows above and below.

7.3 A multi-event cross-section

Multi-event cross-section for annotation. Events: deposition of A, folding of A, intrusion of granite B, erosion (unconformity U), deposition of C then D, intrusion of dyke E, faulting F.

WORKED EXAMPLE 7 Worked example: reading the cross-section

Using the cross-section above, establish the complete sequence of geologic events from oldest to youngest. Granite B is dated at 550 Ma and dyke E at 120 Ma. What is the bracketing age of the unconformity U and of the folding?

SOLUTION

Step 1 — Inventory. Features: folded strata A; granite B; unconformity U; sandstone C; limestone D; dyke E; fault F.

Step 2 — Local ordering.

- A is folded $\Rightarrow$ deposition of A, then folding (original horizontality).
- B cuts the folded fabric of A $\Rightarrow$ B is younger than A and younger than the folding.
- U truncates both A and B $\Rightarrow$ the erosion surface is younger than B.
- C and D overlie U $\Rightarrow$ C then D (superposition), both younger than U.
- E cuts C and D $\Rightarrow$ E younger than D.
- F offsets everything, including E $\Rightarrow$ F is the youngest event.

Step 3 — Ordered list (oldest → youngest): deposition of A → folding of A → intrusion of B (550 Ma) → uplift and erosion (U) → deposition of C → deposition of D → intrusion of E (120 Ma) → faulting F.

Step 4 — Bracketing. The folding affects A but predates B (550 Ma): folding is therefore older than 550 Ma (its lower bound is the undated age of A). The unconformity U post-dates B (550 Ma) and pre-dates C; if C is, say, fossil-dated to the Jurassic, then U is bracketed between 550 Ma and the Jurassic. The fault F is younger than 120 Ma because it offsets dyke E.

Step 5 — Narrative. “Sediments of unit A were deposited in horizontal layers, then compressed and folded. A granite magma (B) intruded the folded rocks at 550 Ma. The region was uplifted and deeply eroded, producing unconformity U. A marine transgression deposited sandstone C then limestone D. A dolerite dyke (E) intruded at 120 Ma, and finally fault F displaced the whole pile.”

7.4 Integrating absolute ages with the relative sequence

Radiometric dates (Section 5) do not replace the relative sequence — they anchor it. The strategy is always the same:

1. Build the relative sequence first, from field relationships alone.
2. Slot each dated rock into its position in the sequence.
3. Every undated event then inherits a bracketing age from its dated neighbours.

EXAMPLE Anchoring a sequence

Suppose in the section above we additionally know that limestone D contains Early Cretaceous fossils. Then: dyke E (120 Ma, Early Cretaceous) is consistent with cutting D; the unconformity U is bracketed between 550 Ma (granite below) and the Early Cretaceous (limestone above); and fault F is younger than 120 Ma. Notice how each new date tightens the brackets.

WARNING Faults and intrusions: read the contact carefully

A fault that offsets an intrusion must be younger than the intrusion. But a fault that is sealed (covered and undisturbed) by an overlying sedimentary unit is older than that unit. The same fault can therefore be bracketed: younger than everything it cuts, older than everything that seals it. Never assume a fault is “recent” just because it looks sharp on a diagram.

WARNING The two classic pitfalls

- Assuming simultaneous deformation. Folding, intrusion and faulting on one section are almost never one event. Each structure must be placed separately in the sequence using its own cross-cutting evidence. Two folds with different orientations may record two distinct orogenic phases separated by an unconformity.
- Ignoring hidden contacts. A contact may be concealed beneath younger cover or below the base of the section. If dyke E disappears beneath unit C, you cannot claim it cuts C — check whether it is truncated by the unconformity (older) or intrudes beneath it (younger). Always ask: what happens at the contact, even where I cannot see it?

7.5 Guided practice: three cross-sections of increasing difficulty**EXERCISE 7** Level 1 — Simple pile with one intrusion

A section shows, from bottom to top: shale (unit 1), sandstone (unit 2), both cut by a basalt dyke (unit 3), and a conglomerate (unit 4) resting unconformably on the eroded top of units 1, 2 and 3. The dyke is dated at 200 Ma. (a) List the events oldest to youngest. (b) Give the bracketing age of the unconformity.

EXERCISE 8 Level 2 — Folding, two intrusions, one fault

Folded greywackes (A) are intruded by granite (G1, dated 600 Ma). An unconformity (U1) separates these from horizontal sandstones (B). A second granite (G2) cuts B but is truncated by a second unconformity (U2) overlain by limestones (C). A fault (F) offsets A, G1, B and G2 but not C. Establish the full sequence and bracket the age of G2 and of F.

EXERCISE 9 Level 3 — The full puzzle

Using the annotated cross-section of this section, but suppose additionally that: (i) a second dyke E' cuts the granite B but is truncated by unconformity U; (ii) fault F is itself sealed by a horizontal basalt flow (G) dated at 30 Ma. Reconstruct the complete geologic history, bracket the age of dyke E', of the folding, and of fault F, and explain what the existence of E' tells us about the duration of magmatic activity in the region.

SOLUTION Exercise Level 1

(a) Events, oldest to youngest: deposition of shale 1 → deposition of sandstone 2 → intrusion of basalt dyke 3 (200 Ma) → uplift and erosion (unconformity) → deposition of conglomerate 4. (b) The unconformity post-dates the dyke (200 Ma) and pre-dates conglomerate 4; its bracketing age is therefore between 200 Ma and the age of unit 4 (younger than 200 Ma).

SOLUTION Exercise Level 2

Sequence: deposition of A → folding of A → intrusion of G1 (600 Ma) → erosion (U1) → deposition of B → intrusion of G2 → erosion (U2) → deposition of C → faulting F. Bracketing: G2 is younger than B (which it cuts) and older than U2 and C (which truncate and overlie it); since B is younger than 600 Ma, G2 is younger than 600 Ma and older than C. Fault F is younger than G2 (it offsets it) and older than C (which seals it, since F does not offset C); F is therefore bracketed between the intrusion of G2 and the deposition of C.

SOLUTION Exercise Level 3

Full history: deposition of A → folding of A → intrusion of granite B (550 Ma) → intrusion of dyke E' (cuts B) → uplift and erosion (U, truncating B and E') → deposition of C → deposition of D → intrusion of dyke E (120 Ma) → faulting F → eruption of basalt G (30 Ma) sealing F. Bracketing: E' is younger than 550 Ma and older than U (hence older than C); the folding is older than 550 Ma; fault F is bracketed between 120 Ma (it offsets E) and 30 Ma (it is sealed by G). Dyke E' shows that magmatism was episodic and long-lived: at least two intrusive episodes separated by a major erosion interval, a pattern typical of repeatedly reactivated magmatic provinces such as the Cameroon Volcanic Line.

KEY POINTS Key points of Section 7

- Reconstruct a geologic history with the **Event List**: inventory, local ordering, global ordering, insert absolute ages, write the narrative.
- An intrusion (or fault) is younger than everything it cuts and older than everything that overlies or seals it.
- A **bracketing age** constrains an undated event between the youngest dated unit below and the oldest dated unit above.
- Absolute dates anchor the relative sequence; they never replace field relationships.

- Beware the two traps: assuming simultaneous deformation, and ignoring hidden or concealed contacts.

DID YOU KNOW? Did you know?

The same logic you have just used on paper was applied in the field to the rocks around Mount Cameroon: geologists recognised that some lava flows are cut by dykes, while others blanket and seal older faulted terrain — allowing the recent volcanic and tectonic history of the Cameroon Volcanic Line to be ordered in time even before precise radiometric dates were available. Relative chronology remains the geologist's first and most powerful tool.

8 CORRELATION OF STRATIGRAPHIC SUCCESSIONS

In the previous section we learned how to read a single outcrop or borehole and reconstruct the sequence of events that produced it. Real geological mapping, however, rarely deals with isolated sections. To understand the regional geology of the Douala Basin, the Cameroon Volcanic Line, or the Congo Craton margin, we must demonstrate that the sandstone at the base of a hill near Kribi is the same unit as the sandstone cropping out 50 km away near Edea, or that a limestone in the Mamfe Basin is time-equivalent to a shale in the Rio del Rey Basin. This is the science of **correlation**: the demonstration of equivalence between stratigraphic units in different geographic areas. Correlation transforms local successions into a regional stratigraphic framework, allowing us to build paleogeographic maps, locate hydrocarbon reservoirs, and calibrate the Geologic Time Scale.

8.1 Principles and Objectives of Correlation

Correlation rests on the fundamental principle that layers which are the same age and formed in the same depositional environment will share similar physical, paleontological, and chemical characteristics. The objective is to establish equivalence of three distinct types:

- **Lithostratigraphic equivalence**: same rock type, same position in the succession (same formation).
- **Biostratigraphic equivalence**: same fossil assemblage, hence same relative age (same biozone).
- **Chronostratigraphic equivalence**: same absolute time interval (same stage, e.g., Cenomanian).

A successful correlation integrates all three. In the Douala Basin, for instance, the Mundek Formation (lithostratigraphy) contains *Orbitolina* foraminifera (biostratigraphy) that place it firmly in the Aptian–Albian (chronostratigraphy). When we find the same trio in a well log offshore, we have correlated the onshore outcrop with the subsurface.

DEFINITION Marker Bed

A **marker bed** (or key bed) is a distinctive, laterally extensive layer – volcanic ash (bentonite), limestone, coal seam, or a unique conglomerate – that can be recognized across a basin and used as a precise correlation horizon. Its lateral continuity and unique lithology make it an isochronous surface (deposited at the same time).

8.2 Lithostratigraphic Correlation

Lithostratigraphic correlation matches rock bodies based on lithology (composition, texture, colour), thickness, sedimentary structures, and vertical sequence. It is the first step in the field.

METHOD Lithostratigraphic Correlation Workflow

1. Describe each section in detail (litholog): bed thickness, grain size, sedimentary structures, fossil content.
2. Identify distinctive marker beds (e.g., a 2 m thick oolitic limestone, a bentonite layer).
3. Match the vertical succession of lithologies between sections (pattern matching).
4. Trace marker beds laterally on the ground or in seismic/well logs.
5. Define formations and members where the lithology is consistent and mappable.

Example – Douala Basin: The Logbaba Formation (Cretaceous) is recognized by its basal conglomerate, followed by cross-bedded sandstones and a distinctive red shale marker bed. In the field, you walk from the type section at Logbaba towards the coast, noting the red shale at the same stratigraphic level, confirming lateral continuity.

WARNING Facies Changes

Lithostratigraphic correlation fails when a formation changes laterally into a different rock type (facies change). A sandstone may pinch out into a shale, or a reef limestone may grade into basinal marl. Correlating the sandstone with the shale as the same formation is a classic error. Always seek biostratigraphic or chronostratigraphic control across facies boundaries.

8.3 Biostratigraphic Correlation

Fossils provide the most precise tool for correlating sedimentary rocks of Phanerozoic age. The principle is faunal/floral succession: fossil assemblages succeed each other in a definite, irreversible order.

PROPERTY Biostratigraphic Zones and FAD/LAD

Biostratigraphic zones (biozones) are bodies of rock defined by their fossil content. The most useful for correlation are **range zones** defined by the **First Appearance Datum (FAD)** and **Last Appearance Datum (LAD)** of an **index fossil** – a species that is geographically widespread, environmentally tolerant, rapidly evolving, abundant, and easily preserved/identified. The zone represents the time interval between the FAD and LAD of that taxon.

Other biozone types include assemblage zones (characteristic association of taxa), abundance zones (acme zones), and interval zones (between two biohorizons). A **range chart** plots the stratigraphic ranges of multiple taxa; the zones of overlap allow high-resolution correlation.

EXAMPLE Correlation using Ammonites in the Mamfe Basin

Two sections 30 km apart in the Mamfe Basin show different lithologies: Section A has sandy shales, Section B has calcareous mudstones. Both yield ammonites. Section A yields *Desmoceras latidorsatum* (FAD: Middle Albian) and *Mortoniceras* sp. (LAD: Late Albian). Section B yields *Desmoceras latidorsatum* and *Stoliczkaia* (FAD: Late Albian). The overlap of *D. latidorsatum* proves the two sections share a Middle–Late Albian interval, despite the facies difference.

8.4 Chronostratigraphic Correlation

Chronostratigraphic correlation aligns local successions to the Global Geologic Time Scale via **Global Boundary Stratotype Sections and Points (GSSPs)** – the “golden spikes” that define the base of each stage. Three powerful tools allow this alignment:

1. **Magnetostratigraphy:** Correlation of the pattern of magnetic polarity reversals (chrons) recorded in the rocks to the Global Polarity Time Scale (GPTS). A sedimentary section yielding a pattern of normal/reverse intervals (e.g., N-R-N-R) can be matched uniquely to the GPTS, providing absolute age control.
2. **Chemostratigraphy:** Correlation using global geochemical signals. The most famous is the $\delta^{13}\text{C}$ curve. Major excursions (e.g., the Weissert Event in the Valanginian, the OAE1a in the Aptian) are global isochrons. Measuring $\delta^{13}\text{C}$ in bulk carbonate or organic matter from a section in the Douala Basin and matching the curve to the global reference instantly ties the section to the absolute time scale.
3. **Astrochronology:** Where Milankovitch cycles (precession, obliquity, eccentricity) are recorded in rhythmic bedding (e.g., limestone–marl couplets), spectral analysis can provide a floating astronomical time scale that is anchored to radiometric dates.

DID YOU KNOW? The Aptian OAE1a in Cameroon

Oceanic Anoxic Event 1a (OAE1a, ~120 Ma) is marked by a prominent positive $\delta^{13}\text{C}$ excursion and widespread black shales. In the Douala Basin, the Mundeck Formation contains organic-rich shales correlated to OAE1a via chemostratigraphy, confirming an Early Aptian age and linking Cameroon's stratigraphy to a global climate perturbation.

8.5 Geophysical Correlation: Seismic and Well Logs

In subsurface exploration (oil, gas, groundwater), correlation relies on geophysical logs and seismic reflection profiles.

- **Well logs:** Gamma-ray (GR) logs distinguish shales (high GR) from clean sandstones/carbonates (low GR). A distinctive GR pattern (e.g., a "serrated" coarsening-upward motif) serves as a marker. Resistivity, sonic, and density logs provide additional correlation horizons.
- **Seismic reflectors:** A seismic line images acoustic impedance contrasts. Continuous, high-amplitude reflectors often correspond to major stratigraphic boundaries (unconformities, flooding surfaces, volcanic layers). **Seismic stratigraphy** correlates these reflectors across the basin, tying well logs to the seismic grid.

METHOD Integrated Well–Seismic Correlation

1. Pick formation tops on well logs (GR, resistivity, sonic).
2. Generate synthetic seismograms from sonic/density logs.
3. Match synthetic wiggles to seismic reflectors at the well location.
4. Extend reflector interpretation across the seismic grid.
5. Map the correlated horizons (time or depth structure maps).

8.6 Correlation Across Facies Changes

This is the ultimate test of correlation skill. When a shallow-marine sandstone (facies A) passes laterally into a deep-marine shale (facies B), lithostratigraphy breaks down. The solution is chronostratigraphic correlation using time-parallel surfaces:

- **Maximum Flooding Surfaces (MFS):** The most landward extent of marine transgression; often a condensed section rich in fossils and with a distinct GR/log signature. It is a time line.
- **Sequence Boundaries:** Subaerial unconformities (or their correlative conformities) formed during base-level fall.
- **Biohorizons:** FAD/LAD of planktonic microfossils (foraminifera, nannofossils) that lived in

the open ocean and rained down across all facies.

- **Chemostratigraphic events:** $\delta^{13}\text{C}$ excursions recorded in both carbonate (shallow) and organic matter (deep).

WARNING The Lithology Trap

Never correlate solely on similar lithology across a facies change. A sandstone in a delta front and a sandstone in a submarine fan may look identical but be millions of years apart. Always ask: "What is the age control?" (fossils, isotopes, magnetostratigraphy, radiometric dates).

8.7 Practical Workflow: Building a Correlation Panel

A **correlation panel** (or fence diagram) is the standard way to present correlated sections. It aligns multiple vertical sections along a datum (usually a marker bed, a sequence boundary, or sea level) to show lateral changes in thickness, facies, and age.

METHOD Stepwise Correlation Workflow for a Panel

1. Data gathering: Collect lithologs, fossil lists, radiometric ages, gamma-ray logs, seismic picks for all sections.
2. Choose a datum: Select a regional, time-significant horizon (e.g., Base Cretaceous Unconformity, MFS, or a dated volcanic ash).
3. Hang sections on the datum: Align all sections vertically so the datum is horizontal.
4. Correlate marker beds: Draw lines connecting identical marker beds (bentonites, coal seams, distinctive limestones).
5. Apply biostratigraphy: Plot FAD/LAD of index fossils; draw biozone boundaries horizontally (they are time lines).
6. Apply chronostratigraphy: Use magnetostratigraphy, $\delta^{13}\text{C}$ chemostratigraphy, or GSSP-tied events to draw stage boundaries (e.g., Aptian/Albian).
7. Interpret facies changes: Show how lithologies change laterally between sections; label depositional environments.
8. Finalize panel: Add scale, legend, location map, and interpretation (systems tracts, sequences).

WORKED EXAMPLE 8 Constructing a Correlation Panel: Three Wells in the Douala Basin

Statement: Three exploration wells (Well A – onshore, Well B – coastal, Well C – off-shore) penetrate the Cretaceous succession of the Douala Basin. The following data are available (depths in meters below rotary table, ages in Ma). The wells penetrate a post-Cretaceous cover before entering the Cretaceous at the Base Cretaceous Unconformity (BCU).

Feature	Well A (Onshore)	Well B (Coastal)	Well C (Off-shore)
Surface (Rotary Table)	0 m	0 m	0 m
Base Cretaceous Unconformity (BCU) / Base Logbaba Fm	120 m	350 m	480 m
Bentonite Marker Bed "Beta" (Radiometric: 112.5 ± 0.3 Ma)	210 m	480 m	610 m
FAD Orbitolina sp. (Early Aptian)	215 m	490 m	615 m
Positive $\delta^{13}\text{C}$ excursion (OAE1a, ~120 Ma)	250 m	540 m	650 m
LAD Orbitolina sp. (Late Aptian)	380 m	720 m	830 m
Top Mundeck Fm (MFS, Base Albian)	450 m	850 m	900 m
Total Depth	600 m	1200 m	1200 m

Construct a correlation panel at a vertical scale of 1 cm = 100 m, using the Base Cretaceous Unconformity as datum. Identify the formations, biozones, and key chronostratigraphic boundaries.

Detailed Solution:

Step 1: Choose Datum and Scale. Datum = Base Cretaceous Unconformity (BCU), which marks the base of the Logbaba Formation (Aptian). Scale: 1 cm = 100 m. On the panel, the BCU is drawn as a horizontal line. The post-Cretaceous cover (0 to BCU) is shown above the datum; the Cretaceous section is shown below.

Step 2: Calculate Depths Below Datum (Positive Downwards).

Horizon	Well A (m)	Well B (m)	Well C (m)
BCU (Datum)	0	0	0
Bentonite β	90	130	170
FAD Orbitolina	95	140	180
OAE1a ($\delta^{13}\text{C}$)	130	190	250
LAD Orbitolina	260	370	500
Top Mundeck (MFS)	330	500	650
Total Depth	480	850	1150


Step 3: Correlate Horizons (Time Lines). On a depth panel, horizons representing the same geological instant (isochrons) will plot at different depths below the datum due to differential subsidence and sedimentation rates. We connect them with sloping correlation lines.

- BCU (Datum): Horizontal line (by definition).
- OAE1a (120 Ma): Global isochron (Early Aptian). Connect points at 1.30, 1.90, 2.50 cm.
- Bentonite β (112.5 Ma): Radiometric isochron (Late Aptian). Connect points at 0.90, 1.30, 1.70 cm. Note: It lies above (younger than) OAE1a in all wells – consistent.
- FAD Orbitolina: Biohorizon (Early Aptian). Lies just above Bentonite β (5–10 m). Connect points.
- LAD Orbitolina: Biohorizon (Late Aptian). Connect points at 2.60, 3.70, 5.00 cm.
- Top Mundeck (MFS, ~113 Ma): Sequence boundary / Maximum Flooding Surface (Aptian/Albian boundary). Connect points at 3.30, 5.00, 6.50 cm.

Step 4: Interpret Formations and Biozones.

- Post-Cretaceous Cover: 0 to BCU (1.2, 3.5, 8.5 cm thick). Likely Tertiary/Volcanic.
- Logbaba Formation (Aptian): BCU to Top Mundeck. Thickness: Well A 330 m, Well B 500 m, Well C 650 m. Thickens basinward.
- Mundeck Formation (Albian): Top Mundeck to TD. Thickness: Well A 150 m, Well B 350 m, Well C 500 m. Thickens basinward.
- Orbitolina Range Zone: Spans FAD to LAD, covering most of the Aptian (Logbaba Fm).

Step 5: Draw the Panel. The figure below is a schematic correlation panel (depth domain). Lithology patterns: Post-Cretaceous (stipple), Logbaba Fm – Sandstone/Shale (dots/horizontal lines), Mundeck Fm – Shale/Limestone (horizontal lines/bricks), Bentonite (zigzag).



Interpretation: The panel shows the Aptian Logbaba Formation thickening significantly from onshore (Well A: 330 m) to offshore (Well C: 650 m), typical of a passive margin basin. The Albian Mundeck Formation thickens even more. The Bentonite β (112.5 Ma) and the OAE1a $\delta^{13}\text{C}$ excursion (120 Ma) provide absolute age tie-points. The Orbitolina range

zone spans the Aptian. The Top Mundeck MFS marks the Aptian/Albian boundary. This panel is the basis for a paleogeographic map and hydrocarbon play fairway analysis.

WARNING Data Consistency Check

In real work, always verify sedimentation rates. Here, the Aptian (125–113 Ma, 12 Myr) is 330–650 m thick (27–54 m/Myr), reasonable for a passive margin. The Bentonite (112.5 Ma) lies correctly above OAE1a (120 Ma). The Orbitolina LAD (Late Aptian) lies above the Bentonite (Late Aptian) in Wells A and B, but at the same level in Well C (500 m). This suggests condensation or a hiatus near the Aptian/Albian boundary in the offshore well – a critical observation for reservoir prediction.

8.8 Summary and Key Takeaways

KEY POINTS Correlation Essentials

- Correlation establishes equivalence between stratigraphic units in different areas: lithostratigraphic (rock type), biostratigraphic (fossils), chronostratigraphic (time).
- Marker beds (bentonites, coals, distinctive limestones) are the backbone of lithostratigraphic correlation.
- Index fossils (wide geographic range, short time range, abundant) define biozones via FAD/LAD; range charts visualize overlap.
- Chronostratigraphic tools: GSSPs, magnetostratigraphy (GPTS), chemostratigraphy ($\delta^{13}\text{C}$ excursions), astrochronology.
- Geophysical logs (gamma-ray, resistivity) and seismic reflectors enable subsurface correlation.
- Facies changes require correlation by time-parallel surfaces (MFS, sequence boundaries, biohorizons, chemostratigraphy), not lithology.
- A correlation panel aligns sections on a datum, integrates all data types, and displays lateral thickness/facies changes.

EXERCISE 10 Practice: Correlation in the Rio del Rey Basin

Two wells (Well X and Well Y) in the Rio del Rey Basin penetrate a Cretaceous succession.

Well X (proximal) shows: 0–200 m Sandstone (Barremian palynomorphs), 200–250 m Bentonite (Ar/Ar 125.2 Ma), 250–500 m Shale (Aptian foraminifera). Well Y (distal) shows: 0–400 m Shale (Barremian–Aptian foraminifera), 400–402 m Bentonite (Ar/Ar 125.2 Ma), 402–900 m Shale (Aptian–Albian foraminifera).

1. Draw a correlation panel at 1 cm = 100 m using the Bentonite as datum.
2. Identify the systems tracts and sequence boundary.
3. Explain why the sandstone in Well X does not appear in Well Y.
4. What chronostratigraphic tool would best constrain the Barremian/Aptian boundary here?

SOLUTION Exercise 8

- Panel: Datum = Bentonite (horizontal line at $y=0$). Well X: Sandstone from $y=-2.0$ to 0 cm (above datum), Bentonite at 0, Shale 0 to +2.5 cm. Well Y: Shale from $y=-4.0$ to 0 cm (above datum), Bentonite at 0, Shale 0 to +5.0 cm. Correlation lines: Base of Sandstone in X (Sequence Boundary) correlates to a horizon within the shale in Y at $y=-2.0$ cm (correlative conformity). Top of Shale in X ($y=+2.5$) correlates to a horizon in Y ($y=+2.5$).
- Systems Tracts: Well X: Lowstand Systems Tract (LST) Sandstone (Barremian) overlain by Transgressive Systems Tract (TST) Shale (Early Aptian). Well Y: Condensed TST Shale (Barremian–Early Aptian) overlying Highstand Systems Tract (not seen). The Bentonite (125.2 Ma, Early Aptian) falls within the TST.
- Facies change: Proximal sandstone (shoreface/delta front) pinches out laterally into distal offshore shale. Same time (Barremian), different environment. The Bentonite (airfall ash) blankets both.
- Tool: Magnetostratigraphy (M-sequence anomalies M0–M3) or chemostratigraphy ($\delta^{13}\text{C}$ curve) across the Barremian/Aptian boundary, calibrated to the GSSP. Palynomorphs give biozones but lower resolution for the boundary itself.

9 INTEGRATION, REVISION & EXAM PRACTICE

Having mastered the art of correlating successions across basins in Section 8, you now possess the full toolkit of a stratigrapher: relative principles, absolute dating, contact analysis, and correlation techniques. This final section is not merely a summary; it is a simulation of the examination room. The GCE Advanced Level Geology paper (Paper 2, Practical) demands that you integrate disparate datasets — a field map, measured sections, fossil lists, and radiometric

ages — into a single, coherent geological model within a strict time limit. Here we rehearse that integration, distil the syllabus into an exam-ready cheat sheet, dissect the marking schemes, and give you a personal audit checklist for the final weeks of revision.

9.1 The Capstone Synthesis Exercise

The ultimate test of your stratigraphic competence is the synthesis question: given a realistic field dataset, produce a stratigraphic column, a correlation panel, and a written geological history. This mirrors Question 1 of the GCE Practical paper. We will work through a complete, exam-style scenario.

EXPERIMENT

Capstone Synthesis: The "Mungo Basin" Field Problem

Scenario. You are provided with the following data from a mapping exercise along the Mungo River corridor (inspired by the Cretaceous Mamfe Basin geology).

Data Set A: Measured Section at Locality 1 (North Quarry).

- 0–12 m: Massive, cross-bedded sandstone, trough cross-bedding, paleocurrent 045°. Rare *Trigonia* bivalves.
- 12–12.3 m: Sharp, erosional base. Pebble conglomerate (quartz, chert clasts up to 5 cm).
- 12.3–25 m: Dark grey shale with siderite nodules. Abundant ammonites: *Desmoceras* sp., *Douvilleiceras* sp. (Albian index fossils).
- 25–25.5 m: Bentonite layer (volcanic ash). U–Pb zircon age: 102.4 ± 0.6 Ma.
- 25.5–40 m: Bioturbated siltstone, *Thalassinoides* trace fossils. *Inoceramus* sp. (Cenomanian).

Data Set B: Measured Section at Locality 2 (South Road Cut), 15 km SSW.

- 0–8 m: Lateritic soil / weathered sandstone.
- 8–20 m: Cross-bedded sandstone, identical lithology to Loc 1 base. *Trigonia* present.
- 20–20.2 m: Conglomerate lag (same clast suite).
- 20.2–30 m: Dark shale. Ammonites: *Desmoceras* sp. only.
- 30–30.1 m: Bentonite. U–Pb zircon age: 102.6 ± 0.5 Ma.
- 30.1–35 m: Siltstone with *Inoceramus*. Top eroded.

Data Set C: Borehole Log (Locality 3, 5 km East).

- 0–50 m: Sands and clays (Tertiary cover).
- 50–95 m: Shale with *Inoceramus*, *Ostrea*.
- 95–95.3 m: Bentonite. K–Ar glauconite age: 94.2 ± 1.2 Ma. (Note: K–Ar on glauconite is prone to argon loss; treat as minimum age).

- 95.3–120 m: Shale with *Desmoceras*, *Douvilleiceras*.
- 120–120.5 m: Conglomerate.
- 120.5–140 m: Sandstone (basal unit).
- 140 m: Basement granite (Pan-African, ~ 550 Ma).

Task.

1. Construct a composite stratigraphic column at 1:500 scale showing lithology, key surfaces, fossil zones, and radiometric dates with errors.
2. Draw a correlation panel (fence diagram style) linking the three localities. Show the pinch-out of the Cenomanian siltstone at Loc 2.
3. Write a concise geological history (max 200 words) integrating relative and absolute data.

WORKED EXAMPLE 9 Full Solution to Mungo Basin Synthesis

1. Composite Stratigraphic Column Construction.

- Scale: 1 cm = 5 m (1:500). Total thickness ~ 40 m → 8 cm column height.
- Lithostratigraphy (bottom to top):
 - **Basal Sandstone Formation** (informal): Massive, trough cross-bedded sandstone, conglomerate base. Fluvial/estuarine. Thickness: 12 m (Loc 1), 12 m (Loc 2), 20 m (BH3).
 - **Mungo Shale Formation** (informal): Dark grey, fossiliferous shale, siderite nodules. Open marine transgression. Thickness: ~ 13 m (Loc 1), ~ 10 m (Loc 2), ~ 25 m (BH3 — thickens basinward).
 - **Bentonite Marker Horizon**: 0.3–0.5 m thick. Key isochronous marker. U-Pb ages overlap within error (102.4 ± 0.6 vs 102.6 ± 0.5 Ma). Weighted mean: 102.5 ± 0.4 Ma (Albian).
 - **Upper Siltstone Member**: Bioturbated siltstone, *Inoceramus*. Cenomanian transgressive maximum. Present at Loc 1 (14.5 m) and BH3 (45 m), absent at Loc 2 (erosional pinch-out/unconformity).
- Chronostratigraphy: Albian (Lower–Middle) → Cenomanian (Lower). Bentonite = Early Albian (~ 102.5 Ma). K-Ar date (94.2 Ma) is discordant (glauconite recoil/argon loss); true age of upper shale is ~ 99–100 Ma (Cenomanian). Always flag discordant dates.

2. Correlation Panel (Fence Diagram).


- Draw three vertical columns spaced horizontally (Loc 1 – Loc 3 – Loc 2).

- Correlate the Bentonite as a horizontal datum (red line). It is the primary correlation tie-point.
- Correlate the Base Conglomerate (sequence boundary / transgressive surface).
- Show the Upper Siltstone wedging out against the Loc 2 column; draw an unconformity surface (wavy line) truncating the Mungo Shale at Loc 2, overlain by Tertiary laterite.
- Label: Lithology patterns, Fossil Zones (Ammonite Biozones), Radiometric Ages ($\pm 2\sigma$), Unconformities (U1, U2).

3. Geological History (Model Answer).

1. Pre-Cretaceous: Pan-African basement (granite, ~ 550 Ma) peneplained.
2. Early Albian (~ 103 Ma): Regional transgression. Deposition of Basal Sandstone (fluvial/estuarine) on uneven basement (onlap).
3. Mid-Albian (~ 102.5 Ma): Maximum flooding. Deposition of Mungo Shale (open marine). Explosive volcanism deposits Bentonite marker bed (U-Pb zircon 102.5 ± 0.4 Ma). Desmoceras/Douvilleiceras biozone.
4. Late Albian – Early Cenomanian (~ 100 Ma): Continued transgression. Deposition of Upper Siltstone (Inoceramus zone). Thickens eastwards (Loc 3) indicating basin deepening towards the depocentre.
5. Mid-Cenomanian (~ 98 Ma): Tectonic uplift / sea-level fall (Santonian? regional event). Erosion creates regional unconformity (U2). Upper Siltstone removed at Loc 2 (structural high), preserved in Loc 1 and Loc 3.
6. Tertiary – Recent: CVL volcanism, lateritisation, Mungo River incision exposing sections.

Examiner's Tip: Note the explicit link between the Bentonite age and the Ammonite biozone (calibration). Note the rejection of the K-Ar date with justification. Note the basinward thickening of the shale (subsidence analysis).



Blank stratigraphic column template (1:500 scale) for examination practice. Reproduce this in your practical notebook.

9.2 The "Cheat Sheet": Definitions, Principles & Formulas

In the exam, you waste precious seconds recalling definitions. Memorise this condensed reference. It covers every lesson (2–22) of the syllabus.

KEY POINTS

Stratigraphy Cheat Sheet — Upper Sixth GCE

A. Scope & Principles (Lessons 2–4)

- **Stratigraphy:** Study of stratified rocks: their geometry, composition, origin, age, and correlation.
- **Law of Superposition:** In an undeformed sequence, oldest at bottom, youngest at top.
- **Principle of Original Horizontality:** Sediments deposit horizontally.
- **Principle of Lateral Continuity:** Layers extend laterally until they thin out or hit a bar-

rier.

- **Principle of Cross-Cutting Relationships:** A feature cutting another is younger.
- **Principle of Inclusions:** Clasts in a rock are older than the host rock.
- **Principle of Faunal Succession (Smith):** Fossil assemblages succeed each other vertically in a definite, determinable order.
- **Uniformitarianism:** "The present is the key to the past" (Hutton/Lyell). Rates may vary.
- **Actualism:** Modern processes and rates explain the past (modern refinement).

B. Geologic Time Scale (Lessons 5–7)

- **Eon > Era > Period > Epoch > Age** (Chronostratigraphic: Eonothem > Erathem > System > Series > Stage).
- **Phanerozoic:** 541 Ma – Present. **Palaeozoic** (541–252 Ma), **Mesozoic** (252–66 Ma), **Cenozoic** (66 Ma–Present).
- **Key Boundaries:** P–Tr (252 Ma, mass extinction), K–Pg (66 Ma, Chicxulub), P–E (56 Ma, PETM).
- **Cameroon Context:** CVL (Cretaceous–Present), Mamfe Basin (Cretaceous), Pan-African Basement (> 541 Ma).

C. Dating Methods (Lessons 8–13)

- **Relative Dating:** Superposition, fossils, cross-cutting, unconformities. No numbers.
- **Absolute (Radiometric) Dating:** Parent → Daughter + Radiation. $N = N_0 e^{-\lambda t}$.
- **Half-life:** $t_{1/2} = \ln 2 / \lambda$.
- **Age Equation:** $t = \frac{1}{\lambda} \ln \left(1 + \frac{D}{P} \right)$.
- **Isochron Method:** Plots D^*/D_{ref} vs P/D_{ref} . Slope = $e^{\lambda t} - 1$. Assumptions: Closed system, initial homogeneity, constant λ .
- **Key Systems:**

System	Half-life	Range	Material
U–Pb (Zircon)	4.47/0.704 Ga	> 1 Ma – 4.5 Ga	Zircon, Titanite, Baddeleyite
K–Ar / Ar–Ar	1.25 Ga	> 10 ka – 4.5 Ga	K-feldspar, Mica, Glauconite*, Volcanics
Rb–Sr	48.8 Ga	> 10 Ma	Whole rock, Mica
Sm–Nd	106 Ga	> 10 Ma	Whole rock, Garnet
C–14	5730 yr	< 50 ka	Organic carbon, Charcoal

- ***Glauconite K–Ar:** Prone to argon loss → minimum ages only. Flag in exams.

- **Concordia/Discordia** (Wetherill): U–Pb on zircon. Concordant = closed system. Discordia chord → upper intercept = crystallisation age, lower intercept = Pb–loss event age.

D. Contacts & Unconformities (Lessons 14–15)

- **Conformable**: Continuous deposition (Gradational, Sharp).
- **Unconformity**: Hiatus (gap in record). Types:
 - **Angular Unconformity**: Tilted older rocks truncated, overlain by horizontal younger.
 - **Disconformity**: Parallel beds, erosional surface (palaeosol, lag), hard to spot.
 - **Nonconformity**: Sediments on crystalline basement.
 - **Paraconformity**: Parallel beds, no erosion, gap shown only by fossils.
 - **Buttress Unconformity**: Onlap against paleotopography (reef, fault scarp).
- **Sequence Boundary**: Regional unconformity = base of a depositional sequence (Vail/Exxon).
- **Transgressive Surface (TS) / Maximum Flooding Surface (MFS)**: Key correlation surfaces.

E. Sequencing Events (Lessons 16–19)

- Algorithm: 1. Identify units (oldest → youngest). 2. Identify structures (folds, faults, intrusions). 3. Apply Cross-Cutting. 4. Identify unconformities (erosion events). 5. Write history: "Deposition of X → Folding → Erosion (U1) → Deposition of Y → Faulting → Present".
- **Inclusion Rule**: Xenoliths in granite > Granite age. Clasts in conglomerate > Conglomerate age.
- **Baked/Chilled Margins**: Contact metamorphism proves intrusion is younger than country rock.

F. Correlation (Lessons 20–22)

- **Lithostratigraphic**: Rock type (formation, member). Diachronic (time-transgressive).
- **Biostratigraphic**: Fossils (Zone, Subzone). Isochronous (time-equivalent) if facies-independent. **Index Fossil**: Wide geographic range, narrow time range, abundant, easily ID'd.
- **Chronostratigraphic**: Time-rock units (System, Stage). Global standard (GSSP = Golden Spike).
- **Geochronologic**: Time units (Period, Age). "Early Jurassic" (time) vs "Lower Jurassic" (rocks).

- **Magnetostratigraphy:** Polarity chrons (C1n, C2An, etc.). Global isochrons.
- **Chemostratigraphy:** $\delta^{13}\text{C}$, $\delta^{18}\text{O}$, $^{87}\text{Sr}/^{86}\text{Sr}$ curves. Global correlation.
- **Event Stratigraphy:** Volcanic ash (bentonite), impact layer (Ir anomaly), OAE (black shale).

9.3 Deconstructing GCE Question Types

Understanding the command words and mark allocation is half the battle.


PROPERTY GCE Marking Scheme Anatomy

The GCE Geology Practical (Paper 2) marking scheme typically allocates marks as follows:

- **Diagrams (30–40%):** Strat columns, correlation panels, cross-sections, stereonet. Marks for: Scale, Title, Legend, Correct patterns, Labels (units, ages, contacts), Neatness (pencil, ruler).
- **Calculations (15–20%):** Radiometric ages, sedimentation rates, dip/apparent thickness. Marks for: Formula stated, correct substitution, units, significant figures (usually 2–3), error propagation.
- **Short Answers / Definitions (20–25%):** "Define...", "State...", "Identify...". Marks for: Key terms (e.g., "closed system", "index fossil", "hiatus").
- **Essay / Geological History (20–25%):** "Write a geological history...", "Discuss the evolution...". Marks for: Logical sequence, integration of relative + absolute data, use of technical vocabulary, identification of hiatuses, tectonic vs eustatic controls.

Rule: A clear, labelled diagram often earns full marks even if the accompanying text is brief. A perfect essay with no diagram loses the diagram marks.

Typical GCE Practical Paper Mark Distribution (Indicative)



Indicative mark breakdown for a GCE Advanced Level Geology Practical Paper (Paper 2). Percentages vary yearly but the hierarchy is stable: Diagrams + Calculations + Definitions + Essay.

WARNING Essay Trap: The "Definition Penalty"

In essay questions (e.g., "Discuss the role of unconformities in basin evolution"), the first 2–3 marks are almost always for definitions.

- Bad start: "Unconformities show gaps..." → 0/3 for definitions.
- Good start: "An unconformity is a surface of erosion or non-deposition representing a hiatus in the geological record. An angular unconformity separates tilted older strata from horizontal younger strata. A disconformity..." → 3/3 for definitions. Then discuss basin evolution.

Examiner's Report Quote (paraphrased): "Candidates who defined terms before discussing scored significantly higher. Many wrote excellent geological narratives but forgot to define 'sequence boundary' or 'maximum flooding surface', losing easy marks."

9.4 Time Management: The 2-Hour Practical Paper Strategy

Paper 2 is 2 hours (120 minutes). A typical paper has 4–5 questions. **Do not** start at Question 1 and work linearly if Q1 is a 30-minute column drawing and Q4 is a 5-minute definition. Use this protocol:

METHOD Exam Room Protocol: 120 Minutes

1. Minutes 0–5: **READ EVERYTHING.** Read the whole paper. Identify the "big" questions (strat column, correlation, history) and the "quick" questions (definitions, calculations, map symbols). Note the mark allocation printed on the paper.
2. Minutes 5–10: **PLAN & SET UP.** Sharpen pencils (2H for lines, HB for shading). Draw your stratigraphic column template (like Fig. 9.1) on graph paper immediately. Draw your correlation panel framework (three vertical lines, datum line). This "scaffolding" saves 10 minutes later.
3. Minutes 10–50: **THE "BIG DRAW"** (Strat Column + Correlation). This is usually 30–40 marks. Work systematically:
 - (a) Plot all contacts/measured thicknesses to scale.
 - (b) Add lithology patterns (use standard symbols: dots=sand, dashes=shale, bricks=conglom).
 - (c) Add fossil names next to the units.
 - (d) Add radiometric ages with $\pm$ errors at the correct horizon.
 - (e) Draw unconformities as wavy lines (erosional) or straight lines with hachures (non-conformity).
 - (f) Correlation: Join the isochronous horizons (bentonite, MFS, sequence boundary) first. Then lithology.
4. Minutes 50–70: **CALCULATIONS.** Radiometric ages, sedimentation rates. Show every step. Formula $\rightarrow$ Substitution $\rightarrow$ Answer $\rightarrow$ Unit $\rightarrow$ Error.
5. Minutes 70–90: **SHORT ANSWERS / MAP WORK.** Definitions, cross-sections, stereonets, map symbols. These are high marks-per-minute.
6. Minutes 90–110: **GEOLOGICAL HISTORY ESSAY.** Use your column/correlation as the script. Write in bullet-point chronological order. Use past tense ("Deposition of...", "Folding occurred...", "Intrusion of..."). Explicitly mention hiatus durations if calculable.
7. Minutes 110–120: **REVIEW** (The "Exam-Ready Checklist"). See Box 9.5.

9.5 The Exam-Ready Checklist (15-Point Final Audit)

Before you hand in your script, run this mental (or written) checklist. Every item is a common cause of lost marks.

METHOD Exam-Ready Checklist — Verify Before Submission

1. Scale Bar: Does every diagram (column, panel, cross-section) have a graphic scale bar (0–100 m / 1:500)?
2. Title Block: "Composite Stratigraphic Column, Mungo Basin, Localities 1–3, Scale 1:500, Candidate Name/Number".
3. Lithology Legend: Is there a key explaining every pattern used (sand, shale, lime, conglom, tuff, basement)?
4. Contact Types: Are contacts drawn correctly? Sharp (straight line), Gradational (zigzag), Unconformity (wavy), Fault (thick line + displacement arrows).
5. Radiometric Errors: Are ages written as 102.5 ± 0.4 Ma (not just "102.5 Ma")? Is the method stated (U–Pb zircon)?
6. Discordant Dates Flagged: Did you note "K–Ar glauconite: minimum age, likely argon loss"?
7. Fossil Zones: Are biozones labelled (e.g., "Desmoceras Zone, Albian") not just fossil names?
8. Correlation Lines: Do tie-lines connect isochronous surfaces (bentonite, MFS, sequence boundary), not just similar lithologies?
9. Pinch-outs/Onlap: Is the wedge geometry of the Upper Siltstone shown correctly at Loc 2?
10. North Arrow / Dip Symbols: On map/cross-section: North arrow, strike/dip symbols, vertical exaggeration stated (e.g., VE = 5×).
11. Calculation Working: Formula → Numbers → Result → Unit → Sig Figs (usually 2 for ages, 3 for rates).
12. History Chronology: Oldest event first. Every deposition, deformation, erosion, intrusion, unconformity event listed.
13. Hiatus Quantification: "Hiatus of ~ 4 Myr (Cenomanian–Turonian missing)" — estimated from biostratigraphy/radiometrics.
14. Terminology Precision: "Lower Jurassic" (rocks) vs "Early Jurassic" (time). "Formation" (litho) vs "Stage" (chrono). "Angular unconformity" not just "unconformity".
15. Neatness: Pencil lines sharp, shading even, no smudges, handwriting legible. Diagrams in pencil, text in pen.

9.6 Self-Assessment: The 22-Lesson Audit

Rate your confidence (1 = Weak, 5 = Exam Ready) for each syllabus lesson. Target: All ≥ 4 two weeks before the exam.

Lesson	Topic	Confidence (1–5)
2	Scope of Stratigraphy	
3	Stratigraphic Principles 1 (Superposition, Horizontality, Continuity)	
4	Stratigraphic Principles 2 (Cross-cutting, Inclusions, Faunal Succession)	
5	Geologic Time Scale 1 (Hierarchy, Phanerozoic divisions)	
6	Geologic Time Scale 2 (Boundary events, GSSPs, Cameroon context)	
7	Geologic Time Scale 3 (Magnetostatigraphy, Chemostratigraphy basics)	
8	Dating 1 (Relative vs Absolute, Half-life, Decay equation)	
9	Dating 2 (K-Ar, Ar-Ar, Rb-Sr, Sm-Nd systems)	
10	Dating 3 (U-Pb, Concordia/Discordia, Zircon)	
11	Dating 4 (C-14, Cosmogenic, Luminescence)	
12	Dating 5 (Isochron theory, Assumptions, Open/Closed systems)	
13	Dating 6 (Error propagation, Geochronology vs Thermochronology)	
14	Stratigraphic Contacts 1 (Conformities, Unconformity types)	
15	Stratigraphic Contacts 2 (Sequence boundaries, TS, MFS, Paraconformity)	
16	Sequence of Events 1 (Cross-section interpretation, Algorithm)	
17	Sequence of Events 2 (Inclusions, Baked margins, Xenoliths)	
18	Sequence of Events 3 (Complex histories: multiple deformations)	
19	Sequence of Events 4 (Integrating radiometric dates into history)	
20	Correlation 1 (Litho- vs Bio- vs Chronostratigraphy)	
21	Correlation 2 (Magnetostatigraphy, Chemostratigraphy, Event strat)	
22	Correlation 3 / Integration (Synthesis: Column + Panel + History)	

Action: For any lesson ≤ 3 , re-read the corresponding course section, do the **exercice** boxes, and check the **corrige**. Do **not** just re-read notes; do active recall (draw column from memory, calculate an age, define 5 terms).

9.7 Further Reading & Resources

DID YOU KNOW?

Beyond the Syllabus: Tools for the Professional Stratigrapher

1. International Chronostratigraphic Chart (ICS). Download the latest PDF from stratigraphy.org. It is the global standard. Know the current ratified GSSPs (Golden Spikes). The GCE expects you to use the ICS timescale (e.g., Cretaceous = 145.0–66.0 Ma, not old values). 2. "Principles of Sedimentology and Stratigraphy" by Sam Boggs Jr. (Pearson). The "Bible" for this level. Chapters 1–3, 12–14 cover our syllabus perfectly. Clear diagrams of unconformities, sequence stratigraphy, correlation methods. 3. "A Geologic Time Scale 2020" (Gradstein et al., Elsevier). The definitive reference for boundary ages and error margins. Use for checking "current" ages in revision. 4. Past GCE Papers (Cameroon GCE Board). Non-negotiable. Do at least 5 full Paper 2 past papers (2018–2023) under timed conditions. Mark them yourself using the official marking schemes (often available from teachers or GCE Board archives). Analyse why you lost marks. 5. Cameroon Geology Specifics:

- Nguimbous-Kouoh et al. (2019) "Geology of the Mamfe Basin" — for Cretaceous stratigraphy, ammonite zones, bentonites.
- Marzoli et al. (1999) "CVL volcanism" — for U-Pb dates on CVL basalts.
- IRGM/Ministry of Mines geological maps (1:500,000 or 1:200,000 sheets). Practice reading the legend and cross-sections.

6. Digital Tools: TimeScale Creator (free Java app, tscreator.org) — build your own custom time charts. Strater or LogPlot (industry software) — for digital column practice (optional but impressive for university).

DEFINITION

Integration

Integration in stratigraphy is the cognitive and technical process of combining relative data (superposition, fossil succession, cross-cutting, unconformities) with absolute data (radiometric ages, magnetostratigraphy, chemostratigraphy) to construct a single, self-consistent, four-dimensional (3D space + time) geological model of a basin or region. It requires resolving conflicts (e.g., discordant dates), identifying hiatuses, and distinguishing allocyclic (eustasy, tectonics) from autocyclic (channel migration) controls. This is the highest-order skill examined at GCE A-Level.

9.8 Final Words: From Student to Geologist

You have now traversed the entire Upper Sixth Stratigraphy syllabus. You can read the Earth's sedimentary archive: you know how to order its pages (principles), date its chapters (geochronology), recognise its missing pages (unconformities), correlate its volumes across the library (correlation), and write its history (synthesis).

The examination is not a trap; it is a performance. You have the script (this course), you have rehearsed the scenes (worked examples), and you know the marking criteria. On the day:

- **Breathe.** Read the question twice.
- **Draw first.** Diagrams anchor your thinking and secure "easy" marks.
- **Define before you discuss.**
- **Integrate.** Never give a relative age when an absolute age is available, and vice versa. Use both.
- **Enjoy it.** You are doing real geology.

Bonne chance, et que la stratigraphie soit avec vous! (Good luck, and may the stratigraphy be with you!)

EXERCISE 11 Final Integration Drill — Timed (45 minutes)

Scenario: A new borehole (BH-4) in the Mungo Basin (Section 9.1) yields:

- 0–30 m: Tertiary sands.
- 30–65 m: Shale with *Inoceramus*, *Ostrea*, *Scaphites* (Turonian index).
- 65–65.2 m: Bentonite. U–Pb zircon: 93.1 ± 0.3 Ma.
- 65.2–80 m: Shale with *Desmoceras* (Albian).
- 80–80.5 m: Conglomerate.
- 80.5–95 m: Sandstone.
- 95 m: Basement.

Tasks (Exam Conditions):

1. Add BH-4 to your Correlation Panel (Section 9.1). Show the new Turonian unit.
2. Calculate the sedimentation rate (m/Myr) for the Albian Shale (Bentonite at 102.5 Ma → Base Turonian at 93.1 Ma). Thickness in BH-3 = 25 m (95.3–120 m); in BH-4 = 15 m (65.2–80 m). Discuss the difference.
3. Update the Geological History to include the Turonian transgression and the new bentonite age.
4. Critical Thinking: The K–Ar glauconite date from BH-3 (94.2 Ma) falls between the two U–Pb bentonite dates (102.5 Ma and 93.1 Ma). Is the K–Ar date reliable? Justify.

SOLUTION Final Integration Drill

1. Correlation Panel Update. Add BH-4 column between BH-3 and Loc 1. New unit: **Tur-**

onion Shale (35 m thick in BH-4) with Scaphites biozone. New Bentonite (93.1 Ma) correlates to a bentonite not seen in other sections (erosion/non-deposition). Draw it as a dashed correlation line? No — U-Pb is robust. Draw solid line, label "Bentonite B (93.1 Ma)". Note: Turonian unit absent at Loc 1, Loc 2, BH-3 → major unconformity (U3) at top of Cenomanian/Albian.

2. Sedimentation Rates.

- BH-3 (Albian Shale): Thickness = 25 m. Time = 102.5 - 93.1 = 9.4 Myr. Rate = 25/9.4 = 2.7 m/Myr.
- BH-4 (Albian Shale): Thickness = 15 m. Same time span (9.4 Myr). Rate = 15/9.4 = 1.6 m/Myr.
- Interpretation: BH-3 is closer to the depocentre (basin axis) → higher subsidence → thicker accumulation. BH-4 is on a structural high or basin margin → lower accommodation space. Consistent with BH-3 having thicker Cenomanian (45 m vs 14.5 m at Loc 1).

3. Updated History Snippet.

5. Early Turonian (~ 93.5 Ma): Renewed transgression. Deposition of Turonian Shale (Scaphites zone). Volcanic event: Bentonite B (U-Pb 93.1 ± 0.3 Ma).

6. Mid-Late Turonian (~ 92 Ma): Major regression / uplift. Regional unconformity U3 removes Turonian at Loc 1, Loc 2, BH-3. Preserved only in BH-4 (depocentre).

4. K-Ar Glauconite Reliability. No, it is not reliable. The K-Ar age (94.2 ± 1.2 Ma) is younger than the underlying Albian bentonite (102.5 Ma) but older than the overlying Turonian bentonite (93.1 Ma). This is stratigraphically impossible for a closed system (superposition violated). Glauconite forms slowly at the sediment-water interface and continues to incorporate K (and lose Ar) long after deposition. The date represents a mixed age (minimum age of authigenesis ≈ Late Albian/Early Cenomanian). Always trust U-Pb zircon over K-Ar glauconite for depositional age.

KEY POINTS

Last-Minute "Pocket" Summary — Print on A6 Card

- Superposition = Relative age order.
- Unconformity = Hiatus (Time gap). 4 Types: Angular, Disconformity, Nonconformity, Paraconformity.
- Index Fossil = Wide geography, Short time, Abundant, Distinctive.
- Radiometric Age = $t = \frac{1}{\lambda} \ln(1 + D/P)$. Closed System essential.
- U-Pb Zircon = Gold standard (Concordia). K-Ar Glauconite = Minimum age (Leaky).

- Correlation Hierarchy: Event (Bentonite) > Biozone > Magnetozone > Chemozone > Lithology.
- Sequence Stratigraphy: SB (Sequence Boundary) → LST → TST → MFS → HST → SB.
- Geological History: Oldest → Youngest. Event + Process + Age + Evidence.
- Exam: Pencil diagrams (Scale, Title, Legend, Labels). Pen text. Define → Discuss. Check Checklist.

10 INTEGRATION ACTIVITY

11 INTEGRATION, REVISION & EXAM PRACTICE

11.1 Integration Exercise: Douala Basin Stratigraphic Synthesis

EXPERIMENT Douala Basin Stratigraphic Synthesis

11.2 Aims of the activity

- Consolidate the full suite of stratigraphic skills taught in this chapter: principles (superposition, original horizontality, cross-cutting, faunal succession), the geologic time scale, absolute and relative dating methods, recognition of stratigraphic contacts and unconformities, sequencing of geologic events, and correlation of successions.
- Apply these skills to a realistic dataset from the **Douala Basin** (Cameroon), a sedimentary basin that records the Cretaceous–Cenozoic evolution of the **Cameroon Volcanic Line** (CVL) and the Atlantic margin.
- Produce a professional-style stratigraphic report including lithostratigraphic columns, a correlation panel, a sequential geologic history, and an exploration-oriented interpretation (hydrocarbon trap prediction).
- Develop teamwork, scientific communication (poster presentation), and critical evaluation of data quality — competencies required for the GCE Advanced Level practical examination and for future university geoscience studies.

11.3 Situation

Geological setting. The Douala Basin is a coastal sedimentary basin in southwestern Cameroon, bounded to the north by the **Congo Craton**, to the west by the Atlantic Ocean, and to the east by the **Cameroon Volcanic Line** (CVL). It contains a thick Cretaceous to Recent succession deposited in fluvial, deltaic, and shallow marine environments, interrupted by volcanic episodes linked to the CVL. The basin is a current target for hydrocarbon exploration.

Data packet provided to each group (3–4 students).

1. Simplified geological map (sketch). Shows the basin outline, major faults (e.g., the **Sanaga Fault**), and the location of three measured sections:
 - Section A (Kribi area) – coastal outcrop, 120 m thick.
 - Section B (Douala city outskirts) – road-cut exposure, 210 m thick.

- Section C (Limbe area) – cliff section near Mount Cameroon, 180 m thick.
2. Measured sections (lithology, thickness, sedimentary structures). Summarised in Table 1.
 3. Fossil assemblage lists for each section (Table 2). Key index fossils: *Orbitolina* spp. (Early Cretaceous, Albian), *Rotalipora* spp. (Cenomanian–Turonian), *Globotruncana* spp. (Campanian–Maastrichtian), *Nummulites* spp. (Paleocene–Eocene), *Miogypsina* spp. (Miocene).
 4. Radiometric ages (absolute dates) from interbedded volcanic layers:
 - U–Pb zircon from a tuff layer in Section B (at 85 m from base): 93.5 ± 0.7 Ma.
 - K–Ar from a basalt flow capping Section C (top 10 m): 28.3 ± 1.2 Ma.
 - Ar–Ar from a volcanic ash layer in Section A (at 40 m from base): 55.2 ± 0.4 Ma.
 5. Seismic line sketch (interpreted). A single NW–SE seismic profile crossing the three sections (Figure 1 description). Key reflectors:
 - R1 – strong, continuous reflector at 2.5 s TWT (base of Cretaceous).
 - R2 – moderately continuous, onlaps onto R1 (Cenomanian transgression).
 - R3 – high-amplitude, chaotic zone (volcanic basement / CVL intrusions).
 - R4 – regional unconformity (Eocene–Oligocene) truncating R2.
 - R5 – prograding clinoforms (Miocene deltaic sequence).

Unit (base to top)	Section A (Kribi)	Section B (Douala)	Section C (Limbe)
1. Basal conglomerate	5 m, clast-supported, quartzite clasts	8 m, matrix-supported, feldspathic	6 m, polymictic, volcanic clasts
2. Sandstone (fluvial)	20 m, cross-bedded, trough cross-strat.	30 m, planar cross-beds, channel fills	25 m, ripple-laminated, minor mud drapes
3. Shale (lacustrine)	15 m, laminated, organic-rich	25 m, fissile, pyritic	20 m, silty, plant fragments
4. Limestone (shallow marine)	30 m, bioclastic, Orbitolina	40 m, wackestone, Rotalipora	35 m, packstone, Globotruncana
5. Marl (transitional)	10 m, fossiliferous, Nummulites	15 m, glauconitic, Nummulites	12 m, foraminiferal, Miogypsina
6. Sandstone (deltaic)	25 m, hummocky cross-strat.	40 m, sigmoidal clinoforms	30 m, distributary channel sands
7. Volcanic interbeds	Tuff at 40 m (Ar-Ar)	Tuff at 85 m (U-Pb)	Basalt flow at top 10 m (K-Ar)
8. Cover (Recent)	15 m, soil, laterite	12 m, alluvium	10 m, volcanic ash soil

Table 1: Simplified lithostratigraphic logs (thickness in metres). All sections rest on a Precambrian basement (not exposed).

Fossil group	Section A	Section B	Section C
Benthic foraminifera	Orbitolina sp. (Unit 4)	Rotalipora sp. (Unit 4)	Globotruncana sp. (Unit 4)
Planktonic foraminifera	–	Rotalipora cushmani (Unit 4)	Globotruncana arca (Unit 4)
Larger foraminifera	Nummulites sp. (Unit 5)	Nummulites sp. (Unit 5)	Miogypsina sp. (Unit 5)
Palynomorphs	Classopollis (Unit 3)	Afropollis (Unit 3)	Retimonocolpites (Unit 3)
Macrofauna	Oyster fragments (Unit 4)	Ammonite aptychi (Unit 4)	Echinoid spines (Unit 4)

Table 2: Key fossil assemblages per section (units refer to Table 1).

11.4 Tasks

1. Lithostratigraphic columns. Using the data in Table 1, draw three scaled lithostratigraphic columns (1 cm = 10 m) showing lithology, thickness, sedimentary structures, and the position of volcanic interbeds. Label each unit with a code (e.g., A1–A8).
2. Contacts and unconformities. On each column, identify and name every contact (conformable, disconformity, angular unconformity, nonconformity). Justify each interpretation using the principles of stratigraphy and the fossil/absolute age data.
3. Correlation panel. Construct a correlation panel aligning the three sections. Use:
 - Lithological similarity (facies matching).
 - Biostratigraphic markers (index fossils from Table 2).
 - Absolute ages (radiometric dates) to constrain the age of key horizons.

Indicate the chronostratigraphic stages (e.g., Albian, Cenomanian, Paleocene, Miocene) on the panel.

4. Sequential geologic history. Write a concise (≈ 300 words) narrative that sequences all events from basement formation to the present, incorporating: depositional environments, tectonic phases (rifting, thermal subsidence, CVL volcanism), sea-level changes, and the identified unconformities. Reference the seismic reflectors (R1–R5) where appropriate.
5. Hydrocarbon trap proposal. Based on the correlation panel and seismic sketch, propose a potential hydrocarbon trap linked to an identified unconformity. Specify:
 - Trap type (structural, stratigraphic, or combination).
 - Reservoir unit(s) and seal unit(s).
 - Source rock candidate and maturation timing relative to trap formation.
 - Risk factors (e.g., fault seal, volcanic intrusion).
6. Poster preparation. Design an A1 poster (portrait) that presents: (i) the three columns, (ii) the correlation panel, (iii) the geologic history as a timeline, (iv) the trap model with a cross-section sketch, and (v) a conclusion box. The poster will be presented in a 5-minute oral defence.

WORKED EXAMPLE 10


Task 1: Lithostratigraphic Columns

Statement: Draw three scaled lithostratigraphic columns (1 cm = 10 m) for Sections A, B, and C using Table 1 data. Show lithology, thickness, sedimentary structures, volcanic in-

terbeds, and label units A1–A8, B1–B8, C1–C8.

SOLUTION

Detailed solution:



Example lithostratigraphic column for Section A (Kribi) at 1 cm = 10 m. Students should draw similar columns for Sections B and C. Lithology patterns: conglomerate (brick), sandstone (crosshatch), shale (dots), limestone (NW lines), marl (crosshatch green), cover (grey). Volcanic interbeds shown as red lines with age labels.

Key points for all columns:

- Use standard lithological patterns (see figure).
- Mark the exact position of volcanic interbeds: Section A tuff at 40 m (base of Unit 4), Section B tuff at 85 m (within Unit 4), Section C basalt at top 10 m (top of Unit 6 / base of Unit 8).
- Annotate sedimentary structures: trough cross-stratification (A2, B2), planar cross-beds (B2), ripple lamination (C2), lamination (A3, B3, C3), hummocky cross-stratification (A6), sigmoidal clinoforms (B6), distributary channels (C6).

- Label the basement contact at the base as a nonconformity (jagged line).

WORKED EXAMPLE 11 Task 2: Contacts and Unconformities

Statement: Identify and name every contact in each column. Justify using stratigraphic principles and fossil/absolute age data.

SOLUTION

Detailed solution:

1. Base of each section (Units 1 on basement): Nonconformity. Justification: Sedimentary rocks (conglomerates) overlie Precambrian crystalline basement. The contact represents a profound erosion surface with a significant time gap (Precambrian to Cretaceous). Principle of **nonconformity**: sedimentary rocks on igneous/metamorphic basement.
2. Unit 1/2 contact (Conglomerate/Sandstone): Conformable (gradational). Justification: Upward fining from conglomerate to sandstone indicates continuous deposition in an alluvial-fan to fluvial transition. No fossil break or erosional surface.
3. Unit 2/3 contact (Sandstone/Shale): Conformable. Justification: Gradational change from fluvial channel sands to lacustrine laminated shales. Palynomorphs (Classopollis, Afropollis, Retimonocolpites) in Unit 3 indicate continuous non-marine deposition.
4. Unit 3/4 contact (Shale/Limestone): Conformable (transgressive surface). Justification: Sharp but conformable transition from lacustrine shale to shallow marine limestone with marine fossils (Orbitolina in A, Rotalipora in B, Globotruncana in C). This records a marine transgression (seismic reflector R2). No erosion; deepening upward.
5. Unit 4/5 contact (Limestone/Marl): Conformable. Justification: Gradational change from carbonate to marl with continuous fossil record (appearance of Nummulites in A and B). Represents continued marine deposition with increased terrigenous input.
6. Unit 5/6 contact (Marl/Deltaic Sandstone):
 - Sections A & B: Disconformity. Justification: Subtle erosional surface with lag gravel (implied by change from marine marl to deltaic sandstone), and a fossil gap: Nummulites (Paleocene–Eocene) in Unit 5, but no fossils in Unit 6. The seismic reflector R4 (Eocene–Oligocene unconformity) correlates here. Missing Oligocene.
 - Section C: Paraconformity (a type of disconformity without obvious erosion). Justification: Unit 5 contains Miogypsina (Miocene) directly overlying Unit 4 with

Globotruncana (Maastrichtian). The contact is sharp but shows no erosional relief. A hiatus of 30 Myr (Paleocene–Oligocene) is indicated by fossil mismatch. This is a **paraconformity**.

7. Volcanic interbeds:

- Section A tuff (40 m, Ar–Ar 55.2 Ma): Isochronous marker horizon. It lies at the base of Unit 4 (limestone). The age (Early Eocene) conflicts with Orbitolina (Albian) in the same unit. Critical evaluation: Either the tuff is a sill intruded later (cross-cutting), the Ar–Ar date reflects alteration, or the Orbitolina is reworked. Given the principle of cross-cutting relationships, if the tuff is a true interbed, the limestone must be Eocene, implying Orbitolina ranges higher here or is misidentified. Most likely: the tuff is a sill, and the 55.2 Ma date gives a minimum age for the host limestone.
- Section B tuff (85 m, U–Pb 93.5 Ma): Isochronous marker horizon. It lies within Unit 4 (limestone with Rotalipora, Cenomanian–Turonian). The U–Pb age (93.5 Ma, Cenomanian) is consistent with the biostratigraphy. This is a reliable tie-point.
- Section C basalt (top 10 m, K–Ar 28.3 Ma): Angular unconformity at its base. The basalt flows over Unit 6 (deltaic sandstone) which is tilted 15° (field observation). The contact is an **angular unconformity**: younger horizontal basalt on older tilted strata. The K–Ar age (28.3 Ma, Late Oligocene) dates the volcanism. Note: Unit 5 below contains Miogypsina (Miocene, <23 Ma), creating an age inversion (Oligocene basalt over Miocene sediment). This suggests either: (a) the basalt is a sill, not a flow; (b) excess argon gives an erroneously old K–Ar age; (c) Miogypsina is reworked. Field relations (flow topology vs. sill) are crucial.

8. Top of sections (Unit 8): Nonconformity / modern erosion surface. Soil/laterite/alluvium on bedrock.

WARNING Common Pitfalls in Contact Identification


- Do not confuse a paraconformity (gap without erosion) with a conformable contact. Always check fossil assemblages for time gaps.
- A nonconformity specifically requires sedimentary rocks overlying igneous/metamorphic basement. An angular unconformity requires tilted/folded older rocks overlain by younger, horizontal strata.
- Radiometric dates on volcanic layers: A date on a tuff within a sedimentary unit gives a maximum age for overlying strata and minimum for underlying (if primary). A date on a basalt overlying tilted strata dates the unconformity (post-tilting). Always verify field relationships (flow vs. sill) before accepting the date as depositional.

WORKED EXAMPLE 12 Task 3: Correlation Panel

Statement: Construct a correlation panel aligning the three sections using lithology, biostratigraphy, and absolute ages. Indicate chronostratigraphic stages.

SOLUTION

Detailed solution: The correlation panel (Figure 2) aligns the sections by **chronostratigraphic** age, not just lithological thickness. The key is the **diachronous** nature of the marine transgression (Unit 4) and the major Eocene–Oligocene unconformity (R4).



Correlation panel for the Douala Basin sections. Time increases upward (0 Ma at top).

Lithological patterns as in Task 1. Red lines: volcanic horizons with radiometric ages.

Purple zigzag: regional unconformity R4. Dashed lines: correlation of key horizons. Note the diachronous marine transgression (Unit 4: Albian in A, Cenomanian in B, Campanian in C) and the age conflict in Section C (Miocene fossils below Oligocene basalt).

Correlation Table (Chronostratigraphic Alignment):

Chronostratigraphic Stage	Section A (Kribi)	Section B (Douala)	Section C (Limbe)
Early Cretaceous (Berriasian–Albian)	Units A1–A3 (rift fill); A4 base (Orbitolina)	Units B1–B3 (rift fill); B4 base (Rotalipora)	Units C1–C3 (rift fill); C4 base (Globotruncana)
Cenomanian (93.5 Ma)	Hiatus / condensed?	Unit B4 continues; Tuff 93.5 Ma (U–Pb)	–
Turonian–Santonian	–	Unit B4 continues	–
Campanian–Maastrichtian	–	–	Unit C4 (Globotruncana)
Paleocene–Eocene	Unit A5 (Nummulites); Tuff 55.2 Ma (Ar–Ar) at base A4?	Unit B5 (Nummulites)	Hiatus (Paraconformity)
Eocene–Oligocene (34 Ma)	Unconformity R4 (Disconformity)	Unconformity R4 (Disconformity)	Angular Unconformity (tilting of Unit C6)
Oligocene (28.3 Ma)	–	–	Basalt flow 28.3 Ma (K–Ar) on tilted Unit C6
Miocene	Unit A6 (deltaic, hummocky)	Unit B6 (deltaic, sigmoidal clinoforms = R5)	Unit C5 (Miogypsina), Unit C6 (deltaic)
Pliocene–Recent	Unit A8 (cover)	Unit B8 (cover)	Unit C8 (cover)

Key Correlation Conclusions:

- The marine transgression (Unit 4) is strongly **diachronous**: Albian in the south (Kribi), Cenomanian in the centre (Douala), Campanian in the north (Limbe). This reflects the progressive northward flooding of the rift basin (seismic R2 onlap).
- The 93.5 Ma tuff in Section B provides a robust **isochron** for the Cenomanian.

- The 55.2 Ma tuff in Section A is problematic: it occurs at the base of the Albian limestone. It likely represents a sill or a remobilized ash, giving a minimum age for the limestone. The Nummulites in Unit A5 confirm Paleocene–Eocene deposition above.
- The regional unconformity R4 (Eocene–Oligocene) is a major sequence boundary. In A and B it is a disconformity at the Unit 5/6 boundary. In C it is an angular unconformity at the base of the basalt (Unit 7), with Unit 6 tilted beneath.
- The Miocene deltaic progradation (Unit 6) correlates basin-wide with seismic clinoforms R5. Miogypsina in Section C Unit 5 confirms Miocene age for the marl, but its position below the 28.3 Ma basalt requires the basalt to be a sill or the K–Ar date to be erroneous (excess argon).

WORKED EXAMPLE 13 Task 4: Sequential Geologic History

Statement: Write a concise (≈ 300 words) narrative sequencing events from basement to present.

SOLUTION

Detailed solution:

1. Precambrian (>540 Ma): Formation and stabilization of the **Congo Craton** basement. Pan-African orogeny (ca. 600–550 Ma) imprints a structural grain (NW–SE faults) later reactivated during rifting.
2. Early Cretaceous (Berriasian–Albian, 145–100 Ma): **Rifting** of the South Atlantic initiates the Douala Basin. Alluvial fans (Unit 1) and braided fluvial systems (Unit 2) deposit on the basement **nonconformity**. Lacustrine shales (Unit 3) accumulate in isolated rift lakes (organic-rich, potential source rocks). Seismic reflector R1 marks the base of this syn-rift sequence.
3. Albian–Cenomanian (113–93 Ma): Marine transgression floods the basin from the south (seismic R2 onlap). Shallow marine carbonates (Unit 4) with *Orbitolina* (Section A) indicate early Albian seaway. In Section B, *Rotalipora* and a U–Pb zircon age of 93.5 ± 0.7 Ma from an interbedded tuff anchor the Cenomanian transgression. Section C remains non-marine or receives deeper water facies later.
4. Turonian–Maastrichtian (93–66 Ma): Thermal subsidence dominates. Carbonate deposition continues (Unit 4 in Section C yields *Globotruncana*, Campanian–Maastrichtian). The basin is a passive margin.
5. Paleocene–Eocene (66–34 Ma): Sea-level highstand deposits marls with Nummulites (Unit 5) in Sections A and B. An ash fall in Section A yields Ar–Ar 55.2 ± 0.4 Ma (Early Eocene), but its position at the base of Unit 4 suggests it may be a sill; the Nummulites in Unit 5 confirm Paleocene–Eocene age for the marl. Section C shows a **para-**

conformity (hiatus of 30 Myr), likely due to uplift near the nascent Mount Cameroon.

6. Eocene–Oligocene (34–28 Ma): Major tectonic uplift and erosion linked to the onset of intense **Cameroon Volcanic Line** activity. The **regional unconformity R4** truncates the Paleogene sequence. In Section C, deltaic sands (Unit 6) are tilted 15° and truncated.
7. Late Oligocene (28 Ma): A basalt flow (K–Ar 28.3 ± 1.2 Ma) erupts over the eroded surface in Section C, forming an **angular unconformity**. This marks the main CVL volcanic phase. (Note: The K–Ar age is older than the overlying Miocene Miogypsina in Unit 5; the basalt is likely a sill or the date affected by excess argon.)
8. Miocene (23–5 Ma): Renewed subsidence and high sediment supply from the rising CVL. Deltaic sandstones (Unit 6) prograde basinward (seismic clinoforms R5). Miogypsina in Section C Unit 5 confirms Miocene age for the transgressive marl.
9. Pliocene–Present: Continued deltaic deposition, lateritic soil formation (Unit 8), and modern coastal processes.

WORKED EXAMPLE 14 Task 5: Hydrocarbon Trap Proposal

Statement: Propose a potential hydrocarbon trap linked to an identified unconformity.

SOLUTION

Detailed solution:

- Trap type: Combined **structural–stratigraphic trap**: a truncation (onlap) trap at the Eocene–Oligocene unconformity (R4). Miocene deltaic sandstones (Unit 6, reservoir) onlap the unconformity surface and are sealed by overlying Miocene shales/marls (top Unit 6 / Unit 8) and, locally, by the basalt flow (Section C).
- Reservoir unit(s): Unit 6 deltaic sandstones (hummocky cross-stratification in A, sigmoidal clinoforms in B, distributary channels in C). Good primary porosity/permeability expected. Laterally extensive on seismic (R5 clinoforms).
- Seal unit(s):
 - Vertical: Overlying Miocene marine shales/marls (top of Unit 6) and the regional basalt flow (where present, Section C) provide effective vertical seals.
 - Lateral: Pinch-out of deltaic sandstones against the R4 unconformity surface (stratigraphic seal).
- Source rock candidate:
 - Primary: Unit 3 lacustrine shales (organic-rich, Type I/II kerogen, TOC >2% inferred from "organic-rich" description). Deposited in Early Cretaceous rift lakes.

- Secondary: Unit 5 marls (Type II kerogen, marine).
- Maturation timing relative to trap formation:
 - Basin modelling suggests Unit 3 entered the oil window in Late Cretaceous (80 Ma) and gas window in Miocene (15 Ma).
 - Trap formation (R4 unconformity + Miocene onlap) occurred at 34 Ma (unconformity) and 23–5 Ma (reservoir deposition/seal).
 - Critical timing: Oil generation (Late Cretaceous) pre-dates trap formation (Oligocene–Miocene). However, gas generation (Miocene) is synchronous with trap formation. Migration pathways: carrier beds along the Sanaga Fault and along the R4 unconformity surface.
- Risk factors:
 - Fault seal integrity: The Sanaga Fault may act as a leak pathway if not sealed by shale gouge.
 - Volcanic intrusions: Basalt flows/sills (Sections A, B, C) may have fractured seals or caused local thermal overmaturity (gas cracking).
 - Reservoir continuity: Uncertainty in lateral extent of Unit 6 sandstones away from the three control points; seismic R5 clinoforms suggest good continuity but need 3D calibration.
 - Source rock maturity: Risk that Unit 3 is overmature (gas only) in the basin centre; oil potential may be limited to flanks.
- Recommendation: Acquire 3D seismic to map the onlap geometry of Unit 6 onto R4, image fault seals on the Sanaga Fault, and delineate basalt/sill distribution. Drill a test well at the crest of the onlap pinch-out (mid-basin, between Sections A and B) to test the truncation trap.

WORKED EXAMPLE 15 Task 6: Poster Preparation & Oral Defence

Statement: Design an A1 poster (portrait) presenting the synthesis. Prepare a 5-minute oral defence.

SOLUTION

Detailed solution: Poster Layout (A1 Portrait, 594 × 841 mm):

1. Title Block (Top 10%): “Stratigraphic Synthesis & Hydrocarbon Potential of the Douala Basin, Cameroon” — Names, Date, GCE Advanced Level Geology.
2. Left Column (30% width): Three Lithostratigraphic Columns. Scaled 1 cm = 10 m, aligned at the basement nonconformity. Colour-coded lithology patterns (legend).

Volcanic horizons highlighted in red with ages. Contacts labelled (NC, DIS, ANG, PARA).

3. Centre Column (40% width): Correlation Panel. As constructed in Task 3 (Figure 2). Chronostratigraphic scale on left. Correlation lines (dashed) for key horizons: Base Cretaceous (R1), Cenomanian Transgression (R2 + 93.5 Ma tuff), Paleogene Marl (Nummulites), R4 Unconformity, Miocene Delta (R5). Colour-code: Yellow = Reservoir (Unit 6), Grey = Seal (Unit 5, 8), Red = Volcanic, Blue = Source (Unit 3).
4. Right Column (30% width): Geologic History Timeline. Vertical timeline (0–145 Ma) with coloured bars for each tectono-stratigraphic phase: Rift (red), Transgression (blue), Thermal Subsidence (green), Uplift/Unconformity (purple), CVL Volcanism (orange), Deltaic Progradation (yellow). Key events annotated with ages and seismic reflectors (R1–R5).
5. Bottom Section (20% height): Trap Model Cross-Section. NW–SE sketch across the basin showing: Basement, Rift fill, Carbonate platform, R4 unconformity (zigzag), Miocene deltaic onlap (yellow), Seal (grey), Basalt sill/flow (red), Sanaga Fault. Hydrocarbon migration arrows from Unit 3 (source) up fault and along R4 into Unit 6 trap. Label: “Truncation Trap at R4”.
6. Conclusion Box (Bottom right): Bullet points: (1) Diachronous Albian–Campanian transgression. (2) R4 unconformity (34 Ma) creates regional trap. (3) Miocene deltaic sandstones (Unit 6) = reservoir. (4) Unit 3 lacustrine shales = source (gas prone). (5) Critical risks: fault seal, volcanic overmaturity. (6) Next step: 3D seismic + exploration well.

Oral Defence Key Messages (5 minutes):

- Integration: “We integrated biostratigraphy (Orbitolina → Rotalipora → Globotruncana → Nummulites → Miogypsina) with three radiometric dates (U–Pb, Ar–Ar, K–Ar) to build a robust chronostratigraphic framework.”
- Critical Data Evaluation: “We identified two age conflicts: (a) the 55.2 Ma tuff at the base of Albian limestone in Section A — interpreted as a sill giving a minimum age; (b) the 28.3 Ma basalt overlying Miocene Miogypsina in Section C — interpreted as a sill or excess argon. This critical evaluation is essential in real exploration.”
- Trap Genesis: “The Eocene–Oligocene unconformity (R4), driven by CVL uplift, created the structural template. Miocene deltaic progradation (R5) provided the reservoir and seal in a classic onlap truncation trap.”
- Cameroon Context: “This model applies the stratigraphic principles taught in this chapter to the Douala Basin, Cameroon’s premier hydrocarbon province, demonstrating the link between CVL tectonics and petroleum systems.”

KEY POINTS

Examiner's Tips for GCE Advanced Level

- In the practical exam, you may be given a similar dataset (logs, fossils, dates, seismic sketch).
- Always: Draw columns to scale. Label every contact with its type and justification (principle + evidence).
- Correlation: Align by time (chronostratigraphy), not just lithology. Use fossils for relative age, radiometric dates for absolute calibration. Note diachroneity.
- History: Use the sequence: Basement → Rift → Transgression → Subsidence → Uplift/Unconformity → Volcanism → Deltaic Progradation → Present. Link each to a seismic reflector if provided.
- Trap Proposal: Be specific: Trap type, Reservoir, Seal, Source, Timing, Risks. Mention "migration pathway".
- Poster: Clear visual hierarchy. Columns aligned. Correlation panel is the centrepiece. Cross-section must show trap geometry. Conclusion box = "take-home message".

DID YOU KNOW?

Cameroon Context: The Douala Basin & CVL

The Douala Basin (also called the Rio del Rey–Douala Basin) is the onshore/offshore extension of the Niger Delta petroleum system into Cameroon. It hosts the **Logbaba** gas field (discovered 1980s, producing since 2013) and the **Sanje** gas discovery. The basin's evolution is intimately tied to the **Cameroon Volcanic Line** (CVL), a 1600 km Y-shaped chain of volcanoes from Pagalu (Annobón) to Lake Chad. The CVL's origin is debated: mantle plume vs. lithospheric fracture. Its activity since the Cretaceous has provided: (1) heat flow for source rock maturation, (2) volcanoclastics as reservoirs/seals, (3) structural traps (faults, folds, unconformities), and (4) risks (seal breach, overmaturity). The 1986 **Lake Nyos** disaster (CO₂ release from a CVL maar) underscores the ongoing volcanic hazard. Understanding the stratigraphy of the Douala Basin is thus not only academic but of direct economic and societal relevance for Cameroon.

12 METHODS AND WORKED EXAMPLES

12.1 Methods and Worked Examples

This section presents the essential methodological tools for the Stratigraphy chapter. Each method is broken down into clear, examinable steps, followed by a GCE-style worked example showing the expected layout, reasoning and precision. Master these techniques: they are the backbone of Paper 2 (Structured/Essay) and of the practical mapwork and data-handling questions.

METHOD Applying Stratigraphic Principles to Decipher a Cross-Section

Goal: Determine the relative chronological order of geological events (deposition, folding, faulting, intrusion, erosion, unconformity) from a vertical cross-section.

Step-by-step procedure:

1. Identify all distinct rock units. Label each sedimentary layer, igneous body (dyke, sill, pluton) and metamorphic basement with a letter (A, B, C...). Note the lithology (shale, sandstone, limestone, granite, basalt).
2. Apply the **Principle of Superposition**. In an undeformed sequence, the oldest layer is at the bottom and the youngest at the top. Check for overturning: look for younging indicators (graded bedding, cross-bedding, ripple marks, mudcracks). If the beds are overturned, the apparent superposition is reversed.
3. Apply the **Principle of Cross-Cutting Relationships**. Any feature (fault, dyke, vein, unconformity surface) that cuts across a rock unit is younger than that unit. A fault displacing a dyke is younger than the dyke.
4. Apply the **Principle of Inclusions**. Fragments (xenoliths) of country rock inside an igneous intrusion are older than the intrusion. A conglomerate containing granite pebbles implies the granite is older than the conglomerate.
5. Identify **Unconformities**. Look for a surface separating two sequences with different dips (**angular unconformity**), a gap in the fossil record between parallel beds (**disconformity**), or sedimentary rocks resting on eroded crystalline basement (**nonconformity**). The rocks below are older; the surface represents missing time (**hiatus**); the rocks above are younger.
6. Use **Faunal Succession** (if fossils are given). Index fossils constrain the relative age of specific layers (e.g., trilobites → Palaeozoic, typically Cambrian–Permian; ammonites → Mesozoic, especially Jurassic–Cretaceous).
7. Construct the **Geological History**. List events from oldest (1) to youngest (last) using standard phrasing: “Deposition of Unit X”, “Folding/tilting”, “Erosion and planation”, “Intrusion of Dyke Y”, “Faulting (normal/reverse)”, “Deposition of Unit Z”.

Examiner's reflexes:

- Always state the principle used for each deduction (e.g., "By superposition, Shale A is older than Sandstone B").
- Distinguish relative age (order of events) from absolute age (numerical age in years). This method gives relative age only.
- On maps: apply the **rule of V's** for dipping beds crossing valleys, and remember that outcrop width increases as dip decreases (true thickness = outcrop width $\times$ sin(dip) for horizontal ground).

WORKED EXAMPLE 16 Relative Dating from a Complex Cross-Section (GCE Style)

Statement: A geological cross-section through a hypothetical area shows the following units:

- A: Massive granite (contains xenoliths of D).
- B: Horizontal sandstone with *Productus* (brachiopod) fossils (Carboniferous).
- C: Tilted shale/sandstone sequence (dipping 40° SE), no fossils.
- D: Metamorphic gneiss (basement).
- E: Dolerite dyke (vertical, cuts A, C and D, but does not cut B).
- F: Normal fault (displaces B, C, D and E; downthrow to the SE).
- G: Alluvial deposits (unconsolidated, flat-lying, covering all other units).

An angular unconformity separates C (below) from B (above). The dyke E is truncated by the unconformity surface beneath B.

Task: Establish the complete chronological sequence of geological events from oldest to youngest, justifying each step with the appropriate stratigraphic principle.

SOLUTION

Detailed Solution:

Step 1: Basement and intrusion.

- Unit D (gneiss) is the country rock; unit A (granite) contains xenoliths of D.
- Principle of Inclusions: the included rock (D) is older than the host (A).
- Event 1: Formation and metamorphism of the gneiss D (oldest basement).
- Event 2: Intrusion of the granite A.

Step 2: Sedimentation, deformation and dyke emplacement.

- Unit C rests on the eroded basement (A, D) and is now tilted at 40°.

- Principle of Original Horizontality: C was deposited horizontally, so the tilting post-dates the deposition of C.
- Event 3: Deposition of the sediments C on the eroded basement.
- Event 4: Tectonic deformation (folding/tilting) of C (and of A, D) to a 40° dip.
- Event 5: Erosion and planation truncating the tilted edges of C, A and D, producing a sub-horizontal erosion surface (the future unconformity).
- The dyke E cuts A, C and D but is truncated by the unconformity and does not cut B.
- Cross-Cutting Relationships: E is younger than A, C, D and younger than the tilting (it is itself vertical and undeformed); because it is truncated by the unconformity surface and sealed by B, it is older than B.
- Event 6: Intrusion of the dolerite dyke E, after the tilting and before the deposition of B.

Step 3: Unconformity and cover sequence.

- B (horizontal sandstone) lies on the eroded surface cutting C, A, D and E. B is horizontal while C dips at 40°: this is an angular unconformity.
- Principle of Unconformities: the rocks below (C, A, D, E) were deformed, intruded and eroded before the deposition of B.
- Fossils in B: *Productus* → Carboniferous (faunal succession).
- Event 7: Deposition of the sandstone B (Carboniferous).

Step 4: Faulting and recent deposits.

- F (normal fault) displaces B, C, D and E. Cross-cutting: F is younger than all the units it offsets.
- G (alluvium) covers everything, including the fault scarp. Superposition: G is the youngest unit.
- Event 8: Normal faulting F (post-Carboniferous extension).
- Event 9: Erosion of the fault scarp.
- Event 10: Deposition of the alluvial deposits G (youngest).

Final chronological table (oldest → youngest):

Order	Geological event
1	Formation of the metamorphic basement gneiss (D).
2	Intrusion of the granite (A) (xenoliths of D).
3	Deposition of the shale/sandstone sequence (C) on the eroded basement.
4	Tectonic deformation (folding/tilting) of C, A, D to a 40° dip.
5	Erosion and planation forming the unconformity surface.
6	Intrusion of the dolerite dyke (E) cutting the basement and the tilted cover.
7	Deposition of the horizontal sandstone (B) with <i>Productus</i> (Carboniferous) on the unconformity.
8	Normal faulting (F) displacing B, C, D, E (downthrow SE).
9	Sub-aerial erosion of the fault scarp.
10	Deposition of the alluvial deposits (G) (youngest).

Summary of justifications for the exam script:

- D older than A: inclusions (xenoliths).
- A, D older than C: superposition (C rests on the basement).
- C older than tilting: original horizontality.
- Tilting older than erosion: angular unconformity (truncation of C).
- E younger than tilting, older than B: cross-cutting plus truncation at the unconformity.
- B older than F: cross-cutting (F displaces B).
- F older than G: superposition (G covers the fault scarp).

METHOD Calculating Absolute Ages by Radiometric Dating

Goal: Calculate the absolute age of a rock or mineral from parent/daughter isotope measurements, using either the **single-sample** age equation or the **isochron** (graphical) method.

Fundamental relations:

1. Decay constant and half-life: $\lambda = \frac{\ln 2}{T_{1/2}} = \frac{0.693}{T_{1/2}}$.

2. Single-sample age equation (closed system, initial daughter zero or corrected):

$$t = \frac{1}{\lambda} \ln \left(1 + \frac{D^*}{P} \right)$$

where D^* is the accumulated radiogenic daughter and P the remaining parent (both in moles or atoms).

3. Isochron equation (e.g., Rb–Sr):

$$\left(\frac{D}{D_{\text{ref}}}\right)_{\text{present}} = \left(\frac{D}{D_{\text{ref}}}\right)_{\text{initial}} + \left(\frac{P}{D_{\text{ref}}}\right)_{\text{present}} (e^{\lambda t} - 1)$$

Plot $y = D/D_{\text{ref}}$ against $x = P/D_{\text{ref}}$ for several cogenetic samples or minerals:

- slope $m = e^{\lambda t} - 1 \Rightarrow t = \frac{1}{\lambda} \ln(m + 1)$;
- intercept = $(D/D_{\text{ref}})_{\text{initial}}$, which constrains the magma source.

Single-sample procedure (e.g., K–Ar):

1. Identify the system: parent, daughter, half-life or decay constants given (e.g., $^{40}\text{K} \rightarrow ^{40}\text{Ar}$, $T_{1/2} = 1.25 \times 10^9 \text{ yr}$).
2. Work in moles (atoms), never in mass. Convert mass to moles with $n = \frac{\text{mass}}{\text{molar mass}}$.
3. Correct for atmospheric daughter (K–Ar): $^{40}\text{Ar}^* = ^{40}\text{Ar}_{\text{meas}} - 295.5 \times ^{36}\text{Ar}_{\text{meas}}$.
4. Compute λ : for branching decay of ^{40}K , $\lambda_{\text{total}} = \lambda_{\beta} + \lambda_{\text{ec}} = 5.543 \times 10^{-10} \text{ yr}^{-1}$, with $\lambda_{\text{ec}} = 0.581 \times 10^{-10} \text{ yr}^{-1}$ (the branch producing ^{40}Ar).
5. Apply the branching age equation:

$$t = \frac{1}{\lambda_{\text{total}}} \ln \left(1 + \frac{\lambda_{\text{total}}}{\lambda_{\text{ec}}} \cdot \frac{^{40}\text{Ar}^*}{^{40}\text{K}} \right)$$

6. Round to the precision of the data (2–3 significant figures) and express the result in Ma or Ga.

Isochron procedure (Rb–Sr):

1. Tabulate $^{87}\text{Rb}/^{86}\text{Sr}$ (x-axis) and $^{87}\text{Sr}/^{86}\text{Sr}$ (y-axis) for each sample.
2. Draw the best-fit straight line; measure the slope $m = \Delta y / \Delta x$.
3. Age: $t = \frac{1}{\lambda_{\text{Rb}}} \ln(m + 1)$, with $\lambda_{\text{Rb}} = 1.42 \times 10^{-11} \text{ yr}^{-1}$.
4. Interpret the intercept (initial $^{87}\text{Sr}/^{86}\text{Sr}$): a high value suggests an old crustal source; a low value (≈ 0.702 – 0.704) a mantle source.
5. If the points scatter widely, the system was open (alteration, metamorphism): the “age” is meaningless.

WARNING Common Traps in Radiometric Calculations

- Confusing λ and $T_{1/2}$: λ is in yr^{-1} ; $T_{1/2}$ is in years. Convert before calculating.
- Mass versus moles: isotope ratios are atomic (mole) ratios. Convert concentrations (wt%, ppm) to moles first.
- Branching decay of ^{40}K : only about 11% of decays produce ^{40}Ar ; the rest produce ^{40}Ca . Use λ_{total} in the prefactor and the ratio $\lambda_{\text{total}}/\lambda_{\text{ec}}$ inside the logarithm.
- Closed-system assumption: heating (metamorphism) or weathering can reset or disturb the clock. A K–Ar date records cooling/last closure, not necessarily crystallisation.
- Units of the answer: with λ in yr^{-1} , t comes out in years; divide by 10^6 for Ma.

WORKED EXAMPLE 17 K–Ar Dating with Atmospheric Correction (Cameroon Volcanic Line)

Statement: A biotite separate from a trachyte of Mount Manengouba (Cameroon Volcanic Line) was analysed for K–Ar dating. Results per gram of sample:

- Potassium concentration: 8.00% K by weight (molar mass of K = 39.10 g mol^{-1}).
- Isotopic abundance of ^{40}K : 0.0117% of total K.
- Measured ^{40}Ar : $5.69 \times 10^{-10} \text{ mol g}^{-1}$.
- Measured ^{36}Ar : $5.00 \times 10^{-13} \text{ mol g}^{-1}$.
- Atmospheric ratio $(^{40}\text{Ar}/^{36}\text{Ar})_{\text{atm}} = 295.5$.
- Decay constants: $\lambda_{\beta} = 4.962 \times 10^{-10} \text{ yr}^{-1}$; $\lambda_{\text{ec}} = 0.581 \times 10^{-10} \text{ yr}^{-1}$.

Calculate the K–Ar age of the trachyte in Ma.

SOLUTION

Detailed Solution:

1. Total decay constant:

$$\lambda_{\text{total}} = \lambda_{\beta} + \lambda_{\text{ec}} = (4.962 + 0.581) \times 10^{-10} = 5.543 \times 10^{-10} \text{ yr}^{-1}$$

2. Moles of ^{40}K per gram (parent P):

mass of K per g = 0.0800 g

$$n(\text{K}) = \frac{0.0800}{39.10} = 2.046 \times 10^{-3} \text{ mol g}^{-1}$$

$$n(^{40}\text{K}) = 2.046 \times 10^{-3} \times 1.17 \times 10^{-4} = 2.394 \times 10^{-7} \text{ mol g}^{-1}$$

3. Atmospheric correction (radiogenic daughter D^*):

$$^{40}\text{Ar}_{\text{atm}} = 295.5 \times 5.00 \times 10^{-13} = 1.478 \times 10^{-10} \text{ mol g}^{-1}$$

$$^{40}\text{Ar}^* = 5.69 \times 10^{-10} - 1.478 \times 10^{-10} = 4.212 \times 10^{-10} \text{ mol g}^{-1}$$

4. Branching age equation:

$$\frac{^{40}\text{Ar}^*}{^{40}\text{K}} = \frac{4.212 \times 10^{-10}}{2.394 \times 10^{-7}} = 1.759 \times 10^{-3}$$

$$\frac{\lambda_{\text{total}}}{\lambda_{\text{ec}}} = \frac{5.543}{0.581} = 9.540$$

$$1 + 9.540 \times 1.759 \times 10^{-3} = 1.01679$$

$$t = \frac{\ln(1.01679)}{5.543 \times 10^{-10}} = \frac{0.01665}{5.543 \times 10^{-10}} = 3.00 \times 10^7 \text{ yr}$$

Final answer:

$$t \approx 30.0 \text{ Ma (Oligocene)}$$

Examiner's comments:

- The result ($\approx 30 \text{ Ma}$) is geologically plausible: the continental sector of the Cameroon Volcanic Line has been active since the Paleogene, and Oligocene ages are known from the CVL. Always check the plausibility of a calculated age against the geological context.
- The atmospheric correction is essential: without it, the age would be overestimated (excess apparent ^{40}Ar).
- Unit check: λ in yr^{-1} gives t in years; $3.00 \times 10^7 \text{ yr} = 30.0 \text{ Ma}$.
- Significant figures: the data carry 3 significant figures, so report 30.0 Ma.

METHOD Constructing and Interpreting a Stratigraphic Column (Log)

Goal: Synthesise lithological, palaeontological and structural observations from a measured section or borehole into a standard graphical log, then interpret the depositional environments and history.

Standard symbols (GCE convention):

- Lithology: sandstone (dots), shale (horizontal dashes), limestone (brick pattern), conglomerate (circles), coal (solid black), basalt (v-symbol), granite (crosses).
- Sedimentary structures: cross-bedding, ripple marks, graded bedding (coarse → fine), mudcracks, burrows.
- Fossils: sketch diagnostic forms (ammonite, trilobite, brachiopod, coral, plant debris).
- Contacts: sharp line (conformable), wavy/erosional line (unconformity), fault (tick on the downthrow side).
- Scale: always state the vertical scale (e.g., 1 cm = 10 m).

Step-by-step construction:

1. Draw the vertical axis with the depth scale and a central lithology column.
2. Fill in the lithology patterns between the correct depths; show grain-size trends (fining-up or coarsening-up).
3. Add sedimentary structures and fossils at their depths on the margins.
4. Mark the key surfaces: erosion surfaces/sequence boundaries (SB), flooding surfaces, and the level of deepest water (**maximum flooding surface**, MFS).
5. Group beds into **facies associations** and interpret the environment of each (use **Walther's Law**: a vertical succession records laterally adjacent environments):
 - Coarsening-up + marine fossils → prograding shoreface/delta;
 - Fining-up + cross-bedding + plant debris → fluvial channel;
 - Limestone + corals → reef/shallow platform;
 - Black shale + pyrite + no bottom fauna → anoxic basin.
6. Assign relative ages from index fossils (biostratigraphy) or superposition.
7. Write a synthesis sentence, e.g., "The log records a transgressive-regressive cycle: basal fluvial conglomerate → estuarine heterolithics → offshore shale (MFS) → prograding deltaic sandstone."

Exam skills:

- Correlation: match the MFS (shale/fossil peak) or erosion surfaces between logs.
- Rates: sedimentation rate = thickness / duration (m/Ma).
- Gaps: identify missing time (hiatus) at unconformities using missing fossil zones.

WORKED EXAMPLE 18 Interpreting a Borehole Log: Transgression–Regression (Rio del Rey Basin)

Statement: Borehole BH-01 (Rio del Rey Basin, offshore Cameroon) recovered the following succession (top → bottom). Construct a schematic log (scale 1 cm = 10 m) and interpret the depositional history.

Depth (m)	Lithology	Structures / Fossils	Gamma-ray log (API)
0–50	Sand, shelly	Turritella, Ostrea, bioturbation	40
50–120	Grey fissile shale	Planktonic forams (Globigerina), pyrite	120
120–122	Hardground (Fe/Mn crust)	Thalassinoides burrows, phosphatic nodules	
122–200	Heterolithic sand/shale	Flaser bedding, Ophiomorpha, brackish forams	60
200–250	Massive sandstone	Trough cross-bedding, plant fragments, coal at top	30
250–255	Conglomerate	Imbrication, erosional base	
255+	Granite basement	Weathered top (saprolite)	

Tasks: (1) Draw the log. (2) Identify facies associations and environments. (3) Identify the sequence–stratigraphic surfaces. (4) Reconstruct the relative sea–level history.

SOLUTION

Detailed Solution:

1. Schematic log (description for the drawing): vertical column 25.5 cm tall (1 cm = 10 m).

- 0–50 m: dot pattern (sand); shells and burrows; low gamma-ray block.
- 50–120 m: dashed pattern (shale); forams, pyrite; gamma-ray peak (120 API).
- 120–122 m: thick wavy line (hardground); burrows, phosphatic nodules.
- 122–200 m: alternating dots/dashes (heterolithic); flaser bedding, Ophiomorpha.
- 200–250 m: dots (sandstone); trough cross-beds; coal streak at top.
- 250–255 m: circles (conglomerate); imbrication; sharp erosional base.
- 255 m+: crosses (granite); stippled weathered top.

2. Facies associations and environments:

Interval	Facies association	Environment
0–50 m	Clean sand, marine shells, bioturbated	Shoreface / inner shelf (high energy, oxygenated).
50–120 m	Fissile shale, planktonic forams, pyrite, max. gamma ray	Offshore / prodelta (low energy, deepest water).
120–122 m	Hardground, bored, phosphatic	Condensed section / hiatus (sediment starvation).
122–200 m	Heterolithic, flaser bedding, Ophiomorpha, brackish forams	Tidal flat / estuary (tide-dominated, mixed energy).
200–250 m	Massive sand, cross-beds, plant/coal, fining-up	Fluvial channel / coastal plain.
250–255 m	Pebble conglomerate, imbrication, erosional base	Braided river / alluvial fan.
255 m+	Weathered granite	Basement / palaeosol.

3. Sequence–stratigraphic interpretation:

- Sequence boundary (SB): at 255 m (conglomerate on weathered granite): subaerial exposure and erosion.
- Lowstand systems tract (LST): 250–255 m (conglomerate) and 200–250 m (fluvial channel fill).
- Transgressive surface (TS): at 200 m (base of the heterolithics; appearance of brackish forams).
- Transgressive systems tract (TST): 122–200 m (estuarine/tidal deposits; landward shift of facies, retrogradation).
- Maximum flooding surface (MFS): at 120–122 m (hardground/condensed section, gamma-ray peak, planktonic forams, pyrite). Key correlation marker.
- Highstand systems tract (HST): 0–120 m (offshore shale passing up to shoreface sand): progradation, shallowing-upward.

4. Relative sea-level history:

- 255–200 m: lowstand then rapid rise (valley filling).
- 200–120 m: rapid rise (transgression); the shoreline moves landward.
- 120 m: turnaround (maximum flooding).
- 120–0 m: stillstand then relative fall (progradation); the shoreline moves seaward.

Summary statement for the exam: “The log records a complete depositional sequence: a sequence boundary on basement (255 m), lowstand fluvial fill, transgressive estuarine deposits, a maximum flooding surface marked by a phosphatic hardground and a

gamma-ray peak at 120 m, and a highstand prograding shoreface succession. The hard-ground at the MFS represents a significant hiatus (condensation).”

METHOD Correlating Stratigraphic Sections (Biostratigraphy and Lithostratigraphy)

Goal: Demonstrate the time-equivalence (or non-equivalence) of rock units in different sections (boreholes, outcrops) in order to reconstruct basin geometry.

Correlation tools (in order of reliability for time correlation):

1. Biostratigraphy (chronostratigraphy): **index fossils** (ammonites, graptolites, foraminifera, nannofossils, palynomorphs) defining **biozones**. Highest resolution; the gold standard.
2. Event stratigraphy: volcanic ash beds (bentonites, datable by radiometry), magnetic reversals (magnetostratigraphy), sequence boundaries and maximum flooding surfaces.
3. Lithostratigraphy: formations defined by lithology. Warning: lithological boundaries are commonly **diachronous** (time-transgressive): a sandstone formation migrates basinward during regression. Never correlate on lithology alone.

Step-by-step procedure:

1. Establish the local zonation: list the fossil assemblages of each section; identify index fossils (short range, wide distribution, abundant) and define biozones.
2. Identify marker horizons: ash beds, distinctive limestones, MFS (gamma-ray peak, condensed fauna), sequence boundaries (erosion, palaeosol).
3. Construct the correlation panel: draw the sections side by side at the same vertical scale and hang them on a time-line datum (an ash bed or MFS), not on the present-day surface.
4. Draw the correlation lines: connect time lines (biozone boundaries, ash beds, MFS) horizontally; draw lithostratigraphic boundaries as dipping lines to show diachronism.
5. Analyse thickness trends: thickening → depocentre (maximum subsidence); thinning/onlap → palaeohigh.
6. Identify hiatuses: missing biozones at unconformities or condensed sections; estimate the duration of the gap from the biozone durations.

Cameroon context:

- In the Douala, Rio del Rey and Logone Birni basins, correlation relies heavily on palynomorphs (pollen, spores, dinoflagellates) and foraminifera, because macrofossils are rare in deltaic and shaly successions.
- Bentonite/tuff layers linked to Cameroon Volcanic Line activity can provide radio-

metric tie-points within sedimentary basins.

- In the Benue Trough (e.g., Mamfe Basin), the Cretaceous marine transgressions are correlated using ammonites and foraminifera.

WORKED EXAMPLE 19 Multi-Well Correlation Panel (Logone Birni Basin)

Statement: Three wells (A, B, C) penetrate the Cretaceous of the Logone Birni Basin (North Cameroon). Palynology gives the following depths (m) of key bio-events (FO = first occurrence, LO = last occurrence).

Event	Well A (m)	Well B (m)	Well C (m)
FO Classopollis (base Albian)	2450	2100	2600
LO Afropollis jardinus (top Albian)	2100	1850	2200
FO Cicatricosisporites (base Cenomanian)	2050	1800	2150
Bentonite bed (dated 98.5 Ma)	1950	1720	absent
LO Spinizonocolpites (top Cenomanian)	1800	1600	1950
FO Gabonisporis (base Turonian)	1750	1550	1900

Tasks: (1) Construct a correlation panel hung on the bentonite datum (98.5 Ma), scale 1 cm = 100 m. (2) Calculate the average sedimentation rate for the Albian in each well (Albian duration $\approx$ 12 Ma, $\approx$ 113–101 Ma). (3) Interpret the basin geometry.

SOLUTION

Detailed Solution:

1. Panel construction:

- Draw a horizontal datum line at 98.5 Ma (bentonite) through wells A (1950 m) and B (1720 m).
- Plot the bio-events of each well at their depths relative to the datum (e.g., Well A: base Albian 500 m below datum; top Albian 150 m below; base Cenomanian 100 m below; top Cenomanian 150 m above; base Turonian 200 m above).
- Well C has no bentonite: interpolate the 98.5 Ma level within its Cenomanian. Cenomanian thickness = $2150 - 1950 = 200$ m over ≈ 6.5 Ma $\Rightarrow$ rate ≈ 30.8 m/Ma. At 98.5 Ma (2.0 Ma after the base Cenomanian): depth $\approx 2150 - 2 \times 30.8 \approx 2088$ m.
- Connect the time lines (biozone boundaries, bentonite) horizontally between wells.

2. Albian sedimentation rates (duration 12 Ma):

Well	Base Albian (m)	Top Albian (m)	Thickness (m)	Rate (m/Ma)
A	2450	2100	350	$350/12 = 29.2$
B	2100	1850	250	$250/12 = 20.8$
C	2600	2200	400	$400/12 = 33.3$

3. Basin geometry:

- Albian thickness: C (400 m) > A (350 m) > B (250 m).
- Well C occupied the Albian depocentre (maximum subsidence and sediment supply).
- Well B stood on a relative palaeohigh (thinnest Albian).
- Cenomanian check: A = 250 m (≈ 38.5 m/Ma), B = 200 m, C = 200 m (≈ 30.8 m/Ma): subsidence at A accelerated in the Cenomanian, while B remained a persistent high.
- The bentonite (98.5 Ma) provides an absolute time tie between A and B; its absence in C (the depocentre) is most likely a preservation/recognition problem, so the 98.5 Ma level in C is interpolated.

Exam answer structure: (1) neat panel with horizontal datum and time lines; (2) rate table with calculations shown; (3) interpretation paragraph: “Well C is the Albian depocentre (400 m; 33 m/Ma); Well B sits on a persistent palaeohigh; Well A shows accelerated Cenomanian subsidence. The dated bentonite confirms the biostratigraphic correlation.”

METHOD Solving the Sequence of Events from a Geological Map (Paper 3 Style)

Goal: Derive the geological history from a map (lithologies, dips, faults, folds, unconformities).

Step-by-step protocol:

1. Read the legend: units are usually listed oldest → youngest. Note the structural symbols: dip/strike, fold axes, faults (with downthrow side), unconformities.
2. Determine dip and younging: younging is perpendicular to strike in the dip direction (upright beds). Apply the **rule of V's**: a dipping bed makes a V pointing in the dip direction where it crosses a valley (for moderate dips); horizontal beds follow the contours.
3. Identify structures: anticline (oldest rocks in the core, limbs dip outward), syncline (youngest in the core, limbs dip inward); faults (repetition or omission of strata across the trace).
4. Identify unconformities: **truncation** of older units beneath the surface; **over-step/onlap** of the younger cover onto progressively older units.

5. Recognise inliers and outliers: inlier = older rocks surrounded by younger; outlier = younger rocks surrounded by older.
6. Write the history (oldest → youngest): deposition of the oldest unit → tectonic event(s) → erosion (unconformity) → deposition of the cover → intrusion/faulting → recent erosion and superficial deposits.

WARNING Map Traps

- A fault repeats or omits strata; a simple lithological boundary follows strike and dip consistently. Do not confuse them.
- A fault sealed (covered but not cut) by a younger unit is older than that unit: this brackets the age of faulting.
- Valleys often follow fault zones (crushed rock erodes easily); ridges follow resistant beds (quartzite, dolerite).

WORKED EXAMPLE 20 Map Interpretation: Unconformity, Tilting and Faulting


Statement: A geological map shows:

- Unit 1 (oldest): Precambrian gneiss (basement), outcropping in the north and south.
- Unit 2: Cambrian quartzite, vertical, N–S strike, forming a narrow central N–S belt.
- Unit 3: Ordovician shale, dipping 30° E, east of the quartzite.
- Unit 4: Silurian limestone, dipping 30° E, east of the shale.
- Unit 5: Carboniferous sandstone, horizontal, in the east, overlapping Units 2, 3, 4 and resting directly on Unit 1 in the north and south.
- A normal fault (downthrow east, N–S trace) cuts Units 1–4 but terminates at the base of Unit 5.
- Topography: a N–S valley follows the fault; a ridge follows the quartzite.

Tasks: (1) Sketch an E–W cross-section. (2) Write the complete geological history. (3) Explain why Unit 5 rests on Unit 1 in the north/south but on Units 2–4 in the centre.

SOLUTION

1. Cross-section (E–W), described:



Schematic E–W cross-section: tilted Units 2–4 and the fault F are truncated by the unconformity and sealed by the horizontal Carboniferous sandstone (Unit 5).

2. Geological history (oldest → youngest):

1. Formation of the Precambrian gneissic basement (Unit 1).
2. Deposition of the Cambrian quartzite (Unit 2) on the eroded basement (nonconformity).
3. Conformable deposition of the Ordovician shale (Unit 3) then the Silurian limestone (Unit 4).
4. Tectonism: tilting of Units 2–4 (to 30° E; quartzite vertical) and normal faulting (down-throw east) affecting Units 1–4. This is post-Silurian, pre-Carboniferous.
5. Prolonged erosion and planation: truncation of the tilted units and of the fault; in the north and south the Palaeozoic cover was completely removed, re-exposing the gneiss. An angular unconformity formed.
6. Carboniferous transgression: deposition of the horizontal sandstone (Unit 5), onlapping the unconformity.
7. Recent erosion sculpting the present landscape (valley on the crushed fault zone; ridge on the resistant quartzite).

3. Explanation of the map pattern (overstep):

- During the long pre-Carboniferous erosion interval, the tilted Palaeozoic sequence was stripped off the northern and southern areas (relative highs), exposing the basement, while it was preserved in the central area (protected by downfaulting to the east).
- The Carboniferous sandstone then blanketed the whole palaeo-landscape: it rests on gneiss where the Palaeozoic rocks had been removed (north/south) and on the truncated Palaeozoic units where they survived (centre). This regional relationship is called **overstep**.

- Significance: the fault is sealed by Unit 5, proving that faulting and tilting are pre-Carboniferous; the unconformity represents a major hiatus (the Devonian is missing).

Examiner's tips: use "overstep" for the regional pattern and "onlap" for the termination of beds against the unconformity; always bracket the age of a fault ("post-Silurian, pre-Carboniferous").

METHOD Graphical Correlation (Shaw Diagram) and Hiatus Quantification

Goal: Detect and quantify missing time (hiatus) or condensation in a section by plotting the depths of isochronous events (fossil first/last occurrences, dated ash beds) in two wells against each other.

Principle:

- Plot depth in Well A (x-axis) against depth in Well B (y-axis) for each synchronous event.
- The **Line of Correlation (LOC)** through the points expresses the ratio of sedimentation rates between the wells.
- An event that plots off the LOC (too shallow in one well) indicates a hiatus or condensed section there.
- Missing thickness = (depth predicted on the LOC) - (actual depth); hiatus duration = missing thickness / local sedimentation rate.

Step-by-step:

1. Select only reliable, isochronous tie-points (index-fossil events, radiometric dates) — never lithological boundaries.
2. Plot the points (Depth_A , Depth_B).
3. Fit the LOC through the reliable points (exclude the suspect point).
4. Predict where the suspect event should lie from its depth in the other well.
5. Compute the missing thickness, then divide by the sedimentation rate of the nearest undisturbed interval in the same well to obtain the hiatus duration.

WORKED EXAMPLE 21 Quantifying a Hiatus with a Shaw Diagram (Douala Basin)

Statement: Wells Alpha and Beta (Douala Basin) penetrate the Cretaceous. Planktonic foraminifera give the following zone-boundary depths (m):

Bio-event	Age (Ma)	Well Alpha (m)	Well Beta (m)
Top Albian (base Cenomanian)	100.5	2800	2500
Mid-Cenomanian event (MCE)	96.0	2450	2250
Top Cenomanian (base Turonian)	93.9	2350	2150
Mid-Turonian event	91.5	2170	2050
Top Turonian (base Coniacian)	89.8	2072	1980

Well Beta is suspected to contain a hiatus/condensed section near the Cenomanian–Turonian boundary.

Tasks: (1) Plot the Shaw diagram for the four reliable events and determine the LOC. (2) Predict the depth of the top Cenomanian in Beta if no hiatus existed. (3) Calculate the missing thickness and the hiatus duration, using the Turonian sedimentation rate of Beta.

SOLUTION

Detailed Solution:

1. Data points (Alpha x, Beta y) and LOC:

- Top Albian: (2800, 2500); MCE: (2450, 2250); Mid-Turonian: (2170, 2050); Top Turonian: (2072, 1980).
- These four points are collinear. Using the end members:

$$R = \frac{\Delta \text{Depth}_\alpha}{\Delta \text{Depth}_\beta} = \frac{2800 - 2072}{2500 - 1980} = \frac{728}{520} = 1.40$$

- LOC equation (through (2800, 2500)):

$$\text{Depth}_\alpha = 1.40 \text{ Depth}_\beta - 700$$

- Check (MCE): $1.40 \times 2250 - 700 = 2450$ ✓; (Mid-Turonian): $1.40 \times 2050 - 700 = 2170$ ✓.

2. Predicted top-Cenomanian depth in Beta: the top Cenomanian lies at 2350 m in Alpha:

$$2350 = 1.40 D_\beta - 700 \Rightarrow D_\beta = \frac{3050}{1.40} = 2178.6 \text{ m}$$

3. Hiatus calculation:

- Actual depth in Beta: 2150 m; predicted: 2178.6 m.
- Missing thickness: $\Delta h = 2178.6 - 2150 = 28.6 \text{ m}$.
- Turonian sedimentation rate in Beta (Mid-Turonian → Top Turonian):

$$SR_\beta = \frac{2050 - 1980}{91.5 - 89.8} = \frac{70 \text{ m}}{1.7 \text{ Ma}} = 41.2 \text{ m/Ma}$$

- Hiatus duration:

$$\Delta t = \frac{\Delta h}{SR_{\beta}} = \frac{28.6}{41.2} \approx 0.69 \text{ Ma}$$

Conclusion: Well Beta contains a hiatus of approximately 0.7 Ma (≈ 28.6 m of missing section) at the Cenomanian–Turonian boundary. This coincides with the well-known Cenomanian–Turonian boundary event (Oceanic Anoxic Event 2), commonly recorded as a condensed or erosive surface in the Douala Basin.

Examiner's note: always use the sedimentation rate of the same well and of the nearest undisturbed interval; using the other well's rate mixes two different subsidence histories.

METHOD Integrated Stratigraphic Interpretation: the “Big Picture” Essay

Goal: Synthesise lithostratigraphy, biostratigraphy, chronostratigraphy, sequence stratigraphy and geochronology into a coherent basin–evolution model (typical GCE long essay / integration question).

Structure of a high–scoring essay:

1. Introduction: locate the basin, state the data available (outcrops, wells) and the objective (stratigraphic framework and evolution).
2. Chronostratigraphic framework: the relevant part of the geologic time scale; the biozones used; the key marker surfaces (MFS, sequence boundaries, dated ash beds).
3. Lithostratigraphy and facies: the formations (lithology, thickness, boundaries); facies associations and depositional environments; lateral facies distribution.
4. Sequence stratigraphy / sea–level history: depositional sequences, systems tracts (LST, TST, HST); eustatic versus tectonic control.
5. Tectono–stratigraphic synthesis: the successive phases (rifting $\rightarrow$ breakup/drift $\rightarrow$ thermal subsidence $\rightarrow$ inversion/recent events), each with its characteristic stratigraphy.
6. Applications: economic significance (hydrocarbons, groundwater, building materials) and geohazards where relevant.
7. Conclusion: one summarising sentence.

Key terms that impress examiners: **accommodation space**, **progradation / retrogradation / aggradation**, **condensed section**, **hiatus**, **diachronous**, **onlap / overstep**, **systems tract**.

WORKED EXAMPLE 22 Integrated Basin–Evolution Essay Plan (Douala / Rio del Rey)

Statement: “Using your knowledge of the stratigraphy of the Douala/Rio del Rey Basin (Cameroon), describe the tectono–stratigraphic evolution from the Early Cretaceous to the Present. Illustrate your answer with the main sequences and key stratigraphic surfaces, and discuss the petroleum–system elements.”

SOLUTION

Model answer structure:

1. Introduction. The Douala and Rio del Rey basins form the Cameroonian segment of the West African margin, initiated during the Early Cretaceous opening of the South Atlantic (breakup of Gondwana). Their evolution reflects rift tectonics, thermal subsidence, eustatic sea-level changes and, later, magmatism of the Cameroon Volcanic Line (CVL).
2. Tectono–stratigraphic phases:

Phase	Time	Processes and stratigraphy
1. Syn-rift	Aptian–Albian	Extensional faulting; half-grabens filled with continental clastics (alluvial, fluvial, lacustrine; e.g., Mundeck-type facies); local volcanics; high sedimentation rates in depocentres.
2. Breakup / drift onset	Late Albian–Cenomanian	Major marine transgression; marine shales and limestones; maximum flooding; organic-rich black shales near the Cenomanian–Turonian boundary (Oceanic Anoxic Event 2) → regional source rock.
3. Thermal subsidence	Turonian–Maastrichtian	Long-wavelength subsidence; deltaic and shoreface progradation (reservoir sands); third-order sequences driven by eustasy.
4. Inversion / uplift	Paleogene	Compression and uplift (linked to Benue Trough inversion); erosion and a major unconformity; onset of CVL continental volcanism.
5. Neogene–Present	Miocene–Recent	Massive clastic progradation (deltaic systems related to the Niger Delta dispersal); growth faults; active CVL volcanism (Mount Cameroon eruptions; Lake Nyos and Lake Monoun maar craters).

3. Key stratigraphic surfaces to cite: breakup unconformity (near the Albian–Cenomanian transition); maximum flooding surfaces (mid-Cenomanian; Cenomanian–Turonian boundary); the Paleogene erosion unconformity; the condensed black-shale interval of OAE 2.

4. Petroleum-system elements (applied stratigraphy):

- Source rocks: Cenomanian–Turonian black shales (OAE 2, oil- and gas-prone); subordinate Albian lacustrine shales.
- Reservoirs: Albian fluvio-deltaic sands; Cenomanian shoreface sands; Late Cretaceous channel and turbidite sands; Miocene deep-water turbidites.

- **Seals:** the thick marine shale intervals (Cenomanian–Turonian, Maastrichtian, Miocene).
- **Traps:** fault-bounded blocks (syn-rift), rollover anticlines above growth faults (Neogene), stratigraphic pinchouts and unconformity traps.
- **Timing:** trap formation must coincide with or post-date hydrocarbon generation and migration; CVL heat flow locally accelerates maturation.

5. **Conclusion.** The Douala/Rio del Rey Basin records a classic margin evolution: continental syn-rift fill (Aptian–Albian), transgressive drift-onset marine deposition with the OAE 2 source rock (Cenomanian–Turonian), progradational passive-margin fill (Late Cretaceous), Paleogene inversion and erosion, and Neogene clastic progradation accompanied by CVL volcanism. The Cenomanian–Turonian boundary interval is the cornerstone of the regional petroleum system.

KEY POINTS Key Points of this Methods Section

- Relative dating rests on five principles: **superposition**, **original horizontality**, **cross-cutting relationships**, **inclusions**, **faunal succession**; unconformities mark **hiatuses**.
- Always name the principle behind every deduction in a cross-section or map exercise.
- Radiometric ages: work in moles, correct for initial/atmospheric daughter, use λ_{total} and the branching ratio for K–Ar, and check the geological plausibility of the result.
- Logs: read grain-size trends and fossils → facies → environments; the **MFS** (gamma-ray/fossil peak, condensed section) is the best correlation marker.
- Correlation: time lines (biozones, ash beds) are horizontal; lithological boundaries are commonly **diachronous** — never correlate on lithology alone.
- Shaw diagram: LOC through reliable tie-points; hiatus = missing thickness / local sedimentation rate.
- Essays: structure = framework → facies → sequences → tectonic phases → applications; use Cameroonian examples (Douala/Rio del Rey basins, CVL, Benue Trough).

13 EXERCISES

13.1 I check my knowledge

EXERCISE 12 MCQ: Stratigraphic Principles

Which of the following statements best describes the **Principle of Cross-Cutting Relationships**?

1. Sedimentary layers are deposited horizontally.
2. A fault or intrusion is younger than the rocks it cuts across.
3. Fossils succeed each other in a definite order.
4. In an undeformed sequence, the oldest layer is at the bottom.

EXERCISE 13 True/False with Justification

State whether each statement is True or False. Justify your answer in one sentence.

1. The half-life of a radioactive isotope changes with temperature and pressure.
2. An angular unconformity always indicates a period of deformation followed by erosion before deposition of the overlying strata.
3. Index fossils must have a wide geographic distribution but a narrow time range.
4. Carbon-14 dating can be used to date a basaltic lava flow from Mount Cameroon that erupted in 1999.

EXERCISE 14 Key Definitions

Define the following terms precisely:


1. **Lithostratigraphic unit** vs **Chronostratigraphic unit**.
2. **Concordia diagram** (in U-Pb geochronology).
3. **Magnetostratigraphy**.
4. **Hiatus**.

EXERCISE 15 Direct Calculation: Radiometric Dating

A zircon crystal from a granitic intrusion in the **Cameroon Volcanic Line** contains 12.5 % of its original ^{238}U (half-life = 4.468e9 years). Assuming a closed system, calculate the age of the crystallisation of the zircon. Show your working.

13.2 I practise**EXERCISE 16** Relative Dating from a Cross-Section

The schematic cross-section below shows a sequence of sedimentary rocks (S1–S4), a granitic intrusion (G), a dolerite dyke (D), and an overlying flat-lying sandstone (S5). A fault (F) offsets all units except S5.



Schematic cross-section for relative dating exercise.

List the geological events (deposition of S1–S4, folding, intrusion G, dyke D, faulting F, erosion, deposition of S5) in correct chronological order from oldest to youngest. State the stratigraphic principle used for each relative age constraint.

EXERCISE 17 Biostratigraphic Correlation

You are given the stratigraphic ranges of five fossil species (A–E) in the table below (Ma = millions of years ago). A well in the **Rio del Rey Basin** penetrates three fossil assemblages at different depths:

- Assemblage 1: Species A, C
- Assemblage 2: Species B, D
- Assemblage 3: Species C, E

Species	First Appearance (Ma)	Last Appearance (Ma)
A	145	130
B	135	110
C	140	120
D	125	90
E	115	85

1. Determine the possible age range (in Ma) for each assemblage.
2. Identify which species could serve as an **index fossil** for the Early Cretaceous (approx. 145–100 Ma) in this basin. Justify.
3. If a volcanic ash bed within Assemblage 2 yields a U–Pb zircon age of 112 ± 2 Ma, how does this refine the correlation?

EXERCISE 18 Concordia–Discordia Interpretation

Three zircon analyses from a granitic gneiss in the **Congo Craton** (Southern Cameroon) plot on a Concordia diagram as follows (ratios are $^{207}\text{Pb}/^{235}\text{U}$ vs $^{206}\text{Pb}/^{238}\text{U}$):

- Analysis 1: (0.125, 0.0185)
- Analysis 2: (0.210, 0.0310)
- Analysis 3: (0.350, 0.0515)

The points define a straight line (Discordia) intersecting the Concordia curve at two points.

1. Sketch a labelled Concordia diagram showing the three analyses and the Discordia line. Indicate the upper and lower intercepts.
2. If the upper intercept corresponds to 2050 ± 20 Ma and the lower intercept to 550 ± 30 Ma, interpret the geological history of the sample.
3. Why do zircon grains often yield discordant ages? Mention two mechanisms.

EXERCISE 19 Unconformities: Identification and Field Evidence

Draw a single schematic stratigraphic column (approx. 15 cm tall) showing, from bottom to top:

1. A **nonconformity** between Precambrian gneiss and Cambrian sandstone.
2. An **angular unconformity** between folded Silurian shales and horizontal Devonian

sandstone.


3. A **disconformity** within the Carboniferous limestone (with a palaeosol).
4. A **paraconformity** between two Jurassic clay units (identified only by fossil gap).

Label each contact clearly. For each unconformity type, list two distinct field criteria you would use to recognise it.

13.3 I prepare for the GCE

EXERCISE 20 Integrated Relative and Absolute Dating – 20 marks

The figure below represents a geological cross-section through part of the **Benue Trough** (Northern Cameroon).



1. Establish the complete relative chronological sequence of all events shown (deposition, tilting/folding, intrusion, dyke emplacement, faulting, erosion, deposition of Ts). [8 marks]
2. Using the U-Pb zircon age provided for the Granite (Gr), state the minimum absolute age of the tilting/folding event affecting the Cretaceous Sandstones (Ks). Explain your reasoning. [4 marks]
3. The Dolerite Dyke (Dd) is not dated. However, a whole-rock K-Ar analysis on the dyke yields 42 ± 2 Ma. Discuss the reliability of this K-Ar age compared to the U-Pb zircon age for constraining the timing of dyke emplacement. Consider the closure temperatures of the systems. [4 marks]

4. The contact between the Basement Gneiss (Bg) and the Cretaceous Sandstones (Ks) is a **nonconformity**. Describe the field evidence you would look for to confirm this interpretation. [4 marks]

EXERCISE 21 Essay: **Magnetostratigraphy and Chemostratigraphy in Cameroon – 25 marks**

“Discuss the role of magnetostratigraphy and chemostratigraphy in refining the correlation of Cretaceous sequences in the Atlantic margin of Cameroon.”

In your answer, you should:

- Define both methods and the principle on which each relies.
- Explain how the **Geomagnetic Polarity Time Scale (GPTS)** is constructed and used for correlation.
- Describe the main **chemostratigraphic** proxies (e.g., $\delta^{13}\text{C}$, $\delta^{18}\text{O}$, $^{87}\text{Sr}/^{86}\text{Sr}$) applicable to Cretaceous marine sediments.
- Evaluate the strengths and limitations of each method when applied to the **Rio del Rey**, **Douala**, and **Kribi-Campo** basins.
- Provide a specific example (real or hypothetical) of how the integration of magnetostratigraphy, chemostratigraphy, and biostratigraphy resolved a correlation problem in the Cretaceous of the Cameroon Atlantic margin.

EXERCISE 22 Multi-Section Correlation and Sequence Stratigraphy – 20 marks

Three boreholes (BH-1, BH-2, BH-3) are drilled along a 50 km transect perpendicular to the coast in the **Douala Basin**. The simplified lithologs and key data are given below.

Depth (m)	BH-1 (Onshore)	BH-2 (Coastal)	BH-3 (Offshore)
0–200	Yellow sands, lignite	Grey clays, forams	Grey clays, forams
200–450	Unconformity (U1)	Unconformity (U1)	Grey marls, Orbitolina
450–600	Red beds, conglomerates	Yellow sands, lignite	Grey marls, Orbitolina
600–800	Basement	Red beds, conglomerates	Black shales, TOC 4%, Inoceramus
800–1000	–	Basement	Black shales, TOC 4%, Inoceramus

Additional data:

- Biostratigraphy: Orbitolina (Aptian), Inoceramus (Turonian–Coniacian). Planktonic forams in BH-2/3 top unit: Globotruncana (Campanian–Maastrichtian).

- Radiometric: Volcanic ash at 550 m in BH-3: U-Pb zircon = 93.5 ± 0.3 Ma (Cenomanian-Turonian boundary).
 - Seismic: U1 correlates with a major regional reflector (Base Tertiary Unconformity).
1. Construct a correlation panel (fence diagram) at a vertical scale of 1 cm = 100 m, showing the three boreholes, the correlation of lithostratigraphic units, and the unconformity U1. [6 marks]
 2. Identify the **systems tracts** (Lowstand, Transgressive, Highstand) represented in the offshore section (BH-3) between 450 m and 1000 m, assuming a eustatic sea-level curve with a major transgression in the Aptian-Albian and a highstand in the Late Cretaceous. Justify using the lithology and fossil data. [6 marks]
 3. Calculate the average sedimentation rate (m/Ma) for the black shale unit in BH-3 (800–1000 m) using the radiometric age constraint and the biostratigraphic range of *Inoceramus*. [4 marks]
 4. Discuss the hydrocarbon potential (source rock, reservoir, seal, trap) of the correlated sequence, referencing the specific units in the three boreholes. [4 marks]

14 SOLUTIONS TO THE EXERCISES

SOLUTION Exercise 1 — MCQ: Stratigraphic Principles

Correct answer: (b) — A fault or intrusion is younger than the rocks it cuts across.

Justification: The **Principle of Cross-Cutting Relationships** (formulated by James Hutton and Charles Lyell) states that any geological feature (fault, dyke, intrusion, vein) that cuts across another rock body must be younger than the rock it cuts, because the rock must already have existed in order to be cut.

Why the other options are wrong:

1. Statement (a) describes the **Principle of Original Horizontality** (Steno).
2. Statement (c) describes the **Principle of Faunal Succession** (William Smith).
3. Statement (d) describes the **Principle of Superposition** (Steno).

WARNING Examiner's tip

In MCQs, read every option: three of them are true statements but they describe other principles. The question tests your ability to match each principle to its correct statement, not merely to recognise a true sentence.

SOLUTION Exercise 2 — True/False with Justification

1. TRUE. The half-life of a radioactive isotope is a nuclear property that is essentially constant and unaffected by temperature, pressure or chemical state; this is precisely why radiometric dating is reliable.
2. TRUE. An angular unconformity records a sequence of: deposition of the lower strata → tectonic deformation (tilting/folding) → uplift and erosion producing a truncated surface → renewed deposition of the overlying horizontal strata.
3. TRUE. A good index fossil combines a wide geographic distribution (so it can correlate rocks over large areas) with a short stratigraphic range (so it defines a narrow time interval), plus abundance and easy identification.
4. FALSE. Carbon-14 dating only works on organic material younger than about 50000 years; a basalt contains no organic carbon, and a 1999 eruption is far too recent — the method of choice for young lavas would be K-Ar or $^{40}\text{Ar}/^{39}\text{Ar}$ dating.

SOLUTION Exercise 3 — Key Definitions

1. Lithostratigraphic unit vs Chronostratigraphic unit: A **lithostratigraphic unit** (e.g., formation, member, group) is a body of rock defined solely by its observable lithological characteristics (rock type, texture, composition); its boundaries may be diachronous (of different ages in different places). A **chronostratigraphic unit** (e.g., system, series, stage) is a body of rock defined by the time interval during which it was deposited; its boundaries are isochronous (same age everywhere).
2. Concordia diagram: A graph plotting the ratio $^{206}\text{Pb}/^{238}\text{U}$ (x-axis) against $^{207}\text{Pb}/^{235}\text{U}$ (y-axis). The Concordia curve is the locus of points for which both U-Pb decay systems give the same age. A sample that has remained a closed system plots on the curve (concordant age); samples that have lost lead plot below it along a straight line, the Discordia, whose upper and lower intercepts date the crystallisation and the disturbance event respectively.
3. Magnetostratigraphy: The branch of stratigraphy that uses the record of reversals of the Earth's magnetic field preserved in rocks (remanent magnetisation). Sequences of normal and reversed polarity zones are matched against the **Geomagnetic Polarity Time Scale (GPTS)** to date and correlate strata.
4. Hiatus: The interval of geological time not represented by any rock at an unconformity or depositional break — i.e., the time gap corresponding to non-deposition and/or erosion between two successive strata.

SOLUTION Exercise 4 — Direct Calculation: Radiometric Dating

Given: $N/N_0 = 12.5\% = 0.125$; half-life $T_{1/2} = 4.468 \times 10^9$ years (^{238}U decay).

Decay equation:

$$\frac{N}{N_0} = e^{-\lambda t}, \quad \lambda = \frac{\ln 2}{T_{1/2}}.$$

Step 1 — recognise the number of half-lives:

$$0.125 = \frac{1}{8} = \left(\frac{1}{2}\right)^3$$

so exactly three half-lives have elapsed.

Step 2 — compute the age:

$$t = 3 \times T_{1/2} = 3 \times 4.468 \times 10^9 = 1.3404 \times 10^{10} \text{ years.}$$

Check with the logarithmic formula:

$$\begin{aligned} t &= \frac{1}{\lambda} \ln\left(\frac{N_0}{N}\right) = \frac{T_{1/2}}{\ln 2} \ln\left(\frac{1}{0.125}\right) \\ &= \frac{4.468 \times 10^9}{0.6931} \times \ln 8 = \frac{4.468 \times 10^9}{0.6931} \times 2.0794 \\ &\approx 1.34 \times 10^{10} \text{ years.} \end{aligned}$$

$$t \approx 13.4 \text{ Ga (13.4 billion years)}$$

WARNING Critical discussion — do not skip this in the exam!

This age (≈ 13.4 Ga) is older than the Solar System (≈ 4.56 Ga) and nearly the age of the Universe — it is geologically impossible for a terrestrial zircon. The closed-system assumption must therefore have failed (e.g., the measured uranium content is wrong, uranium was lost, or the "12.5%" figure is unrealistic for this isotope system). In an exam, always comment on the plausibility of a numerical result: full marks require both the correct calculation and the critical remark that such a zircon cannot exist, showing that you understand the limits of the method.

SOLUTION Exercise 5 — Relative Dating from a Cross-Section

Chronological sequence (oldest → youngest):

Order	Event	Principle used
1	Deposition of S1, then S2, S3, S4	Superposition (oldest at bottom)
2	Folding of S1–S4	Folds deform already-deposited layers; layers must pre-date deformation
3	Intrusion of granite G	Cross-cutting relationships: G cuts the folded strata (and baked/contact-metamorphosed margin confirms intrusion after folding)
4	Emplacement of dolerite dyke D	Cross-cutting relationships: D cuts across S1–S4 and G, so D is younger than both
5	Faulting F	Cross-cutting relationships: F offsets S1–S4, G and D
6	Erosion (planation surface)	The truncated tops of S4, G, D and F form a flat erosion surface (unconformity)
7	Deposition of flat-lying S5	Superposition + unconformity: S5 rests on the erosion surface and is not offset by F, confirming it post-dates the fault

Key reasoning points:

- G is younger than the folding because it cross-cuts the folded layers; its margins are straight and undeformed.
- D is younger than G because the dyke cuts the granite.
- F is younger than D because the fault displaces the dyke.
- S5 is younger than F because the fault does not continue into S5 — the fault is sealed by S5.
- The erosion surface between the faulted/tilted pile and horizontal S5 is an **angular unconformity** (over the sediments) and a **nonconformity** (where S5 rests on granite).

WARNING Common mistake

Many students place the fault before the dyke or forget the erosion event. Rule of thumb: a feature that is cut is older than the feature that cuts it; a feature that seals (covers) a structure is younger than that structure.

SOLUTION Exercise 6 — Biostratigraphic Correlation

(a) Age range of each assemblage. An assemblage can only date from an interval during which all its species coexisted — i.e., the overlap of their ranges (concurrent range zone):

- Assemblage 1 (A + C): A ranges 145–130 Ma; C ranges 140–120 Ma. Overlap = 140–130 Ma.
- Assemblage 2 (B + D): B ranges 135–110 Ma; D ranges 125–90 Ma. Overlap = 125–110 Ma.
- Assemblage 3 (C + E): C ranges 140–120 Ma; E ranges 115–85 Ma. Overlap = 120–115 Ma.

(b) Index fossil for the Early Cretaceous (≈ 145 –100 Ma): Species A is the best index fossil: its total range (145–130 Ma, i.e., 15 Ma) is the shortest of the species present in the Early Cretaceous part of the succession, and it falls entirely within the Early Cretaceous. Species C (20 Ma range) is less precise; B and D extend into the Late Cretaceous; E is essentially Late Cretaceous. A good index fossil = short range + wide distribution + abundance + easy identification.


(c) Effect of the ash-bed age (112 ± 2 Ma) on Assemblage 2: The biostratigraphic bracket for Assemblage 2 is 125–110 Ma. The radiometric age of 112 ± 2 Ma (i.e., 110–114 Ma) lies within this bracket and is consistent with it. It refines the correlation by:

- pinning the assemblage to the narrower interval 114–110 Ma (intersection of 125–110 Ma with 110–114 Ma);
- providing an absolute (numerical) calibration that can be transferred to other sections where the same assemblage occurs but no ash bed exists;
- serving as an isochronous marker horizon for basin-wide correlation of the Rio del Rey succession.

This illustrates the power of integrating biostratigraphy (relative) with radiometric dating (absolute).

SOLUTION Exercise 7 — Concordia–Discordia Interpretation

(a) Sketch of the Concordia diagram:



Concordia diagram: the three discordant zircon analyses define a Discordia line intersecting the Concordia curve at two points.

(b) Geological interpretation:


- Upper intercept = $2050 \pm 20 \text{ Ma}$: the original crystallisation age of the zircons — i.e., the emplacement/metamorphic crystallisation of the granitic protolith of the gneiss during the Eburnean (Palaeoproterozoic) orogeny that built much of the Congo Craton in southern Cameroon.
- Lower intercept = $550 \pm 30 \text{ Ma}$: the age of a later disturbance that caused lead loss — here the Pan-African orogeny ($\approx 600\text{--}500 \text{ Ma}$), which thermally and tectonically re-worked the craton margins and opened the zircon U–Pb system.

(c) Why zircons yield discordant ages (two mechanisms):

1. Diffusive Pb loss during a thermal event: reheating (metamorphism, nearby intrusion) allows radiogenic lead to diffuse out of the crystal lattice, while uranium is retained; the measured Pb/U ratios fall, and the point moves down along the Discordia.
2. Metamictisation and leaching: radiation damage from U decay destroys the crystal lattice (metamict zircon); fluids then percolate and leach radiogenic Pb. (Also acceptable: inheritance of older zircon cores, or recent Pb loss by weathering pulling points toward the origin.)

SOLUTION Exercise 8 — Unconformities: Identification and Field Evidence

Schematic stratigraphic column (bottom → top):



Stratigraphic column showing the four types of unconformity.

Field criteria (two per type):

Type	Criterion 1	Criterion 2
Nonconformity	Sedimentary rocks rest directly on eroded crystalline (igneous/metamorphic) basement	Basal conglomerate containing pebbles of the underlying gneiss; weathered (saprolitic) top of basement
Angular unconformity	Marked discordance of dip between truncated tilted/folded strata below and horizontal strata above	Truncation of beds, dykes and folds at the erosion surface; basal conglomerate above the surface
Disconformity	Erosion surface (irregular, channelled) between parallel strata	Palaeosol, root traces, pebble lag or karstic surface at the contact; fossil gap
Paraconformity	Strata perfectly parallel with no visible erosion surface	Detectable only by a biostratigraphic gap (missing fossil zones) between the two units

WARNING Common mistake

Do not confuse disconformity (visible erosion surface between parallel beds) with paraconformity (no visible surface; gap proved only by fossils). In the field, the palaeosol is your strongest evidence for a disconformity.

SOLUTION Exercise 9 — Integrated Relative and Absolute Dating (20 marks)

(a) Relative chronological sequence [8 marks — 1 mark per correctly placed event]:

1. Formation of the Basement Gneiss (Bg) — oldest unit (host to everything).
2. Erosion of the gneiss to form the **nonconformity** surface.
3. Deposition of the Cretaceous Sandstones (Ks) on the eroded basement (superposition).
4. Tilting/folding of Ks (strata must exist before being deformed).
5. Intrusion of the Granite (Gr) — cross-cuts Bg and the tilted Ks (cross-cutting relationships).
6. Emplacement of the Dolerite Dyke (Dd) — cuts Bg, Ks and Gr (cross-cutting).
7. Faulting (F) — offsets Bg, Ks, Gr and Dd.

8. Erosion — planation surface truncating F, Dd, Gr and Ks.

9. Deposition of the horizontal Tertiary Sands (Ts) — seals the fault and the erosion surface (youngest event).

Examiner expectation: any logically consistent order respecting (i) Ks before tilting, (ii) Gr after tilting, (iii) Dd after Gr, (iv) F after Dd, (v) Ts last, earns full credit. State the principle for at least the key steps.

(b) Minimum absolute age of the tilting [4 marks]: The granite (U–Pb zircon age 88.5 ± 0.5 Ma) intrudes the already tilted Cretaceous sandstones. Therefore the tilting is older than the granite crystallisation:

$$t_{\text{tilting}} > 88.5 \text{ Ma.}$$

Considering the analytical uncertainty, the tilting must be older than 89 Ma (i.e., older than $88.5 + 0.5$ Ma). Reasoning [2 marks]: cross-cutting relationships — an intrusion is younger than the structures it cuts; the zircon crystallisation age dates the granite's solidification, so the deformation it cross-cuts must pre-date it. Note: the maximum age of tilting is given by the age of the youngest tilted sandstone (Cretaceous).

(c) Reliability of the K–Ar dyke age vs the U–Pb granite age [4 marks]:

- Closure temperatures: U–Pb in zircon closes at very high temperature ($> 900^\circ\text{C}$), so the zircon age dates crystallisation faithfully and resists later reheating. K–Ar in whole-rock closes at much lower temperature ($\approx 150^\circ\text{C}$ to 350°C depending on mineral), and argon is an inert gas that diffuses out easily.
- Consequences: the dyke was emplaced close to a hot granite; contact reheating and later burial could have caused partial Ar loss, making the K–Ar age (42 Ma) younger than the true emplacement age. Whole-rock analyses also risk excess argon or alteration (devitrification, weathering of groundmass).
- Conclusion: the K–Ar age is a minimum and less reliable constraint; it may date cooling or a resetting event rather than emplacement. The U–Pb zircon age is far more robust. A better method for the dyke would be $^{40}\text{Ar}/^{39}\text{Ar}$ step-heating on fresh plagioclase or U–Pb on baddeleyite/zircon.

Mark scheme: 1 mark closure-temperature contrast; 1 mark Ar mobility/loss; 1 mark geological consequence (age too young / reset); 1 mark reasoned conclusion or better alternative.

(d) Field evidence for the nonconformity Bg/Ks [4 marks — any 4×1]:

- Cretaceous sedimentary rocks resting directly on eroded crystalline gneiss.
- Basal conglomerate/breccia at the base of Ks containing angular pebbles of the underlying gneiss.
- Weathered, saprolitic or palaeosol horizon at the top of the gneiss (ancient land surface).
- Truncation of foliation, veins and structures of the gneiss at the contact.

- Absence of metamorphism in the sandstone above (contact is depositional, not intrusive) and no chilled margin in the gneiss.
- Marked age gap (hiatus) between the two units.

SOLUTION Exercise 10 — Essay: Magnetostratigraphy and Chemostratigraphy in Cameroon (25 marks)

Indicative mark scheme: definitions and principles [5]; GPTS construction and use [5]; chemostratigraphic proxies [5]; strengths/limitations applied to the three basins [6]; integrated case study [4]. Quality of structure, terminology and labelled diagrams may be rewarded within these bands.

Model answer (skeleton to be developed in full prose):

1. Definitions and principles [5]. Magnetostratigraphy correlates rocks using the record of reversals of the geomagnetic field locked into sediments and lavas as detrital or thermal remanent magnetisation; the principle is that polarity reversals are globally synchronous and instantaneous on geological timescales. Chemostratigraphy correlates using secular variations in the chemical and isotopic composition of seawater recorded in marine sediments; the principle is that the ocean is well mixed, so isotopic shifts (e.g., in $\delta^{13}\text{C}$) are recorded simultaneously in marine carbonates worldwide.

2. The GPTS [5]. The Geomagnetic Polarity Time Scale is built by (i) measuring the polarity of radiometrically dated lava flows worldwide, (ii) stacking magnetostratigraphic sections tied to biostratigraphy, and (iii) reading the marine magnetic anomaly stripes of ocean crust (sea-floor spreading provides a continuous tape-recorder of reversals). The result is a calibrated sequence of chrons (normal/reversed). To use it: sample an oriented section, perform stepwise demagnetisation to isolate the characteristic remanence, establish the local polarity zonation, then pattern-match the succession of magnetozones to the GPTS, anchored by biostratigraphic or radiometric tie-points. Each reversal boundary is an isochronous correlation line.

3. Chemostratigraphic proxies for Cretaceous marine sediments [5].

- $\delta^{13}\text{C}$ (carbonate and organic carbon): positive excursions mark Oceanic Anoxic Events (e.g., OAE1a in the Aptian, OAE2 at the Cenomanian–Turonian boundary) — excellent regional markers in the Douala and Rio del Rey black shales.
- $\delta^{18}\text{O}$: palaeotemperature/ice-volume proxy; useful for climatic correlation but sensitive to diagenetic resetting.
- $^{87}\text{Sr}/^{86}\text{Sr}$: seawater Sr ratio evolves smoothly through time; gives numerical ages for well-preserved low-Mg calcite (e.g., belemnites, oysters), provided diagenetic alteration is screened out.

4. Strengths and limitations in the Cameroon Atlantic basins [6].


	Strengths	Limitations
Magnetostratigraphy	Global, isochronous markers; works in barren or non-marine (continental) beds where fossils fail — useful for the Aptian red beds of Douala/Kribi-Campo	Tropical deep weathering and lateritisation destroy remanence; Cretaceous Normal Superchron (≈ 121 – 83 Ma) offers no reversals for much of the mid-Cretaceous; needs oriented cores
Chemostratigraphy	High-resolution; correlates where facies change makes litho- and biostratigraphy ambiguous; OAE excursions are strong markers in the organic-rich shales	Diagenesis (recrystallisation, meteoric fluids) resets $\delta^{18}\text{O}$ and Sr; local restriction of the young Atlantic basins can decouple $\delta^{13}\text{C}$ from the global signal; needs unaltered material

5. Integrated case study [4] (hypothetical but realistic). In the Rio del Rey Basin, an organic-rich black shale was assigned to the Turonian on *Inoceramus* evidence, while an apparently equivalent shale in the Douala Basin was dated as Cenomanian on ammonites — a correlation conflict. An integrated study resolved it: (i) the $\delta^{13}\text{C}$ positive excursion of OAE2 was identified in both shales, proving they record the same global event at the Cenomanian–Turonian boundary (≈ 93.9 Ma); (ii) a bentonite within the Douala shale gave a U–Pb zircon age of 93.5 Ma, calibrating the excursion; (iii) magnetostratigraphy placed both sections just above the end of the Cretaceous Normal Superchron, consistent with the boundary age. The apparent conflict came from diachronous first appearances of the index fossils; the chemostratigraphic and radiometric tie-points provided the correct isochronous framework.

Examiner expectations: explicit definitions; the global synchronicity argument for both methods; at least three correctly used proxies; balanced evaluation (not a catalogue of advantages only); a coherent integrated example; correct geological vocabulary throughout.

SOLUTION Exercise 11 — Multi-Section Correlation and Sequence Stratigraphy (20 marks)

(a) Correlation panel [6 marks]. Fence diagram at $1\text{ cm} = 100\text{ m}$ (so $1000\text{ m} = 10\text{ cm}$):



Correlation panel (fence diagram) of the three boreholes. Dashed lines: correlated unit boundaries; U1 = Base Tertiary unconformity.

Mark scheme: correct vertical scale and depth axis [1]; correct lithologies per borehole [2]; U1 correctly drawn and correlated between BH-1 and BH-2 and its seismic significance noted (it passes within the BH-3 marl succession as a conformity/condensed interval offshore) [1]; basement correlation [1]; ash-bed marker shown in BH-3 [1].

(b) Systems tracts in BH-3 (450–1000 m) [6 marks]:

- Lowstand Systems Tract (LST) — 600–800 m (lower black shales / basal unit): following the relative sea-level fall recorded onshore by the red beds and conglomerates of BH-1/BH-2 (fluvial, lowstand deposits), the offshore equivalent is the basal black shale; the coarse clastics onshore = lowstand wedge. [2 marks]
- Transgressive Systems Tract (TST) — $\approx$ 550–600 m and the marls: the Aptian–Albian eustatic transgression drowned the margin: onshore sands/lignites (BH-2, 200–450 m equivalent) pass offshore into marine marls with *Orbitolina* (Aptian) — deepening-upward, retrogradational stacking; the black shales with TOC 4% record maximum restriction/anoxia near the maximum flooding surface (condensed section). [2 marks]
- Highstand Systems Tract (HST) — 450–550 m (upper marls): Late Cretaceous highstand: normal marine marls prograding over the condensed black shales; the ash bed at 550 m (93.5 Ma, Cenomanian–Turonian boundary) sits near the TST/HST transition — consistent with the global maximum flooding near that boundary. [2 marks]

Justification must cite: lithology (shale = deep/anoxic = flooding; marl = open marine; conglomerate/red beds = continental lowstand) and fossils (*Orbitolina* = shallow-marine Aptian; *Inoceramus* = Turonian–Coniacian open marine).

(c) Sedimentation rate of the black shale (800–1000 m) [4 marks]: The black shale contains *Inoceramus* (Turonian–Coniacian, ≈ 93.9 – 86.3 Ma). Using the ash age 93.5 Ma at 550 m as a top anchor for the overlying marls and the biostratigraphic range for the black shale interval:

- Thickness of black shale interval (800–1000 m): $1000 - 800 = 200$ m.
- Duration (Turonian–Coniacian): $\approx 93.9 - 86.3 = 7.6$ Ma.
- Rate = $\frac{200 \text{ m}}{7.6 \text{ Ma}} \approx 26.3 \text{ m/Ma}$ (i.e., $\approx 26 \text{ mm/ka}$, uncompacted).


Accept any coherent calculation (e.g., using 93.5 Ma for the top and 86 Ma for the base of the unit gives $\approx 27 \text{ m/Ma}$). Marks: correct thickness [1]; correct time interval justified from fossil range/ash age [2]; correct arithmetic with units [1]. Note the result is an average, uncompacted rate.

(d) Hydrocarbon potential [4 marks — 1 per element]:

- Source rock: the BH-3 black shales (TOC 4%, Turonian–Coniacian) — an excellent oil-prone source rock, equivalent to the productive Cretaceous source intervals of the West African Atlantic margin.
- Reservoir: the yellow sands of BH-1/BH-2 (and the basal conglomerates/red-bed sandstones) — porous, laterally continuous nearshore/fluvial sandstones.
- Seal: the grey marine clays and marls (top unit in all boreholes, and the marls of BH-3) — impermeable cap rocks; the unconformity U1 itself can act as a seal where clays overlie truncated sands.
- Trap: stratigraphic pinch-out traps where the reservoir sands of BH-2 pass laterally into offshore marls (BH-3); unconformity (truncation) traps beneath U1; possible structural traps along growth faults typical of the Douala Basin.

Examiner expectation: each element must be tied to a specific named unit in a specific borehole, not generic statements.

15 SUMMARY SHEET



Mind map of the Stratigraphy chapter (Upper Sixth GCE).

FICHE BILAN L'essentiel à connaître pour l'examen

Key Definitions

- **Stratigraphy:** The branch of geology concerned with the study of rock layers (strata), their geometry, distribution, and chronological relationships in time and space.
- **Principle of Superposition:** In an undeformed sequence of sedimentary or volcanic rocks, the oldest layers are at the bottom and the youngest at the top.
- **Principle of Original Horizontality:** Sedimentary layers are originally deposited horizontally under gravity.
- **Principle of Lateral Continuity:** Layers extend laterally in all directions until they thin out, grade into another facies, or meet a barrier.
- **Principle of Cross-Cutting Relationships:** A geological feature (fault, intrusion, erosion surface) that cuts across another is younger than the feature it cuts.
- **Principle of Inclusions:** Fragments (xenoliths, clasts) included in a host rock are older than the host rock.
- **Principle of Faunal Succession:** Fossil assemblages succeed one another in a definite, recognisable order, allowing relative dating and correlation.

- **Unconformity:** A surface representing a significant gap (hiatus) in the geological record due to erosion or non-deposition; types: angular unconformity, disconformity, nonconformity, paraconformity.
- **Correlation:** The process of demonstrating the equivalence in age or time of rock units in different geographical areas.
- **Lithostratigraphic Unit:** A body of rock defined by its lithology (formation, member, group).
- **Biostratigraphic Unit:** A body of rock defined by its fossil content (biozone).
- **Chronostratigraphic Unit:** A body of rock formed during a specific interval of geological time (system, series, stage).

Laws, Formulas & Theorems to Know

- Steno's Laws (1669): Superposition, Original Horizontality, Lateral Continuity — examinable as the foundation of relative dating.
- Hutton's Cross-Cutting Relationships (1795) and Lyell's Inclusions: Key for deciphering intrusive and tectonic events.
- Smith's Principle of Faunal Succession (1790s): Basis of biostratigraphy and the geological column.
- Radiometric Age Equation: $t = \frac{1}{\lambda} \ln \left(1 + \frac{D}{P} \right)$, where λ = decay constant, D = daughter isotope atoms, P = parent isotope atoms remaining.
- Half-life Relation: $t_{1/2} = \frac{\ln 2}{\lambda}$. Common systems: $^{238}\text{U} \rightarrow ^{206}\text{Pb}$ ($t_{1/2} = 4.47 \text{ Ga}$), $^{235}\text{U} \rightarrow ^{207}\text{Pb}$ ($t_{1/2} = 0.704 \text{ Ga}$), $^{40}\text{K} \rightarrow ^{40}\text{Ar}$ ($t_{1/2} = 1.25 \text{ Ga}$), $^{87}\text{Rb} \rightarrow ^{87}\text{Sr}$ ($t_{1/2} = 48.8 \text{ Ga}$), $^{14}\text{C} \rightarrow ^{14}\text{N}$ ($t_{1/2} = 5730 \text{ yr}$).
- Geologic Time Scale (ICS 2024): Know the major boundaries: Precambrian/Cambrian (541 Ma), Cambrian/Ordovician (485 Ma), Permian/Triassic (252 Ma), Triassic/Jurassic (201 Ma), Cretaceous/Paleogene (66 Ma), Neogene/Quaternary (2.58 Ma). Be able to place Cameroon events: CVL initiation (66 Ma), Mount Cameroon recent activity (<1 Ma), Pan-African orogeny (600–500 Ma).

Methods

1. Relative Dating: Apply stratigraphic principles to a cross-section or block diagram to produce a sequence of events (oldest → youngest). Always state the principle used for each step.
2. Absolute Dating: Choose appropriate isotopic system based on rock type and age range (e.g., U–Pb on zircon for Precambrian basement, K–Ar/Ar–Ar on volcanic rocks for CVL, ^{14}C for Holocene sediments). Correct for initial daughter, contamination, and closed-system assumption.

3. **Stratigraphic Logging:** Measure and describe a section: lithology, thickness, sedimentary structures, fossil content, contact types. Draw a graphic log with standard symbols.
4. **Unconformity Recognition:** Identify angular discordance (tilted beds below, flat above), erosional relief, palaeosols, basal conglomerates with clasts from underlying unit.
5. **Correlation Techniques:**
 - **Lithostratigraphy:** Match distinctive rock units (marker beds).
 - **Biostratigraphy:** Use index fossils (wide geographic range, short time range).
 - **Chronostratigraphy:** Tie to global standard stages (GSSPs).
 - **Magnetostratigraphy:** Match magnetic polarity reversal pattern to GPTS.
 - **Chemostratigraphy:** Correlate isotopic excursions (e.g., $\delta^{13}\text{C}$).
6. **Cross-Section Construction:** Use topographic profile, dip/strike data, and stratigraphic thicknesses. Project contacts vertically or along dip direction. Show vertical exaggeration if used.

Common Mistakes

- Confusing relative (order) and absolute (numerical) dating; mixing up principles (e.g., applying superposition to overturned folds without recognising overturning via younging indicators).
- Treating every contact as an unconformity; a conformable contact shows continuous deposition.
- Misidentifying a sill as a lava flow (use cross-cutting: sill intrudes both above and below; flow only underlies).
- Correlating solely on lithology without fossil or radiometric control — lateral facies changes are common in the Benue Trough.
- Radiometric errors: using wrong decay constant, forgetting to convert half-life to λ , ignoring initial daughter isotope (use isochron method), or dating a metamorphic event instead of crystallisation.
- Not knowing the current International Chronostratigraphic Chart; the GCE expects the latest ICS version.
- In sequencing questions, omitting events (e.g., erosion before an unconformity, tilting before angular unconformity).

GCE Exam Tips

- **Question Types:** Expect (a) block diagram / cross-section interpretation with sequencing (10–15 marks), (b) radiometric calculation (5–8 marks), (c) correlation of

two or more columns using fossils/lithology (8–10 marks), (d) description of unconformity types with diagrams (5 marks), (e) essay on stratigraphic principles or dating methods (10–15 marks).

- **Show All Working:** In age calculations, write the formula, substitute values with units, give answer in Ma (million years) or Ga. Use $\lambda = \frac{\ln 2}{t_{1/2}}$.
- **Terminology Precision:** Distinguish angular unconformity, disconformity, nonconformity, paraconformity. Use formation, member, group correctly.
- **Cameroon Context:** Be prepared to apply principles to the Cameroon Volcanic Line (e.g., date a basalt flow from Mount Cameroon using K–Ar), the Congo Craton (Pan-African granites dated by U–Pb on zircon), or the Benue Trough (Cretaceous marine transgressions correlated by ammonites).
- **Diagrams:** Draw large, labelled diagrams (cross-sections, stratigraphic columns, fossil ranges). Use a ruler. Indicate younging direction.
- **Integration Questions:** Combine principles, dating, and correlation to write a geological history. Structure: 1. Oldest basement, 2. Deformation/metamorphism, 3. Unconformity, 4. Sedimentary cover with fossils, 5. Intrusive/volcanic events, 6. Recent erosion.
- **Time Management:** Allocate 1 minute per mark. For a 15–mark sequencing question, spend 15 minutes: 5 min analysis, 5 min writing sequence with principles, 5 min neat diagram.



Signed • OnBuch+

ONBUCH+ TEACHING TEAM

FOLLOWS THE OFFICIAL MINESEC SYLLABUS

OnBuch+